


# Reversing Channel Incision and Enhancing Steelhead Habitat in Tepee Cr

Will Conley, Hydrologist  
Yakama Nation Fisheries Program

Salmon Habitat Project Conference  
Shelton, WA April 15, 2009




# Outline

- Background
- Design
- Implementation
- Results
- Insights
  - Bed Material
  - Average Gradient
  - Materials Salvage
- Cost / Acknowledgements
- Special Features...

# Location

- Klickitat River tributary
- Klickitat Lead Entity
- south-central Washington State
- east-slope of Cascade Mountains
- 22 miles due east of Mt. Adams
- within Yakama Nation Reservation



# Setting

- Forested watershed (3000-4000')
- Basal geology is Grande Ronde basalt (CRB group)
- Hard parent materials and low to moderate relief = very limited bedload supply
- Contributing drainage area of 8.4 square-miles
- Project reach is at 2965' elevation
- Cohesive soils / banks (Aquandic Haploxeralfs)
- Prevailing texture is clay loam

# Fisheries Significance

- Habitat for Middle Columbia River steelhead (ESA-“threatened”)
- Tepee Creek accounts, on average, for 6.3% of the total observed spawning in the Klickitat subbasin
- Extensive reaches are incised and intermittent. Spawning habitat is marginal and rearing conditions are poor and limiting
- Reach is located within one of the top priority areas of the Klickitat Salmon Recovery Strategy

# Problem

- Project reach dried-up in 4 out of 5 years preceding project implementation
- Limited rearing and spawning habitat
- Stranding issues
- Field indicators and hydraulic modeling indicated that project reach was incised 3 to 4 feet within its historic planform

# Goals

- Restore water table / floodplain storage
- Enhance in-channel habitat conditions for rearing steelhead
- Restore suitability of valley bottom for medicinal and traditional food plants

# Project Team

- Will Conley – YN Fisheries Program
  - Project Management
  - Design
  - Construction Oversight
- Mike McAlister, PE - Interfluve, Inc
  - Design
  - Construction Oversight
- Mike Brunfelt - Interfluve, Inc
  - Design
  - Construction Oversight



# Hydrology

- Ungaged (pre-project)
- Peak-flow hydrology is driven by rain-on-snow events
- Base flow (for years when it exists) = 10-12 gpm
  - $Q_2 : Q_{\text{base}} \sim 1 : 6,200$

Recurrence Interval (yrs)	Region 6 USGS Equation Results	
	Discharge (cfs) <sup>a</sup>	Discharge (cfs) <sup>b</sup>
2	112.8	165.2
10	331.4	414.2
25	496.4	585.1
50	643.8	730.5
100	816.9	895.7

<sup>a</sup> using 17.4" MAP correlated with HEC-HMS model

<sup>b</sup> using 27.6" MAP from nearby RAWS station

# Design

## Conceptual:

- Import gravels to raise the bed elevation to restore inundation frequency to the pre-disturbance floodplain
- Build “immature” (higher W/D) cross-section and allow stream to adjust


## Parameters:

Design dimensions were modeled iteratively in HEC-RAS


- average slope (0.0093 ft/ft)
- bankfull area = 19.7 ft<sup>2</sup>
- bankfull top width = 18.4 ft

# 30% drawings for fit-in-the-field

Plan View



Profile View



# Sequencing

Implemented over two field seasons:

## ■ Fall 2006

- All riffles roughed-in
- Downstream grade control completed
- All LWD and rock material delivered to site
- Roughly half of the LWD jams completed
- Temporary erosion control measures implemented

■ Maximum discharge over winter 2006/2007 = 143 cfs

## ■ July 2007

- Final grading on pools and riffles
- LWD jams and floodplain LWD completed
- Revegetation and weed control completed
- Fence construction completed
- Access routes rehabilitated

# Implementation

- A 140' coarsened riffle (0.03 ft/ft) was constructed at the downstream end of the reach for grade-control
- Ninety-five feet of new channel constructed
- Reconnected 135' of historic channel
- Imported gravel to raise bed elevation (~3') and reconstruct pool/riffle sequences along 1850'
- Overall reach lengthened to 1990'
- 28 LWD jams constructed along channel margins
- Numerous floodplain LWD placements constructed
- Removed 2 culverts and related fill from an abandoned cross-valley road alignment

# Downstream Grade Control



140' roughened channel subreach (0.03 ft/ft) to transition to untreated downstream reach

# Typical Riffle Fill: Before & After

8/25/04



STA 6+35

Elevation of constructed  
bank toe / channel invert

5/19/08



*Gradation Table  
Imported Gravel*

Percent Smaller Than	Diameter (in)
100	4.0
84	1.6
50	0.7
16	0.2

$$D_{84} / D_{100} = 0.4$$

$$D_{84} / D_{16} = 8.0$$

$$D_{84} / D_{50} = 2.3$$

# Typical Riffle Fill and LWD: Under Construction



STA 13+40  
Under construction  
10/20/06

8/25/04



## STA 20+90

(IXL Road Crossing – upstream end of project reach)

Culvert outlets backwatered to improve fish passage



4/5/07


# Results

- Flow Duration: perennial pools maintained both years since construction
- Groundwater: 2 - 4' increase in summer water table
- High Flow Access: at bankfull or lower flows to four side channels totaling 835 lineal feet
- Pools: increased from 15 to 23 (65%); greater depths & cover
- Wetlands: ~3100 ft<sup>2</sup> of emergent wetland created
- Riparian Vegetation: Rapid recovery, particularly of salvaged plant materials
- Spawning: Two steelhead redds observed
- Rearing: 2x – 3x increase in juvenile *O. mykiss* abundance
- Macroinvertebrates: Rapid colonization by multiple species of caddisflies and mayflies


# Groundwater

## Post-project:

- 2' – 4' increase in summer/fall water table
- 1.8' increase in the average annual water table
- Less variability between and amongst wells



# Residual Pool Depths



Note: because some pools were under-filled during construction, the median value for residual depths under equilibrium conditions is anticipated to be 2.0' - 2.49'

# Steelhead Spawning



**One of two steelhead redds observed in project reach in 2007**

# Bed Material: Pre-Project



colluvial armor; clasts  $>40\text{mm}$   
mostly sub-angular



bi-modal distribution;  
very high fines content

# Bed Material: Sourcing

## Crushed vs. Alluvium:

- Which is more like the bed material in the stream?
  - Bed material in Tepee Creek is mostly sub-angular (<40 mm is somewhat sub-rounded)
  - Commercially available alluvium is rounded to well-rounded
- Consider:
  - Ethics of becoming party to floodplain gravel mining
  - Burning additional fossil fuels to haul
  - Project Goals: NOT trying to improve spawning habitat (rearing-limited)
- In the case of Tepee Creek, the costs of hauling alluvium from the Yakima R. floodplain were unjustified

# Bed Material: Design

- Size distribution should balance:
  - stability
  - porosity

Percent Smaller Than	Diameter (in)
100	4.0
84	1.6
50	0.7
16	0.2

$$D_{84} / D_{100} = 0.4$$

$$D_{84} / D_{16} = 8.0$$

$$D_{84} / D_{50} = 2.3$$

- Consider:
  - Ambient passage conditions
  - Temperature vs dissolved oxygen trade-offs
    - D.O. recovers faster than temperature
    - Erred on side of too porous, hence lower potential for adverse temperature and stability effects

# Bed Material: Delivery

- End-dump directly to stream or stockpile on-site?
  - f (cost, access, disturbance tolerance)
- Sorting in box of truck during hauling
  - Haul gradations separately and mix on site if necessary
- Inspect material before and during hauling
  - Spend as much time as necessary at source to get distribution right

# Bed Material: Observations

- Soil plugs in subgrade of riffle crests:
  - Do increase residual pool depths
  - Are as-yet untested in live-bed conditions
- Riffle porosity inversely correlated with:
  - Amount of tracking by equipment
  - Ambient moisture conditions at time of construction
- Fish passage through constructed riffles
  - Is comparable to ambient conditions
- Macroinvertebrate response very positive
- Steelhead and resident trout spawning observed
- Dissolved Oxygen
  - Appears to be an issue where known groundwater inputs occur

# Flow Through Riffles

Threshold for wetting



STA 13+20\*

10/30/08

Surface flow at control

~ 0.56 cfs\*\*

11/4/08

Top-to-bottom surface flow

~ 1.90 cfs\*\*

\* STA 13+20 is one of four controls that has a “plug” of native soil in the subgrade

\*\* adult passage and spawning throughout project is comparable to untreated reaches  
(median spawning flow = 12.6 cfs)


# Flow Through Riffles (cont'd)

$Q < 0.5$  cfs



- No subgrade “plug” in either control
- Both stations have comparable cross-sectional fill areas
- STA 2+70 constructed under wetter ambient conditions than 15+80 (i.e. more intrusion of native fines into fill during construction)

# The Thing About Average Gradient...




- Medium to high flows: OK because energy line and bed slope are more or less parallel
- Low flows: energy line is stepped which (in the absence of further treatment) causes headcutting of riffle toes

# Implementing Average Gradient

Basically three approaches:

- Extend riffle downstream into pool  
and / or
- Transition slope into head of pool  
and / or
- Harden / armor riffle toe
  - coarsen bed material
  - add a log drop (only done in one place)



# Native Material Salvage

Expensive (adds equipment time)

Vegetation: sod and shrubs

- VERY effective

Gravels

- Mostly window-dressing (in Tepee Creek)

# Sod salvage and gravel filling



3/20/03



STA 14+80

5/19/08



Salvaged sod and shrubs used along bank

# Ineffective areas intentionally left unfilled

- encourages recruitment of fines
- minimizes suitability for weeds
- hastens colonization by desired hydrophytes

**STA 6+70**

8/7/07

# Weeds

- Two bull thistle (*Cirsium vulgare*) individuals observed pre-project
- Thousands of bull thistle rosettes and scores of stalks in first growing season



- Intensive manual pulling in first season (August 2007)
- Virtually no subsequent control required

# How Much to “Finish”?

- Build-out pools or leave under-filled?
- Rough-in riffles or finely-grade?
- Trick-out your LWD jams or get primary members placed and secured?
- It's all a matter of \$\$\$\$\$

# Cost

## Materials (delivered; 40.9%)

- rock	\$100,013
- LWD	\$ 40,500
- revegetation* and erosion control	\$ 5,087
- cable, clamps, and anchors	\$ 3,354
- fencing materials	\$ 1,420

Construction\*\* (32.7%) \$120,334

Planning, Design, and Oversight (26.4%) \$ 97,226

**TOTAL (~\$185/l.f.) \$367,934**

\*Salvage and placement of sod mats and shrubs is incorporated under “construction”

\*\* hourly contract

# Acknowledgements

- WA State Salmon Recovery Funding Board
  - materials and construction \$188,192
- Bonneville Power Administration (BPA)  
Klickitat Watershed Enhancement Project
  - materials, planning, design, & oversight \$139,092
- The Yakama Nation (in-kind)
  - LWD \$ 40,650
- Ralph Kiona, Watershed Technician priceless

# **A Few Nuggets of Restoration Wisdom...**

**(rolling with the punches)**

If your project is within a commercial timber sale boundary, it's a fair bet the loggers don't care as much about what the stream looks like as you.



Will Conley, Yakama Nation Fisheries

When the grazing permittee (in clear violation of his permit) throws a salt block out next to the creek you began restoring the previous fall, don't be afraid to take matters into your own hands....



(some people just don't get it)

...relocate salt block to the top of the ridge where it belongs...



...and when construction is done...



...put up a fence.

# Pay attention to signs

(keeping in mind that the sign, itself, is not always safe)



No matter how far out of harm's way you think  
you placed your saw,  
your excavator operator may prove you wrong



# For More Information

[http://www.ykfp.org/klickitat/KWEP\\_TepeeIXL.htm](http://www.ykfp.org/klickitat/KWEP_TepeeIXL.htm)

