

2021 Pre-Bid Site Visit Meeting Notes:

1. **Question: Will plants, mulch, fencing, ect need to be staged on sites for the planting contractor?** *100 CY of wood chips (supplied by the Owner), and some fencing material (supplied by the owner) will need to be hauled from the Twisp Log Yard and staged in select locations within the project area.*
2. **Question: The existing access driveway at Alder Creek. The riverbank near that point is steep and tall, and could become weak with loaded trucks driving and turning nearby. Can the access route be adjusted to avoid that hazard?** *Yes, the access route can cut across roughly 40' farther back from the river bank. Do not remove the pine or cottonwood trees. If there is a depression there, it may be temporarily filled but shall be returned to the original grade prior to final site demobilization.*
3. **Requirement:** *A culvert conveys Alder Creek under the road to the spoils repository area. It appears to be 2' diameter cmp and the road cover is roughly 3-4 feet. Protections shall be implemented to prevent damage to the culvert. Steel plates are suggested, but other methods may be proposed. This work does not have measurement and payment, and shall be incidental to Mobilization.*
4. **Question: Portions of the access road to the spoils repository area are paved. The plans call for gravel to be placed on the access road up to the gate, which includes the paved area. Can gravel be installed on top of the pavement?** *The pavement is in very poor condition and will not likely withstand the haul truck traffic. The pavement DOES NOT need to be repaired, and gravel can be placed where pavement was following construction. If any pieces of pavement remain intact, they will need to be removed and hauled out prior to gravelling.*
5. **Requirement:** *When metal debris such as car parts, metal roofing, old machinery is encountered within work areas, it shall be removed and hauled to a disposal site provided by the contractor. This work does not have measurement and payment, and shall be incidental to Mobilization.*