

Toppenish Creek 3-Way Levee Removal (Phase II)

Basis of Design Report

Appendix 7.1

Final (100%) Levee Removal and Channel Restoration Project
Plan Sheets and Specifications

May 2025

FINAL DESIGN PHASE
MAY, 2025

WASHINGTON

BELLINGHAM

SEATTLE

WENATCHEE

ELLENSBURG

YAKIMA

SPOKANE

IDAHO

OREGON

PORTLAND

LOCATION MAP

STATE OF WASHINGTON

Map of the Yakima Indian Reservation area. The map shows the Ahtanum Ridge, Ahtanum Rd, W Wapato Rd, Branch Rd, Wapato, Zillah, Toppenish, and the Yakima Valley Hwy. A black box highlights the area around White Swan, which is connected to the main map by a line.

PROJECT LOCATION

FORT SIMCOE RD

ETHIER RD

WESLEY RD

TO WHITE SWAN

SIGNAL PEAK RD

FLOW

TOPPENISH CREEK

North Arrow

SHEET LIST

- 1 COVER, LOCATION, AND SHEET LIST
2 CONSERVATION MEASURES (1 OF 3)
3 CONSERVATION MEASURES (2 OF 3)
4 CONSERVATION MEASURES (3 OF 3)
5 GENERAL NOTES AND ABBREVIATIONS
6 EROSION & SEDIMENT CONTROL
7 EROSION & SEDIMENT CONTROL
8 EXISTING CONDITIONS & SURVEY CONTROL
9 PROPOSED CONDITIONS & SHEET INDEX
10 PROPOSED CONDITIONS (1 OF 5)
11 PROPOSED CONDITIONS (2 OF 5)
12 PROPOSED CONDITIONS (3 OF 5)
13 PROPOSED CONDITIONS (4 OF 5)
14 PROPOSED CONDITIONS (5 OF 5)
15 PROPOSED HIGH FLOW SIDE CHANNEL 1-4 PROFILES
16 PROPOSED HIGH FLOW SIDE CHANNEL 5-6 & LEVEE REMOVAL B PROFILES
17 GRADING SECTIONS (1 OF 3)
18 GRADING SECTIONS (2 OF 3)
19 GRADING SECTIONS (3 OF 3)

- 20 TYPICAL DETAILS CHANNEL REMEANDER-PARTIAL PLUG
21 LARGE WOOD TYPICAL DETAILS- BANK BURIED WOOD
22 LARGE WOOD TYPICAL DETAILS- CHANNEL SPANNING
23 LARGE WOOD TYPICAL DETAILS- APEX STRUCTURE
24 TYPICAL DETAILS- FLOODPLAIN ROUGHNESS (1 OF 2)
25 TYPICAL DETAILS- FLOODPLAIN ROUGHNESS (2 OF 2)
26 LOG PILE TEST
27 REVEGETATION PLAN (1 OF 3)
28 REVEGETATION PLAN (2 OF 3)
29 REVEGETATION PLAN (3 OF 3)
30 SEED AND PLANT LISTS
31 TYPICAL DETAILS- REVEGETATION
32 SPECIFICATIONS (1 OF 3)
33 SPECIFICATIONS (2 OF 3)
34 SPECIFICATIONS (3 OF 3)

TO THE BEST OF MY PROFESSIONAL KNOWLEDGE,
JUDGMENT AND BELIEF, THIS DESIGN MEETS NRCS
STANDARDS



EXPIRES:	11/23/2025
----------	------------

IN-WATER WORK IS PERMITTED
JULY 1- OCTOBER 31

COORDINATES:

COORDINATES:
LATITUDE 46°19'11.97" N
LONGITUDE 120°46'38.12" W

SECTIONS 24, 35-36, TOWNSHIP 10N, RANGE 16E

WATERBODY: TOPPENISH CREEK
TRIBUTARY OF: YAKIMA RIVER

<u>BB</u> DRAWN	<u>PL, DM, JB, JB, NS</u> DESIGNED	<u>PL, JB, MB</u> CHECKED
<u>PL, DM, EA</u> APPROVED	<u>05/09/2025</u> DATE	<u>23-02-21</u> PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

COVER, LOCATION, AND SHEET LIST

SHEET

1 OF 34

NRCS CONSERVATION MEASURES: ADAPTED FROM BPA'S HIP GENERAL CONSERVATION MEASURES

THE ACTIVITIES COVERED UNDER THE HIP ARE INTENDED TO PROTECT AND RESTORE FISH AND WILDLIFE HABITAT WITH LONG-TERM BENEFITS TO ESA-LISTED SPECIES. THE FOLLOWING GENERAL CONSERVATION MEASURES (DEVELOPED IN COORDINATION WITH USFWS AND NMFS) WILL BE APPLIED TO ALL ACTIONS OF THIS PROJECT.

PROJECT DESIGN AND SITE PREPARATION.

1. TRIBAL AND FEDERAL PERMITS.

- A. ALL APPLICABLE REGULATORY PERMITS AND OFFICIAL PROJECT AUTHORIZATIONS WILL BE OBTAINED BEFORE PROJECT IMPLEMENTATION.
- B. THESE PERMITS AND AUTHORIZATIONS INCLUDE, BUT ARE NOT LIMITED TO, NATIONAL ENVIRONMENTAL POLICY ACT, NATIONAL HISTORIC PRESERVATION ACT, THE APPROPRIATE REMOVAL AND FILL PERMIT, USACE CLEAN WATER ACT (CWA) 404 PERMITS, AND CWA SECTION 401 WATER QUALITY CERTIFICATIONS.

2. TIMING OF IN-WATER WORK.

- A. APPROPRIATE FEDERAL (NOAA) AND YAKAMA NATION FISHERIES GUIDELINES FOR TIMING OF IN-WATER WORK WINDOWS (IWW) WILL BE FOLLOWED.
- B. CHANGES TO ESTABLISHED WORK WINDOWS WILL BE APPROVED BY REGIONAL NOAA BIOLOGISTS AND BPA'S EC LEAD.
- C. LAMPREY. WORKING IN STREAM OR RIVER CHANNELS THAT CONTAIN PACIFIC LAMPREY WILL BE AVOIDED FROM MARCH 1 TO JULY 1 FOR REACHES <5,000 FEET IN ELEVATION AND FROM MARCH 1 TO AUGUST 1 FOR REACHES >5,000 FEET. IF EITHER TIMEFRAME IS INCOMPATIBLE WITH OTHER OBJECTIVES, THE AREA WILL BE SURVEYED FOR NESTS AND LAMPREY PRESENCE, AND AVOIDED IF POSSIBLE. IF LAMPREYS ARE KNOWN TO EXIST, THE PROJECT SPONSOR WILL UTILIZE DEWATERING AND SALVAGE PROCEDURES (SEE FISH SALVAGE AND ELECTROFISHING SECTIONS) TO MINIMIZE ADVERSE EFFECTS.
- D. THE IN-WATER WORK WINDOW WILL BE PROVIDED IN THE CONSTRUCTION PLANS.

3. CONTAMINANTS.

- A. EXCAVATION OF MORE THAN 20 CUBIC YARDS WILL REQUIRE A SITE VISIT AND DOCUMENTED ASSESSMENT FOR POTENTIAL CONTAMINANT SOURCES. THE SITE ASSESSMENT WILL BE STORED WITH PROJECT FILES OR AS AN APPENDIX TO THE BASIS OF DESIGN REPORT.
- B. THE SITE ASSESSMENT WILL SUMMARIZE:
1. THE SITE VISIT, CONDITION OF THE PROPERTY, AND IDENTIFICATION OF ANY AREAS USED FOR VARIOUS INDUSTRIAL PROCESSES;
 2. AVAILABLE RECORDS, SUCH AS FORMER SITE USE, BUILDING PLANS, AND RECORDS OF ANY PRIOR CONTAMINATION EVENTS;
 3. INTERVIEWS WITH KNOWLEDGEABLE PEOPLE, SUCH AS SITE OWNERS, OPERATORS, OCCUPANTS, NEIGHBORS, OR LOCAL GOVERNMENT OFFICIALS; AND
 4. THE TYPE, QUANTITY, AND EXTENT OF ANY POTENTIAL CONTAMINATION SOURCES.

4. SITE LAYOUT AND FLAGGING.

- A. CONSTRUCTION AREAS TO BE CLEARLY FLAGGED BY YEAR PRIOR TO CONSTRUCTION.
- B. AREAS TO BE FLAGGED WILL INCLUDE:
1. SENSITIVE RESOURCE AREAS;
 2. EQUIPMENT ENTRY AND EXIT POINTS;
 3. ROAD AND STREAM CROSSING ALIGNMENTS;
 4. STAGING, STORAGE, AND STOCKPILE AREAS; AND

5. TEMPORARY ACCESS ROADS AND PATHS.

- A. EXISTING ACCESS ROADS AND PATHS WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER AND LENGTH OF TEMPORARY ACCESS ROADS AND PATHS THROUGH RIPARIAN AREAS AND FLOODPLAINS WILL BE MINIMIZED. TEMPORARY ACCESS ROADS WILL BE LIMITED TO THE ALIGNMENTS IDENTIFIED IN THE PLAN OR IF APPROVED ON SITE BY YRWP.
- B. VEHICLE USE AND HUMAN ACTIVITIES, INCLUDING WALKING, IN AREAS OCCUPIED BY TERRESTRIAL ESA-LISTED SPECIES WILL BE MINIMIZED.
- C. TEMPORARY ACCESS ROADS AND PATHS WILL NOT BE BUILT ON SLOPES WHERE GRADE, SOIL, OR OTHER FEATURES SUGGEST A LIKELIHOOD OF EXCESSIVE EROSION OR FAILURE. IF SLOPES ARE STEEPER THAN 30%, THEN THE ROAD WILL BE DESIGNED BY A CIVIL ENGINEER WITH EXPERIENCE IN STEEP ROAD DESIGN.
- D. THE REMOVAL OF RIPARIAN VEGETATION DURING CONSTRUCTION OF TEMPORARY ACCESS ROADS WILL BE MINIMIZED. WHEN TEMPORARY VEGETATION REMOVAL IS REQUIRED, VEGETATION WILL BE CUT AT GROUND LEVEL (NOT GRUBBED).
- E. AT PROJECT COMPLETION, ALL TEMPORARY ACCESS ROADS AND PATHS WILL BE OBLITERATED, AND THE SOIL WILL BE STABILIZED AND REVEGETATED. ROAD AND PATH OBLITERATION REFERS TO THE MOST COMPREHENSIVE DEGREE OF DECOMMISSIONING AND INVOLVES DECOMPACTING THE SURFACE AND DITCH, PULLING THE FILL MATERIAL ONTO THE RUNNING SURFACE, AND RESHAPING TO MATCH THE ORIGINAL CONTOUR.

6. TEMPORARY STREAM CROSSINGS

- A. EXISTING STREAM CROSSINGS OR BEDROCK WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER OF TEMPORARY STREAM CROSSINGS WILL BE MINIMIZED AND ALLOWED ONLY IN LOCATIONS IDENTIFIED BY YRWP.
- B. TEMPORARY BRIDGES AND CULVERTS WILL BE INSTALLED TO ALLOW FOR EQUIPMENT AND VEHICLE CROSSING OVER PERENNIAL STREAMS DURING CONSTRUCTION. TREATED WOOD SHALL NOT BE USED ON TEMPORARY BRIDGE CROSSINGS OR IN LOCATIONS IN CONTACT WITH OR DIRECTLY OVER WATER.
- C. FOR PROJECTS THAT REQUIRE EQUIPMENT AND VEHICLES TO CROSS IN THE WET:
 1. THE LOCATION AND NUMBER OF ALL WET CROSSINGS SHALL BE APPROVED BY THE BPA EC LEAD AND DOCUMENTED IN THE CONSTRUCTION PLANS;
 2. VEHICLES AND MACHINERY SHALL CROSS STREAMS AT RIGHT ANGLES TO THE MAIN CHANNEL WHENEVER POSSIBLE;
 3. NO STREAM CROSSINGS WILL OCCUR 300 FEET UPSTREAM OR 100 FEET DOWNSTREAM OF AN EXISTING REDD OR SPAWNING FISH; AND
 4. AFTER PROJECT COMPLETION, TEMPORARY STREAM CROSSINGS WILL BE OBLITERATED AND BANKS RESTORED.

7. STAGING, STORAGE, AND STOCKPILE AREAS

- A. STAGING AREAS (USED FOR CONSTRUCTION EQUIPMENT STORAGE, VEHICLE STORAGE, FUELING, SERVICING, AND HAZARDOUS MATERIAL STORAGE) WILL BE 150 FEET OR MORE FROM ANY NATURAL WATER BODY OR WETLAND. STAGING AREAS CLOSER THAN 150 FEET WILL BE APPROVED BY THE EC LEAD.
- B. NATURAL MATERIALS USED FOR IMPLEMENTATION OF AQUATIC RESTORATION, SUCH AS LARGE WOOD, GRAVEL, AND BOULDERS, MAY BE STAGED WITHIN 150 FEET IF CLEARLY INDICATED IN THE PLANS THAT AREA IS FOR NATURAL MATERIALS ONLY.
- C. ANY LARGE WOOD, TOPSOIL, AND NATIVE CHANNEL MATERIAL DISPLACED BY CONSTRUCTION WILL BE STOCKPILED FOR USE DURING SITE RESTORATION AT A SPECIFICALLY IDENTIFIED AND FLAGGED AREA.
- D. ANY MATERIAL NOT USED IN RESTORATION, AND NOT NATIVE TO THE FLOODPLAIN, WILL BE DISPOSED OF OUTSIDE THE 100-YEAR FLOODPLAIN.

8. EQUIPMENT.

- A. MECHANIZED EQUIPMENT AND VEHICLES WILL BE SELECTED, OPERATED, AND MAINTAINED IN A MANNER THAT MINIMIZES ADVERSE EFFECTS ON THE ENVIRONMENT (E.G., MINIMALLY-SIZED, LOW PRESSURE TIRES; MINIMAL HARD-TURN PATHS FOR TRACKED VEHICLES; TEMPORARY MATS OR PLATES WITHIN WET AREAS OR ON SENSITIVE SOILS).
- B. EQUIPMENT WILL BE STORED, FUELED, AND MAINTAINED IN A CLEARLY IDENTIFIED STAGING AREA THAT MEETS STAGING AREA CONSERVATION MEASURES.


- C. EQUIPMENT WILL BE REFUELED IN A VEHICLE STAGING AREA OR IN AN ISOLATED HARD ZONE, SUCH AS A PAVED PARKING LOT OR ADJACENT, ESTABLISHED ROAD (THIS MEASURE APPLIES ONLY TO GAS-POWERED EQUIPMENT WITH TANKS LARGER THAN 5 GALLONS).
- D. BIODEGRADABLE LUBRICANTS AND FLUIDS WILL BE USED ON EQUIPMENT OPERATING IN AND ADJACENT TO THE STREAM CHANNEL AND LIVE WATER.
- E. EQUIPMENT WILL BE INSPECTED DAILY FOR FLUID LEAKS BEFORE LEAVING THE VEHICLE STAGING AREA FOR OPERATION WITHIN 150 FEET OF ANY NATURAL WATER BODY OR WETLAND.
- F. EQUIPMENT WILL BE THOROUGHLY CLEANED BEFORE OPERATION BELOW ORDINARY HIGH WATER, AND AS OFTEN AS NECESSARY DURING OPERATION, TO REMAIN GREASE FREE.

9. EROSION CONTROL.

- A. TEMPORARY EROSION CONTROL MEASURES INCLUDE:
1. TEMPORARY EROSION CONTROLS WILL BE IN PLACE BEFORE ANY SIGNIFICANT ALTERATION OF THE ACTION SITE AND APPROPRIATELY INSTALLED DOWNSLOPE OF PROJECT ACTIVITY WITHIN THE RIPARIAN BUFFER AREA UNTIL SITE REHABILITATION IS COMPLETE;
 2. IF THERE IS A POTENTIAL FOR ERODED SEDIMENT TO ENTER THE STREAM, SEDIMENT BARRIERS WILL BE INSTALLED AND MAINTAINED FOR THE DURATION OF PROJECT IMPLEMENTATION;
 3. TEMPORARY EROSION CONTROL MEASURES MAY INCLUDE SEDGE MATS, FIBER WATTLES, SILT FENCES, JUTE MATTING, WOOD FIBER MULCH AND SOIL BINDER, OR GEOTEXTILES AND GEOSYNTHETIC FABRIC;
 4. SOIL STABILIZATION UTILIZING WOOD FIBER MULCH AND TACKIFIER (HYDRO-APPLIED) MAY BE USED TO REDUCE EROSION OF BARE SOIL IF THE MATERIALS ARE NOXIOUS WEED FREE AND NONTOXIC TO AQUATIC AND TERRESTRIAL ANIMALS, SOIL MICROORGANISMS, AND VEGETATION;
 5. SEDIMENT WILL BE REMOVED FROM EROSION CONTROLS ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE CONTROL; AND
 6. ONCE THE SITE IS STABILIZED AFTER CONSTRUCTION, TEMPORARY EROSION CONTROL MEASURES WILL BE REMOVED.
- B. EMERGENCY EROSION CONTROLS. THE FOLLOWING MATERIALS FOR EMERGENCY EROSION CONTROL WILL BE AVAILABLE AT THE WORK SITE:
1. A SUPPLY OF SEDIMENT CONTROL MATERIALS; AND
 2. AN OIL-ABSORBING FLOATING BOOM WHENEVER SURFACE WATER IS PRESENT.

10. DUST ABATEMENT.

- A. THE PROJECT SPONSOR WILL DETERMINE THE APPROPRIATE DUST CONTROL MEASURES BY CONSIDERING SOIL TYPE, EQUIPMENT USAGE, PREVAILING WIND DIRECTION, AND THE EFFECTS CAUSED BY OTHER EROSION AND SEDIMENT CONTROL MEASURES.
- B. WORK WILL BE SEQUENCED AND SCHEDULED TO REDUCE EXPOSED BARE SOIL SUBJECT TO WIND EROSION.
- C. DUST-ABATEMENT ADDITIVES AND STABILIZATION CHEMICALS (TYPICALLY MAGNESIUM CHLORIDE, CALCIUM CHLORIDE SALTS, OR LIGNINSULFONATE) WILL NOT BE APPLIED WITHIN 25 FEET OF WATER OR A STREAM CHANNEL AND WILL BE APPLIED SO AS TO MINIMIZE THE LIKELIHOOD THAT THEY WILL ENTER STREAMS. APPLICATIONS OF LIGNINSULFONATE WILL BE LIMITED TO A MAXIMUM RATE OF 0.5 GALLONS PER SQUARE YARD OF ROAD SURFACE, ASSUMING MIXED 50:50 WITH WATER.
- D. APPLICATION OF DUST ABATEMENT CHEMICALS WILL BE AVOIDED DURING OR JUST BEFORE WET WEATHER, AND AT STREAM CROSSINGS OR OTHER AREAS THAT COULD RESULT IN UNFILTERED DELIVERY OF THE DUST ABATEMENT MATERIALS TO A WATERBODY (TYPICALLY THESE WOULD BE AREAS WITHIN 25 FEET OF A WATERBODY OR STREAM CHANNEL; DISTANCES MAY BE GREATER WHERE VEGETATION IS SPARSE OR SLOPES ARE STEEP).
- E. SPILL CONTAINMENT EQUIPMENT WILL BE AVAILABLE DURING APPLICATION OF DUST ABATEMENT CHEMICALS.
- F. PETROLEUM-BASED PRODUCTS WILL NOT BE USED FOR DUST ABATEMENT.

				BPA DRAWN	BPA DESIGNED	BPA CHECKED	CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2 WHITE SWAN, WA		501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com	CONSERVATION MEASURES (1 OF 3)	SHEET
					05/09/2025	23-02-21					2 OF 34
				APPROVED	DATE	PROJECT					
NO.	BY	DATE	REVISION DESCRIPTION								

[illegible]

4. DEWATERING.

- ## CONSTRUCTION AND POST CONSTRUCTION CONSERVATION MEASURES.

1. FISH PASSAGE.

- ## 2. CONSTRUCTION AND DISCHARGE WATER

- A. SURFACE WATER MAY BE DIVERTED TO MEET CONSTRUCTION NEEDS ONLY IF DEVELOPED SOURCES ARE UNAVAILABLE OR INADEQUATE.
- B. DIVERSIONS WILL NOT EXCEED 10% OF THE AVAILABLE FLOW.
- C. CONSTRUCTION DISCHARGE WATER WILL BE COLLECTED AND TREATED TO REMOVE DEBRIS, NUTRIENTS, SEDIMENT, PETROLEUM HYDROCARBONS, METALS, AND OTHER POLLUTANTS.

3. TIME AND EXTENT OF DISTURBANCE.

- A. EARTHWORK REQUIRING IN-STREAM MECHANIZED EQUIPMENT (INCLUDING DRILLING, EXCAVATION, DREDGING, FILLING, AND COMPACTING) WILL BE COMPLETED AS QUICKLY AS POSSIBLE.
- B. MECHANIZED EQUIPMENT WILL WORK FROM TOP OF BANK UNLESS WORK FROM ANOTHER LOCATION WILL RESULT IN LESS HABITAT DISTURBANCE (TURBIDITY, VEGETATION DISTURBANCE, ETC.).

4. CESSATION OF WORK.

- A. PROJECT OPERATIONS WILL CEASE WHEN HIGH FLOW CONDITIONS MAY RESULT IN INUNDATION OF THE PROJECT AREA (FLOOD EFFORTS TO DECREASE DAMAGES TO NATURAL RESOURCES PERMITTED).
- B. WATER QUALITY LEVELS EXCEEDED. SEE CWA SECTION 401 WATER QUALITY CERTIFICATION AND TURBIDITY MEASURES.

5. SITE RESTORATION.

- A. DISTURBED AREAS, STREAM BANKS, SOILS, AND VEGETATION WILL BE CLEANED UP AND RESTORED TO IMPROVED OR PRE-PROJECT CONDITIONS.
- B. PROJECT-RELATED WASTE WILL BE REMOVED.
- C. TEMPORARY ACCESS ROADS AND STAGING WILL BE DECOMPACTED AND RESTORED. SOILS WILL BE LOOSENEED IF NEEDED FOR REVEGETATION OR WATER INFILTRATION.
- D. THE PROJECT SPONSOR WILL RETAIN THE RIGHT OF REASONABLE ACCESS TO THE SITE TO MONITOR AND MAINTAIN THE SITE OVER THE LIFE OF THE PROJECT.

6. REVEGETATION.

- A. PLANTING AND SEEDING WILL OCCUR PRIOR TO OR AT THE BEGINNING OF THE FIRST GROWING SEASON AFTER CONSTRUCTION.

- B. A MIX OF NATIVE SPECIES (INVASIVE SPECIES NOT ALLOWED) APPROPRIATE TO THE SITE WILL BE USED TO REESTABLISH VEGETATION, PROVIDE SHADE, AND REDUCE EROSION. REESTABLISHED VEGETATION SHOULD BE AT LEAST 70% OF PRE-PROJECT CONDITIONS WITHIN THREE YEARS.
- C. RIPARIAN VEGETATION SUCH AS WILLOWS, SEDGES, OR RUSH MATS WILL BE SALVAGED FROM DISTURBED OR ABANDONED AREAS TO BE REPLANTED.
- D. SHORT-TERM STABILIZATION MEASURE MAY INCLUDE THE USE OF NON-NATIVE STERILE SEED MIX (WHEN NATIVE NOT AVAILABLE), WEED-FREE CERTIFIED STRAW, OR OTHER SIMILAR TECHNIQUES.
- E. SURFACE FERTILIZER WILL NOT BE APPLIED WITHIN 50 FEET OF ANY STREAM, WATER BODY, OR WETLAND.
- F. FENCING WILL BE INSTALLED AS NECESSARY TO PREVENT ACCESS TO REVEGETATED SITES BY LIVESTOCK OR UNAUTHORIZED PERSONS.
- G. INVASIVE PLANTS WILL BE REMOVED OR CONTROLLED UNTIL NATIVE PLANT SPECIES ARE WELL ESTABLISHED (TYPICALLY THREE YEARS POST-CONSTRUCTION).

7. SITE ACCESS AND IMPLEMENTATION MONITORING.

- A. THE PROJECT SPONSOR WILL PROVIDE CONSTRUCTION MONITORING DURING IMPLEMENTATION TO ENSURE ALL CONSERVATION MEASURES ARE ADEQUATELY FOLLOWED, EFFECTS TO LISTED SPECIES ARE NOT GREATER THAN PREDICTED, AND INCIDENTAL TAKE LIMITATIONS ARE NOT EXCEEDED.
- B. THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL SUBMIT THE PROJECT COMPLETION FORM (PCF) WITHIN 30 DAYS OF PROJECT COMPLETION.


8. CWA SECTION 401 WATER QUALITY CERTIFICATION

- A. THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL COMPLETE AND RECORD WATER QUALITY OBSERVATIONS (SEE TURBIDITY MONITORING) TO ENSURE IN-WATER WORK IS NOT DEGRADING WATER QUALITY.
- B. DURING CONSTRUCTION, WATER QUALITY PROVISIONS PROVIDED BY THE OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY, WASHINGTON DEPARTMENT OF ECOLOGY, IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE FOLLOWED.

STAGED REWATERING PLAN.

- A. WHEN REWATERING NEWLY CONSTRUCTED AREAS AND NEWLY CONSTRUCTED CHANNELS, A STAGED REWATERING PLAN WILL BE APPLIED.
- B. THE FOLLOWING WILL BE APPLIED TO ALL REWATERING EFFORTS. COMPLEX REWATERING EFFORTS MAY REQUIRE ADDITIONAL NOTES OR A DEDICATED SHEET IN THE CONSTRUCTION DETAILS.
 1. TURBIDITY MONITORING PROTOCOL WILL BE APPLIED TO REWATERING EFFORTS.
 2. PRE-WASH THE AREA BEFORE REWATERING. TURBID WASH WATER WILL BE DETAINED AND PUMPED TO THE FLOODPLAIN OR SEDIMENT CAPTURE AREAS RATHER THAN DISCHARGING TO FISH-BEARING STREAMS.
 3. INSTALL SEINE NETS AT UPSTREAM END TO PREVENT FISH FROM MOVING DOWNSTREAM UNTIL 2/3 OF TOTAL FLOW IS RESTORED TO THE CHANNEL.
 4. STARTING IN EARLY MORNING INTRODUCE 1/3 OF NEW CHANNEL FLOW OVER PERIOD OF 1-2 HOURS.
 5. INTRODUCE SECOND THIRD OF FLOW OVER NEXT 1 TO 2 HOURS AND BEGIN FISH SALVAGE OF BYPASS CHANNEL IF FISH ARE PRESENT.
 6. REMOVE UPSTREAM SEINE NETS ONCE 2/3 FLOW IN REWATERED CHANNEL AND DOWNSTREAM TURBIDITY IS WITHIN ACCEPTABLE RANGE (LESS THAN 40 NTU OR LESS THAN 10% BACKGROUND).
 7. INTRODUCE FINAL THIRD OF FLOW ONCE FISH SALVAGE EFFORTS ARE COMPLETE AND DOWNSTREAM TURBIDITY VERIFIED TO BE WITHIN ACCEPTABLE RANGE.
 8. INSTALL PLUG TO BLOCK FLOW INTO OLD CHANNEL OR BYPASS. REMOVE ANY REMAINING SEINE NETS.
 9. IN LAMPREY SYSTEMS, LAMPREY SALVAGE AND DRY SHOCKING MAY BE NECESSARY.

- A. RECORD THE READING, LOCATION, AND TIME FOR THE BACKGROUND READING APPROXIMATELY 100 FEET UPSTREAM OF THE PROJECT AREA USING A RECENTLY CALIBRATED TURBIDIMETER OR VIA VISUAL OBSERVATION (SEE THE HIP HANDBOOK TURBIDITY MONITORING SECTION FOR A VISUAL OBSERVATION KEY).
- B. RECORD THE TURBIDITY READING, LOCATION, AND TIME AT THE MEASUREMENT COMPLIANCE LOCATION POINT.
 1. 50 FEET DOWNSTREAM FOR STREAMS LESS THAN 30 FEET WIDE.
 2. 100 FEET DOWNSTREAM FOR STREAMS BETWEEN 30 AND 100 FEET WIDE.
 3. 200 FEET DOWNSTREAM FOR STREAMS GREATER THAN 100 FEET WIDE.
 4. 300 FEET FROM THE DISCHARGE POINT OR NONPOINT SOURCE FOR LOCATIONS SUBJECT TO TIDAL OR COASTAL SCOUR.
- C. TURBIDITY SHALL BE MEASURED (BACKGROUND LOCATION AND COMPLIANCE POINTS) EVERY 4 HOURS WHILE WORK IS BEING IMPLEMENTED.
- D. IF THERE IS A VISIBLE DIFFERENCE BETWEEN A COMPLIANCE POINT AND THE BACKGROUND, THE EXCEEDANCE WILL BE NOTED IN THE PROJECT COMPLETION FORM (PCF). ADJUSTMENTS OR CORRECTIVE MEASURES WILL BE TAKEN IN ORDER TO REDUCE TURBIDITY.
- E. IF EXCEEDANCES OCCUR FOR MORE THAN TWO CONSECUTIVE MONITORING INTERVALS (AFTER 8 HOURS), THE ACTIVITY WILL STOP UNTIL THE TURBIDITY LEVEL RETURNS TO BACKGROUND. THE BPA EC LEAD WILL BE NOTIFIED OF ALL EXCEEDANCES AND CORRECTIVE ACTIONS AT PROJECT COMPLETION.
- F. IF TURBIDITY CONTROLS (COFFER DAMS, WADDLES, FENCING, ETC.) ARE DETERMINED INEFFECTIVE, CREWS WILL BE MOBILIZED TO MODIFY AS NECESSARY. OCCURRENCES WILL BE DOCUMENTED IN THE PROJECT COMPLETION FORM (PCF).
- G. FINAL TURBIDITY READINGS, EXCEEDANCES, AND CONTROL FAILURES WILL BE SUBMITTED TO THE BPA EC LEAD USING THE PROJECT COMPLETION FORM (PCF).

				<div>BPA DRAWN</div>	<div>BPA DESIGNED</div>	<div>BPA CHECKED</div>	CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2 WHITE SWAN, WA	 <div>501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com</div>	CONSERVATION MEASURES (3 OF 3)	SHEET
				<div>05/09/2025</div>	<div>23-02-21</div>	4 OF 34				
NO.	BY	DATE	REVISION DESCRIPTION	APPROVED	DATE	PROJECT				

2-ClientFiles/Q-TToppennish3WayPa2-230221DrawingsTToppennish3WayPa2.dwg - htopcedric - 5/2025

THE CONTRACTOR SHALL ATTEND A PRE-BID SITE MEETING.

THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH THE CONTRACTING AGENT (YAKAMA RESERVATION WATERSHED PROJECT (YRWP)) AND YRWP'S REPRESENTATIVE PRIOR TO BEGINNING CONSTRUCTION.

ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT), AND LOCAL STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT SHALL PREVAIL.

IN CASE OF DISCREPANCY, BETWEEN NOTES, LOCAL REGULATIONS, OR OTHER CONTRACT DOCUMENTATION, CONTRACTOR SHALL OBTAIN CLARIFICATION/DIRECTION FROM CONTRACTING AGENT (YRWP).

EXISTING DATA

TOPOGRAPHIC SURVEY COLLECTED BY INTER-FLUVE, INC. USING RTK GPS AND A TOTAL STATION ON JUNE 20-22,2023 AND NOVEMBER 8-9, 2023. SURVEY DATA IS REFERENCED TO NAD83 WASHINGTON STATE PLANE, SOUTH ZONE, US FEET, NAVD 88.

LIDAR DATA SOLICITED BY WASHINGTON DEPARTMENT OF NATURAL RESOURCES AS PART OF THE YAKIMA BASIN DATA SET. DATA ACQUIRED BY QUANTUM SPATIAL IN NOVEMBER 2017 & MAY 2018.

HYDRAULIC MODELING BY INTER-FLUVE USING USACE HEC-RAS (6.4.1). MODEL VALIDATED USING SURVEYED WATER SURFACE ELEVATIONS AND FIELD OBSERVATIONS.

WATERS OF THE U.S.

THE ORDINARY HIGH WATER (OHW) LINES DISPLAYED IN THE DESIGN PACKAGE ARE BASED UPON ANALYSIS, MODELING AND BEST PROFESSIONAL JUDGEMENT.

WETLAND DELINEATION WAS COMPLETED IN 2024 BY INTER-FLUVE.

SOILS

TOPPENISH CREEK ALLUVIUM: COBBLE, GRAVEL, SAND, AND SILT.

UTILITIES

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.

INFORMATION FOR UTILITY LOCATION CAN BE FOUND AT:

``CALL811.COM/911-IN-YOUR-STATE/MAP/STATE/WASHINGTON

THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES. THE CONTRACTOR SHALL PROVIDE EQUIPMENT OR LABOR TO AID THE AFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR DESTROYED UTILITIES AT NO COST TO YRWP.

IN-WATER WORK PERIODS

WORK SHALL OCCUR DURING THE PERMITTED IN-WATER WORK PERIOD AS STATED IN THE APPLICABLE PERMITS.

FISH RESCUE

ALL FISH RESCUE EFFORTS SHALL BE SUPERVISED BY A QUALIFIED YAKAMA NATION FISHERIES/AQUATIC BIOLOGIST EXPERIENCED WITH THE COLLECTION AND HANDLING OF SALMONID FISHES FROM CONSTRUCTION SITES.

ALL FISH TRAPPED IN RESIDUAL POOLS WITHIN THE PROJECT AREA SHALL BE CAREFULLY COLLECTED BY SEINE AND/OR DIP NETS AND PLACED IN CLEAN TRANSFER CONTAINERS WITH ADEQUATE VOLUME OF WATER AND HELD WITHIN NO LONGER THAN 10 MINUTES.

CAPTURED FISHES SHALL BE IMMEDIATELY RELEASED INTO THE RIVER.

CONTRACTOR WILL PROVIDE AGREED UPON ADVANCE NOTICE TO YRWP PRIOR TO FISH RESCUE. CONTRACTOR IS RESPONSIBLE FOR ISOLATING THE CONSTRUCTION LOCATION FROM THE STREAM.

CULTURAL RESOURCES

CULTURAL RESOURCE MONITORING TO BE PROVIDED BY YRWP DURING GROUND DISTURBING ACTIVITIES. THE CONTRACTOR SHALL ACCOMMODATE THE MONITORING PERSONNEL AND COMPLY WITH THEIR DIRECTION RELATIVE TO INTERACTIONS WITH POTENTIAL CULTURAL RESOURCES.

IF YOUR WORK BRINGS YOU INTO CONTACT WITH ANY OF THE FOLLOWING CULTURAL RESOURCES:

- NATIVE AMERICAN CULTURAL ARTIFACTS (EXAMPLE: FLAKES, ARROWHEADS, STONE TOOLS, BONE TOOLS, POTTERY, HEARTH FEATURES, ETC)
- HISTORIC ERA ARTIFACTS (EXAMPLE: BUILDING FOUNDATIONS, HOMESTEADS, MINING CAMPS, ETC)
- HUMAN SKELETAL REMAINS AND BONE FRAGMENTS

YOU MUST IMMEDIATELY DISCONTINUE ALL GROUND-DISTURBING ACTIVITY. DO NOT TOUCH OR MOVE THE OBJECTS AND MAINTAIN THE CONFIDENTIALITY OF THE SITE. FOLLOW THE PROCEDURES LISTED IN THE TRIBES INADVERTENT DISCOVERY PROCEDURE. THEN AWAIT FURTHER DIRECTION FROM THE TRIBE'S CULTURAL RESOURCES STAFF.

TREE SALVAGE

ALL SAPLING AND TREES TO BE REMOVED SHALL BE APPROVED AND CLEARLY MARKED BY YRWP'S OR THEIR CONTRACTED REPRESENTATIVE.

ALL REMOVED NATIVE VEGETATION SHALL BE INCORPORATED INTO LOG STRUCTURES AS DIRECTED BY YRWP OR THEIR CONTRACTED REPRESENTATIVE. IF EXCESS VEGETATION MATERIAL NEEDS DISPOSAL OUTSIDE OF CHANNEL WORK, IT SHALL BE DISTRIBUTED IN DESIGNATED AREAS ON THE FLOODPLAIN OR ON THE FLOODPLAIN AS DIRECTED BY YRWP'S REPRESENTATIVE.

ALL TREES REMOVED WITHIN CLEARING LIMITS SHALL BE REMOVED WHOLE WITH ROOTS INTACT AND UTILIZED IN THE SIDE CHANNEL CONSTRUCTION OR IN MAINSTEM WORK AS DIRECTED BY CONTRACTING AGENT'S REPRESENTATIVE.

REMOVE SOIL FROM ROOTS OF SALVAGED TREES BEFORE PLACEMENT IN THE WATERWAY.

LIVE TREES

ALL TREES NOT MARKED FOR REMOVAL SHALL BE PRESERVED AND UNDISTURBED. CONSTRUCTION ACTIVITY SHALL NOT DEBARK OR DAMAGE LIVE TREES.

KEEP OUT OF DRIP LINE OF ALL PRESERVED EXISTING TREES.

PLANTINGS

PLANT INSTALLATION SHALL BE SCHEDULED FOR BEST SURVIVAL RATE. YRWP WILL COORDINATE PLANTING SCHEDULE WITH THE CONTRACTOR.

CONTRACTOR IS RESPONSIBLE FOR PROPER HANDLING, STORAGE, WATERING, AND INSTALLATION.

CONTRACTOR'S PLANS

CONTRACTOR SHALL PREPARE AND SUBMIT FOR APPROVAL BY THE YRWP PRIOR TO COMMENCING WORK THE FOLLOWING PLANS:

- ACCESS, TRAFFIC CONTROL AND TEMPORARY STREAM CROSSING PLAN
- CONSTRUCTION SEQUENCING PLAN
- STREAM DIVERSION AND SITE DEWATERING PLAN
- EROSION, SEDIMENT AND DUST CONTROL PLAN
- EARTHWORKS EXCAVATION, PLACEMENT, SALVAGE & REUSE, AND DISPOSAL PLAN
- FENCE INSTALLATION SHOP DRAWINGS

CONSTRUCTION ACCESS

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR OBTAINING ANY REQUIRED TRAFFIC CONTROL OR ACCESS PERMITS, AND PROVIDING REQUIRED TRAFFIC CONTROL MEASURES INCLUDING, BUT NOT LIMITED TO, SIGNAGE AND FLAGGERS.

ALL EQUIPMENT, MATERIALS AND PERSONNEL SHALL REMAIN WITHIN THE LIMITS OF DISTURBANCE.

THE CONTRACTOR SHALL KEEP THE WORK AREAS IN A NEAT AND CLEAN CONDITION FREE OF DEBRIS AND LITTER FOR THE DURATION OF THE PROJECT.

TEMPORARY ACCESS ROUTES IN AREAS PRONE TO INUNDATION DURING THE IN-WATER WORK WINDOW SHALL BE DECOMMISSIONED BEFORE THE END OF THE IN-WATER WORK WINDOW.

CONSTRUCTION STAKING

YRWP OR DESIGNATED REPRESENTATIVE WILL INSTALL FLAGGING TO DELINEATE EQUIPMENT ENTRY AND EXIT POINTS, STAGING AND STOCKPILE AREAS, APPROXIMATE LOG STRUCTURE LOCATIONS, AND PROJECT LIMITS. YRWP'S REPRESENTATIVE WILL INSTALL ELEVATION CONTROL POINTS. THE CONTRACTOR SHALL BE RESPONSIBLE, AT OWN EXPENSE, FOR STAKING AND REPLACING DAMAGED OR MISSING STAKES.

YRWP AND YRWP'S REPRESENTATIVE WILL MARK LIMITS OF DISTURBANCE PRIOR TO MOBILIZATION OF EQUIPMENT OR MATERIALS ONTO THE SITE.

SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED. LOCATION, ALIGNMENT, AND ELEVATION OF LOGS AND LOGS WITH ROOTWADS ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS, AND MATERIAL SIZE PER DIRECTION FROM YWRP'S REPRESENTATIVE.

ANY PROPERTY MONUMENTS DISTURBED OR DESTROYED SHALL BE REPLACED BY A WASHINGTON STATE PROFESSIONAL LICENSED SURVEYOR AT CONTRACTOR'S EXPENSE.

ABBREVIATIONS

APPROX	APPROXIMATE
CY	CUBIC YARDS
°	DEGREES
DIA or Ø	DIAMETER
DBH	DIAMETER AT BREAST HEIGHT
EA	EACH
EL or ELEV	ELEVATION
ESC	EROSION AND SEDIMENT CONTROL
EXIST	EXISTING
FT or '	FEET
FTR	FULLY THREADED ROD
HORIZ	HORIZONTAL
IN or "	INCH
INV	INVERT
LWM	LARGE WOODY MATERIAL
MAX	MAXIMUM
MIN	MINIMUM
MSF	THOUSAND SQUARE FEET
OHW	ORDINARY HIGH WATER
%	PERCENT
RMx	RIVER MILE x
STA	STATION
SY	SQUARE YARDS
TBD	TO BE DETERMINED
TYP	TYPICAL
VERT	VERTICAL
WSE	WATER SURFACE ELEVATION
YR	YEAR



NO.	BY	DATE	REVISION DESCRIPTION

BB	PL, DM, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

GENERAL NOTES AND ABBREVIATIONS	SHEET 5 OF 34
---------------------------------	------------------

EROSION CONTROL

CONTRACTOR SHALL BE SOLELY RESPONSIBLE AT OWN EXPENSE FOR PROVIDING AND MAINTAINING ALL NECESSARY EROSION CONTROL FACILITIES TO COMPLY WITH APPLICABLE EROSION CONTROL REGULATIONS AND TO MAINTAIN CLEAN ACCESS ROUTES.

EROSION/SEDIMENTATION CONTROL (ESC) PLAN

THE EROSION AND SEDIMENT CONTROL (ESC) PLAN PROVIDED IS FOR INFORMATIONAL PURPOSES ONLY, THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING EROSION CONTROL MEASURES TO COMPLY WITH APPLICABLE REGULATIONS.

THE RECOMMENDATIONS FOR AN ESC PLAN INCLUDED HEREIN WILL PROVIDE GUIDELINES FOR THE CONTRACTOR TO DEVELOP AND IMPLEMENT AN ESC PLAN. THE CONTRACTOR'S ESC PLAN SHALL BE SUBMITTED TO THE OWNER PRIOR TO MOBILIZATION.

- A. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED AT NO ADDITIONAL COST FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- B. THE IMPLEMENTATION OF AN ESC PLAN AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- C. THE ESC FACILITIES ARE TO BE CONSTRUCTED PRIOR TO CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DO NOT ENTER THE DRAINAGE SYSTEM.
- D. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- E. THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- F. THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
- G. STABILIZED CONSTRUCTION ENTRANCES AND ADDITIONAL MEASURES MAY BE REQUIRED AND SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT AT CONTRACTOR'S EXPENSE.

STABILIZE SOILS AND PROTECT SLOPES

FROM MAY 1 THROUGH SEPTEMBER 30, ALL EXPOSED SOILS SHALL BE PROTECTED FROM EROSION BY MULCHING, PLASTIC SHEETING, HYDROSEED COVERING, OR OTHER APPROVED MEASURES WITHIN THREE DAYS OF GRADING. FROM OCTOBER 1 THROUGH APRIL 30, ALL EXPOSED SOILS MUST BE PROTECTED WITHIN 2 DAYS OF GRADING. SOILS SHALL BE STABILIZED BEFORE A WORK SHUTDOWN, HOLIDAY OR WEEKEND IF NEEDED BASED ON THE WEATHER FORECAST. SOIL STOCKPILES MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES. MULCH AS SOON AS PRACTICAL ALL DISTURBED AREAS NOT INDICATED IN THE CONTRACT DOCUMENTS FOR OTHER PERMANENT STABILIZATION MEASURES. HAY, STRAW, AND MULCH USED ON SITE MUST BE 99.9% WEED-FREE.

DESIGN, CONSTRUCT, AND PHASE CUT AND FILL SLOPES IN A MANNER THAT WILL MINIMIZE EROSION. REDUCE SLOPE VELOCITIES ON DISTURBED SLOPES BY PROVIDING TEMPORARY BARRIERS. STORMWATER FROM OFF SITE SHOULD BE HANDLED SEPARATELY FROM STORMWATER GENERATED ON SITE.

AFTER FINAL SITE STABILIZATION

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY BMPS ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED FROM THE SITE OR INCORPORATED INTO FINISHED GRADING. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED.

INVASIVE SPECIES CONTROL

THE FOLLOWING MEASURES WILL BE FOLLOWED TO AVOID INTRODUCTION OF INVASIVE PLANTS AND NOXIOUS WEEDS INTO PROJECT AREAS:

PRIOR TO ENTERING THE SITE, ALL VEHICLES AND EQUIPMENT WILL BE POWER WASHED, ALLOWED TO FULLY DRY, AND INSPECTED TO MAKE SURE NO PLANTS, SOIL, OR OTHER ORGANIC MATERIAL ADHERES TO THE SURFACE.

WATERCRAFT, WADERS, BOOTS, AND ANY OTHER GEAR TO BE USED IN OR NEAR WATER WILL BE INSPECTED FOR AQUATIC INVASIVE SPECIES.

WADING BOOTS WITH FELT SOLES ARE NOT TO BE USED DUE TO THEIR PROPENSITY FOR AIDING IN THE TRANSFER OF INVASIVE SPECIES.

DUST CONTROL

THE CONTRACTOR SHALL CONTROL DUST FOR THE DURATION OF THE PROJECT. CONTROL MEASURES SHALL BE IN ACCORDANCE WITH APPLICABLE REGULATIONS, AND MAY INCLUDE WATERING, MULCH, AND SLOWER VEHICLE SPEEDS.

CONSTRUCTION DEWATERING

CONTRACTOR SHALL PERFORM CONSTRUCTION DEWATERING IN SUCH A MANNER AS TO AVOID THE RELEASE OF TURBID OR SEDIMENT-LADEN WATER IN ORDER TO PREVENT CONTAMINATION OR INCREASE TURBIDITY OF SURFACE WATERS. EXCAVATION OF DEWATERING SUMPS BEYOND LIMITS SHOWN SHALL BE AT NO ADDITIONAL COST. SEDIMENT LADEN WATER MAY BE PUMPED TO AN UPLAND DISCHARGE LOCATION AND ALLOWED TO SHEET FLOW THROUGH EXISTING VEGETATION BEFORE INFILTRATING INTO THE GROUND. IF THIS METHOD IS NOT SUFFICIENT TO PREVENT RETURN OF TURBID WATER TO SURFACE WATERS OR SENSITIVE FLOODPLAIN AREAS, A 'DIRT-BAG' OR SEDIMENT RETENTION STRUCTURE MAY BE REQUIRED AS NECESSARY TO COMPLY WITH LAWS AND PERMIT REQUIREMENTS AT NO ADDITIONAL COST.

CONTRACTOR SHALL PROVIDE, OPERATE, AND MAINTAIN NUMBER AND SIZE OF PUMPS AS NECESSARY TO ACHIEVE DEWATERING NEEDS. AT A MINIMUM, CONTRACTOR SHALL PROVIDE A 6" DRI-PRIME DIESEL POWERED PUMP AND A PORTABLE 2" PUMP. ADDITIONAL PUMPS AND OF DIFFERENT CAPACITIES MAY BE REQUIRED AT CONTRACTOR'S EXPENSE.

YRWP, OR REPRESENTATIVE SHALL APPROVE DEWATERING DISCHARGE LOCATION PRIOR TO IMPLEMENTATION.

SPILL PREVENTION, CONTROL, AND COUNTER MEASURES

THE USE OF MECHANIZED MACHINERY INCREASES THE RISK FOR ACCIDENTAL SPILLS OF FUEL, LUBRICANTS, HYDRAULIC FLUID, OR OTHER CONTAMINANTS INTO THE RIPARIAN ZONE OR DIRECTLY INTO THE WATER. THE CONTRACTOR SHALL ADHERE TO THE FOLLOWING MEASURES:

A DESCRIPTION OF HAZARDOUS MATERIALS THAT WILL BE USED, INCLUDING INVENTORY, STORAGE, AND HANDLING PROCEDURES SHALL BE AVAILABLE ON-SITE.

WRITTEN PROCEDURES FOR NOTIFYING ENVIRONMENTAL RESPONSE AGENCIES SHALL BE POSTED AT THE WORK SITE.

Cut/Fill volumes within OHW		
Earthwork Areas	Cut (cy)	Fill (cy)
A-C volumes within OHW	107	7,113
D-E volumes within OHW	247	1,366

NOTE:

VOLUME IS IN PLACE MEASURE. EXPANSION OF EXCAVATED MATERIAL AND CONTRACTION OF PLACED MATERIAL IS NOT INCLUDED. MEASUREMENT BY WEIGHT OR TRUCK COUNT SHALL REQUIRE OWNER'S PRIOR WRITTEN APPROVAL.

CY = CUBIC YARDS

EA = EACH

MSF = 1,000 SQUARE FEET



EXPIRES: 11/23/2025

SPILL CONTAINMENT KITS (INCLUDING INSTRUCTIONS FOR CLEANUP AND DISPOSAL) ADEQUATE FOR THE TYPES AND QUANTITY OF HAZARDOUS MATERIALS USED AT THE SITE SHALL BE AVAILABLE AT THE WORK SITE.

WORKERS SHALL BE TRAINED IN SPILL CONTAINMENT PROCEDURES AND SHALL BE INFORMED OF THE LOCATION OF SPILL CONTAINMENT KITS.

ANY WASTE LIQUIDS GENERATED AT THE STAGING AREAS SHALL BE TEMPORARILY STORED UNDER AN IMPERVIOUS COVER, SUCH AS A TARPULIN, UNTIL THEY CAN BE PROPERLY TRANSPORTED TO AND DISPOSED OF AT A FACILITY THAT IS APPROVED FOR RECEIPT OF HAZARDOUS MATERIALS.

VEGETABLE BASED HYDRAULIC FLUIDS (BIODEGRADABLE OIL) SHALL BE USED IN ANY VEHICLE THAT WILL BE OPERATED NEAR THE WATER.

INSPECTION AND MAINTENANCE

ALL ESC FACILITIES SHALL BE INSPECTED, MAINTAINED, AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL ESC FACILITIES SHALL BE INSPECTED DAILY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD AND AFTER EVENTS EXCEEDING 2 HOURS DURATION.

CONTRACTOR'S ESC RECORD

WEEKLY REPORTS SUMMARIZING THE SCOPE OF INSPECTIONS, THE PERSONNEL CONDUCTING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL PLAN, AND ACTIONS TAKEN AS A RESULT OF THESE INSPECTIONS SHALL BE PREPARED AND RETAINED ON SITE BY THE CONTRACTOR. IN ADDITION, A RECORD OF THE FOLLOWING DATES SHALL BE INCLUDED IN THE REPORTS:

- WHEN MAJOR GRADING ACTIVITIES OCCUR,
- DATES OF RAINFALL EVENTS EITHER EXCEEDING 2 HOURS DURATION OR MORE THAN 0.5 INCHES/24 HOURS,
- WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON SITE, OR ON A PORTION OF THE SITE,
- WHEN STABILIZATION MEASURES ARE INITIATED FOR PORTIONS OF THE SITE.

ESC RECORDS SHALL BE MADE AVAILABLE TO THE OWNER AND OWNER'S REPRESENTATIVE ON REQUEST AND SHALL BE PROVIDED FOR REVIEW AND APPROVAL PRIOR TO APPLICATION FOR PAYMENT.

Description	Units	Quantity within Work Area							Item Subtotal
		A	B	C	D	E	F	G	
<u>Earthworks:</u>									
cut	(cy)	11,610	12,086	31,200	18,395	26,480	671	906	101,348
fill	(cy)	4,565	2,391	1,997	468	116	70,493	0	80,030
Haul to Pom Pom	(cy)	NA	NA	30,000	NA	NA	NA	NA	30,000
<u>Large wood structures:</u>									
Type 1 Channel Spanning LW Structure	(ea)		3			4		1	8
Type 2 Channel Spanning LW Structure	(ea)	1		2	2			5	10
Type 1 Bank Buried LW Structure	(ea)	5	1	7	6	1		6	26
Type 2 Bank Buried LW Structure	(ea)	9	6	5	2	12			34
Side Channel Inlet LW Structure	(ea)	2	1	1	1	1			6
Apex Jam	(ea)	2	0	2					4
<u>Floodplain treatments:</u>									
Floodplain Roughness Piles & Sash	(acre)	0.9	0.0	0.7					2
Floodplain Roughness Willow Trenches	(lf)	813.6	601.2	1,620.0	868.0	796.0			4,699
Floodplain Roughness Horizontal Logs with Piles & Sash	(lf)	288.0	475.0	600.0	175.0	708.0			2,246
<u>Vegetation:</u>									
Overbank seed and live plants	(acre)	2.3	1.2	2.9	1.6	1.9			10.0
Transitional/ Upland Seed and Live Plants	(acre)	0.2	0.0				3.8	1.5	5.5
Transitional/Upland Seed Only	(acre)	0.4				2.2			2.5
Willow Bank Installation	(lf)	791.0	476.0	1,278.0	540.0	138.0			3,223

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com



EROSION & SEDIMENT CONTROL

SHEET

6 of 34

NO.	BY	DATE	REVISION DESCRIPTION

BB DRAWN	PL, DM, JB, JB, NS DESIGNED	PL, JB, MB CHECKED
PL, DM, EA APPROVED	05/09/2025 DATE	23-02-21 PROJECT




1
7


TYPICAL SILT FENCE DETAIL
NOT TO SCALE

SILT FENCES:

1. THE SILT FENCE SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, SILT FENCE SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6 INCH OVERLAP, AND BOTH ENDS SECURELY FASTENED TO THE POST. ALTERNATIVELY, OVERLAP AND INTERLOCK TWO POSTS WITH ATTACHED FABRIC AS REQUIRED TO MEET APPLICABLE REGULATIONS.
2. THE SILT FENCE IS TO BE INSTALLED AT LOCATIONS SHOWN ON THE PLAN ALONG THE DOWNHILL PERIMETER OF CONSTRUCTION AREAS. THE FENCE POSTS SHALL BE SPACED A MAXIMUM OF 6 FEET APART AND DRIVEN SECURELY INTO THE GROUND A MINIMUM OF 24 INCHES.
3. THE SILT FENCE SHALL HAVE A MINIMUM VERTICAL BURIAL OF 6 INCHES. ALL EXCAVATED MATERIAL FROM SILT FENCE INSTALLATION SHALL BE BACK-FILLED AND COMPACTED ALONG THE ENTIRE DISTURBED AREA.
4. STANDARD OR HEAVY DUTY SILT FENCE SHALL HAVE MANUFACTURED STITCHED LOOPS FOR 2 INCHES X 2 INCHES POST INSTALLATION.
5. SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY PROTECTED AND STABILIZED, OR AS DIRECTED BY OWNER'S REPRESENTATIVE.





NOTE:
INDIVIDUAL SHEET WEIGHT
45 LBS PER LINEAR FOOT



2
7

TYPICAL DETAIL - TEMPORARY SHEET PILE COFFERDAM
NOT TO SCALE



3
7

TURBIDITY CURTAIN DETAILS
NOT TO SCALE



CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA




501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

EROSION & SEDIMENT CONTROL

SHEET

7 of 34



LEGEND


- SURVEY CONTROL POINT
- EXISTING 2-FT CONTOURS
- APPX. PROPERTY LINE
- ORDINARY HIGH WATER (EXISTING CONDITIONS, APPX 1-YR FLOOD)
- EXISTING ACCESS
- DELINEATED WETLAND (INTER-FLUVE 2024)
- EXISTING LEVEE
- RIVER MILE


SURVEY CONTROL

POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
301	362984.38	1571766.26	1225.60	REBAR
400	360579.25	1570298.45	1251.77	REBAR
405	360848.10	1570611.76	1252.15	REBAR
406	360985.11	1570635.74	1244.83	NAIL
407	361718.91	1571108.95	1239.54	NAIL
408	362003.88	1571211.51	1236.58	NAIL
423	361812.15	1571134.71	1238.18	NAIL
424	361203.16	1570924.00	1244.97	NAIL
425	361254.92	1570969.18	1244.67	NAIL
426	360920.65	1570795.28	1242.33	NAIL
427	360945.94	1570751.56	1242.20	NAIL







EXPIRES: 11/23/2025







LEGEND

- PROPERTY LINE
- RIVER MILE 42.0
- 600+00 PROPOSED CHANNEL ALIGNMENT
- EXISTING 2 FT CONTOURS
- PROPOSED 1 FT CONTOURS
- EXISTING ORDINARY HIGH WATER
- LIMITS OF DISTURBANCE
- PROPOSED ACCESS
- PROPOSED LEVEE REMOVAL AREA
- COFFERDAM
- TYPE 1 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL 1/22
- TYPE 2 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL 2/22
- TYPE 1 BANK BURIED WOOD STRUCTURE, SEE DETAIL 1/21
- TYPE 2 BANK BURIED WOOD STRUCTURE, SEE DETAIL 2/21
- APEX STRUCTURE/CHANNEL PLUG, SEE DETAIL 1/23
- SIDE CHANNEL INLET STRUCTURE, SEE DETAIL 2/20



SECTION- LEVEE REMOVAL A

NOTE:
1.REMOVE LEVEE TO TIE INTO
EXISTING WEST-SIDE
FLOODPLAIN GRADE



LEVEE REMOVAL A PROFILE




NO.	BY	DATE	REVISION DESCRIPTION	BB	PL, DM, JB, NS	PL, JB, MB
				DRAWN	DESIGNED	CHECKED
				PL, DM, EA	05/09/2025	23-02-21
				APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA




501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

PROPOSED CONDITIONS (1 OF 5)




EXPIRES: 11/23/2025



- SUGGESTED SEQUENCE:
1. CONSTRUCT NEW MAIN STEM, SIDE CHANNEL AND INSET FLOODPLAIN
 2. INSTALL TEMPORARY CROSSING
 3. INSTALL COFFER DAM, PLUG AND FILL EXISTING CHANNEL

LEGEND

- PROPERTY LINE
- RIVER MILE
- PROPOSED CHANNEL ALIGNMENT
- EXISTING 2 FT CONTOURS
- PROPOSED 1 FT CONTOURS
- EXISTING ORDINARY HIGH WATER
- LIMITS OF DISTURBANCE
- PROPOSED ACCESS
- REMEANDERED MAINSTEM
- PROPOSED HIGH-FLOW SIDE CHANNEL
- PROPOSED LEVEE REMOVAL AREA
- WILLOW TRENCH ROUGHNESS SEE DETAIL (1/24)
- HORIZONTAL LOG ROUGHNESS SEE DETAIL (1/25)
- PILES AND SLASH ROUGHNESS SEE DETAIL (2/25)
- PARTIAL CHANNEL FILL AREA
- PROPOSED ALCOVE
- PROPOSED STAGING AREA
- TEMPORARY BRIDGE
- COFFERDAM
- TYPE 1 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL (1/22)
- TYPE 2 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL (2/22)
- TYPE 1 BANK BURIED WOOD STRUCTURE, SEE DETAIL (1/21)
- TYPE 2 BANK BURIED WOOD STRUCTURE, SEE DETAIL (2/21)
- APEX STRUCTURE/CHANNEL PLUG, SEE DETAIL (1/23)
- SIDE CHANNEL INLET STRUCTURE, SEE DETAIL (2/20)



NO.				BY	DATE	REVISION DESCRIPTION
				BB	PL, DM, JB, NS	PL, JB, MB
				DRAWN	DESIGNED	CHECKED
				PL, DM, EA	05/09/2025	23-02-21
				APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

PROPOSED CONDITIONS (2 OF 5)

SHEET
11 OF 34




MATCH LINE SHEET 11

MATCH LINE SHEET 13


- SUGGESTED SEQUENCE:
1. CONSTRUCT NEW MAIN STEM, SIDE CHANNEL AND INSET FLOODPLAIN
 2. INSTALL TEMPORARY CROSSING
 3. INSTALL COFFER DAM, PLUG AND FILL EXISTING CHANNEL

LEGEND


- PROPERTY LINE
- RIVER MILE
- PROPOSED CHANNEL ALIGNMENT
- EXISTING 2 FT CONTOURS
- PROPOSED 1 FT CONTOURS
- EXISTING ORDINARY HIGH WATER
- LIMITS OF DISTURBANCE
- PROPOSED ACCESS
- REMEANDERED MAINSTEM
- PROPOSED HIGH-FLOW SIDE CHANNEL
- PROPOSED LEVEE REMOVAL AREA
- PARTIAL CHANNEL FILL AREA
- PROPOSED ALCOVE
- PROPOSED STAGING AREA
- TEMPORARY BRIDGE
- COFFERDAM
- TYPE 1 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL (1/22)
- TYPE 2 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL (2/22)
- TYPE 1 BANK BURIED WOOD STRUCTURE, SEE DETAIL (1/21)
- TYPE 2 BANK BURIED WOOD STRUCTURE, SEE DETAIL (2/21)
- APEX STRUCTURE/CHANNEL PLUG, SEE DETAIL (1/23)
- SIDE CHANNEL INLET STRUCTURE, SEE DETAIL (2/20)



SCALE: 1" = 10'
10x VERTICAL EXAGGERATION



- WILLOW TRENCH ROUGHNESS SEE DETAIL (1/24)
- HORIZONTAL LOG ROUGHNESS SEE DETAIL (1/25)
- PILES AND SLASH ROUGHNESS SEE DETAIL (2/25)



NO.				BY				DATE				REVISION DESCRIPTION			
BB				PL, DM, JB, NS				PL, JB, MB							
DRAWN				DESIGNED				CHECKED							
PL, DM, EA				05/09/2025				23-02-21							
APPROVED				DATE				PROJECT							

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA





501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

PROPOSED CONDITIONS (3 OF 5)


SHEET

12 OF 34





- LEGEND**
- PROPERTY LINE
 - RIVER MILE
 - PROPOSED CHANNEL ALIGNMENT
 - EXISTING 2 FT CONTOURS
 - PROPOSED 1 FT CONTOURS
 - EXISTING ORDINARY HIGH WATER
 - LIMITS OF DISTURBANCE
 - PROPOSED ACCESS
 - PROPOSED HIGH-FLOW SIDE CHANNEL
 - TEMPORARY BRIDGE
 - HORIZONTAL LOG ROUGHNESS
SEE DETAIL $\frac{1}{25}$
 - TYPE 1 CHANNEL SPANNING WOOD STRUCTURE, SEE DETAIL $\frac{1}{22}$
 - TYPE 1 BANK BURIED WOOD STRUCTURE, SEE DETAIL $\frac{1}{21}$
 - TYPE 2 BANK BURIED WOOD STRUCTURE, SEE DETAIL $\frac{2}{21}$



NO.	BY	DATE	REVISION DESCRIPTION


BB DRAWN	PL, DM, JB, NS DESIGNED	PL, JB, MB CHECKED
PL, DM, EA APPROVED	05/09/2025 DATE	23-02-21 PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA




501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com


PROPOSED CONDITIONS (5 OF 5)




SIDE CHANNEL 1 PROFILE



SIDE CHANNEL 2 PROFILE




SIDE CHANNEL 3 PROFILE



SIDE CHANNEL 4 PROFILE

NOTE: END OF SIDE CHANNEL
ALIGNMENTS REPRESENT
TIE-IN TO PROPOSED MAIN
STEM



LEGEND

----- EXISTING GRADE
————— PROPOSED GRADE



EXPIRES: 11/23/2025

NO.	BY	DATE	REVISION DESCRIPTION

BB	PL, DM, JB, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

PROPOSED HIGH FLOW SIDE
CHANNEL 1-4 PROFILES

SHEET
15 OF 34




EXISTING GRADE

PROPOSED GRADE




CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA




SHEET


16 OF 34



SECTION - HIGH FLOW SIDE CHANNEL 6



SECTION - HIGH FLOW SIDE CHANNEL 5



SECTION - MAINSTEM STA 62+75


1x VERTICAL EXAGGERATION
SCALE: 1" = 10'


LEGEND

--- EXISTING GRADE
— PROPOSED GRADE




EXPIRES: 11/23/2025

				<div>BB DRAWN</div> <div>PL, DM, EA</div> <div>APPROVED</div>	<div>PL, DM, JB, NS</div> <div>DESIGNED</div> <div>DATE</div>	<div>PL, JB, MB</div> <div>CHECKED</div> <div>23-02-21</div> <div>PROJECT</div>	<div>CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION</div> <div>TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2</div> <div>WHITE SWAN, WA</div>	<div></div> <div>501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com</div>	<div>GRADING SECTIONS (1 OF 3)</div>	<div>SHEET</div> <div>17 OF 34</div>
		</								




SECTION - HIGH FLOW SIDE CHANNEL 4



SECTION - MAINSTEM STA 71+89

SCALE: 1" = 10'
1x VERTICAL EXAGGERATION
SCALE: 1" = 10'




SECTION - MAINSTEM STA 74+61






LEGEND

----- EXISTING GRADE
————— PROPOSED GRADE



EXPIRES: 11/23/2025

				<div>BB DRAWN</div> <div>PL, DM, EA APPROVED</div>			<div>PL, DM, JB, JB, NS DESIGNED</div> <div>05/09/2025 DATE</div>			<div>PL, JB, MB CHECKED</div> <div>23-02-21 PROJECT</div>			CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2 WHITE SWAN, WA				<div></div> <div>501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com</div>			GRADING SECTIONS (2 OF 3)			SHEET 18 OF 34	



1x VERTICAL EXAGGERATION
SCALE: 1" = 10'

LEGEND

--- EXISTING GRADE
— PROPOSED GRADE



EXPIRES: 11/23/2025

NO.	BY	DATE	REVISION DESCRIPTION
1	BB	05/09/2025	DESIGNED
2	PL, DM, EA	05/09/2025	APPROVED
3	PL, DM, EA	05/09/2025	APPROVED
4	PL, DM, EA	05/09/2025	APPROVED
5	PL, DM, EA	05/09/2025	APPROVED
6	PL, DM, EA	05/09/2025	APPROVED
7	PL, DM, EA	05/09/2025	APPROVED
8	PL, DM, EA	05/09/2025	APPROVED
9	PL, DM, EA	05/09/2025	APPROVED
10	PL, DM, EA	05/09/2025	APPROVED
11	PL, DM, EA	05/09/2025	APPROVED
12	PL, DM, EA	05/09/2025	APPROVED
13	PL, DM, EA	05/09/2025	APPROVED
14	PL, DM, EA	05/09/2025	APPROVED
15	PL, DM, EA	05/09/2025	APPROVED
16	PL, DM, EA	05/09/2025	APPROVED
17	PL, DM, EA	05/09/2025	APPROVED
18	PL, DM, EA	05/09/2025	APPROVED
19	PL, DM, EA	05/09/2025	APPROVED
20	PL, DM, EA	05/09/2025	APPROVED
21	PL, DM, EA	05/09/2025	APPROVED
22	PL, DM, EA	05/09/2025	APPROVED
23	PL, DM, EA	05/09/2025	APPROVED
24	PL, DM, EA	05/09/2025	APPROVED
25	PL, DM, EA	05/09/2025	APPROVED
26	PL, DM, EA	05/09/2025	APPROVED
27	PL, DM, EA	05/09/2025	APPROVED
28	PL, DM, EA	05/09/2025	APPROVED
29	PL, DM, EA	05/09/2025	APPROVED
30	PL, DM, EA	05/09/2025	APPROVED
31	PL, DM, EA	05/09/2025	APPROVED
32	PL, DM, EA	05/09/2025	APPROVED
33	PL, DM, EA	05/09/2025	APPROVED
34	PL, DM, EA	05/09/2025	APPROVED
35	PL, DM, EA	05/09/2025	APPROVED
36	PL, DM, EA	05/09/2025	APPROVED
37	PL, DM, EA	05/09/2025	APPROVED
38	PL, DM, EA	05/09/2025	APPROVED
39	PL, DM, EA	05/09/2025	APPROVED
40	PL, DM, EA	05/09/2025	APPROVED
41	PL, DM, EA	05/09/2025	APPROVED
42	PL, DM, EA	05/09/2025	APPROVED
43	PL, DM, EA	05/09/2025	APPROVED
44	PL, DM, EA	05/09/2025	APPROVED
45	PL, DM, EA	05/09/2025	APPROVED
46	PL, DM, EA	05/09/2025	APPROVED
47	PL, DM, EA	05/09/2025	APPROVED
48	PL, DM, EA	05/09/2025	APPROVED
49	PL, DM, EA	05/09/2025	APPROVED
50	PL, DM, EA	05/09/2025	APPROVED
51	PL, DM, EA	05/09/2025	APPROVED
52	PL, DM, EA	05/09/2025	APPROVED
53	PL, DM, EA	05/09/2025	APPROVED
54	PL, DM, EA	05/09/2025	APPROVED
55	PL, DM, EA	05/09/2025	APPROVED
56	PL, DM, EA	05/09/2025	APPROVED
57	PL, DM, EA	05/09/2025	APPROVED
58	PL, DM, EA	05/09/2025	APPROVED
59	PL, DM, EA	05/09/2025	APPROVED
60	PL, DM, EA	05/09/2025	APPROVED
61	PL, DM, EA	05/09/2025	APPROVED
62	PL, DM, EA	05/09/2025	APPROVED
63	PL, DM, EA	05/09/2025	APPROVED
64	PL, DM, EA	05/09/2025	APPROVED
65	PL, DM, EA	05/09/2025	APPROVED
66	PL, DM, EA	05/09/2025	APPROVED
67	PL, DM, EA	05/09/2025	APPROVED
68	PL, DM, EA	05/09/2025	APPROVED
69	PL, DM, EA	05/09/2025	APPROVED
70	PL, DM, EA	05/09/2025	APPROVED
71	PL, DM, EA	05/09/2025	APPROVED
72	PL, DM, EA	05/09/2025	APPROVED
73	PL, DM, EA	05/09/2025	APPROVED
74	PL, DM, EA	05/09/2025	APPROVED
75	PL, DM, EA	05/09/2025	APPROVED
76	PL, DM, EA	05/09/2025	APPROVED
77	PL, DM, EA	05/09/2025	APPROVED
78	PL, DM, EA	05/09/2025	APPROVED
79	PL, DM, EA	05/09/2025	APPROVED
80	PL, DM, EA	05/09/2025	APPROVED
81	PL, DM, EA	05/09/2025	APPROVED
82	PL, DM, EA	05/09/2025	APPROVED
83	PL, DM, EA	05/09/2025	APPROVED
84	PL, DM, EA	05/09/2025	APPROVED
85	PL, DM, EA	05/09/2025	APPROVED
86	PL, DM, EA	05/09/2025	APPROVED
87	PL, DM, EA	05/09/2025	APPROVED
88	PL, DM, EA	05/09/2025	APPROVED
89	PL, DM, EA	05/09/2025	APPROVED
90	PL, DM, EA	05/09/2025	APPROVED
91	PL, DM, EA	05/09/2025	APPROVED
92	PL, DM, EA	05/09/2025	APPROVED
93	PL, DM, EA	05/09/2025	APPROVED
94	PL, DM, EA	05/09/2025	APPROVED
95	PL, DM, EA	05/09/2025	APPROVED
96	PL, DM, EA	05/09/2025	APPROVED
97	PL, DM, EA	05/09/2025	APPROVED
98	PL, DM, EA	05/09/2025	APPROVED
99	PL, DM, EA	05/09/2025	APPROVED
100	PL, DM, EA	05/09/2025	APPROVED

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA





501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com


GRADING SECTIONS (3 OF 3)

SHEET


19 OF 34



				<div>BB DRAWN</div>	<div>PL, DM, JB, NS DESIGNED</div>	<div>PL, JB, MB CHECKED</div>	<div>CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2 WHITE SWAN, WA</div>	<div><div>501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com</div></div>	<div>TYPICAL DETAILS CHANNEL REMEANDER-PARTIAL PLUG</div>	SHEET
			<div>PL, DM, EA APPROVED</div>	<div>05/09/2025 DATE</div>	<div>23-02-21 PROJECT</div>	20 OF 34				
NO.	BY	DATE	REVISION DESCRIPTION							




PLAN




SECTION A-A

1
21 TYPICAL DETAIL -TYPE 1 BANK BURIED WOOD STRUCTURE
NOT TO SCALE

- DEWATERING NOTES:
- A CONSTRUCTION DEWATERING SUMP. CONTRACTOR SHALL PROVIDE PUMP TO DRAW DOWN WATER LEVEL SUFFICIENTLY FOR PLACEMENT OF LWM, AND CONTAIN TURBID WATER.
 - B CONSTRUCTION DEWATERING DISCHARGE LOCATION. CONTROL DISCHARGE TO PREVENT EROSION AND RETURN OF TURBID WATER TO SURFACE WATERS.



PLAN



SECTION B-B

2
21 TYPICAL DETAIL -TYPE 2 BANK BURIED WOOD STRUCTURE
NOT TO SCALE



EXPIRES: 11/23/2025

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com


LARGE WOOD TYPICAL DETAILS-
BANK BURIED WOOD

SHEET
21 OF 34

BB	PL, DM, JB, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT


NO.	BY	DATE	REVISION DESCRIPTION

BURY 15FT LENGTH OF LOG IN TRENCH WITH COBBLE/GRAVEL STREAM BED MATERIAL TO 2FT DEPTH OF COVER .



PLAN

ROOTWADS SET INTO BED SO TRUNKS ARE PLACED ALONG THE CHANNEL BED




BURY 15FT LENGTH OF LOG IN TRENCH WITH COBBLE/GRAVEL STREAM BED MATERIAL TO 2FT DEPTH OF COVER .

SECTION


1 TYPICAL DETAIL - TYPE 1 CHANNEL SPANNING LARGE WOOD STRUCTURE
22 NOT TO SCALE

CHANNEL TOP, TYP



PLAN


ROOTWADS SET INTO BED SO TRUNKS ARE PLACED ALONG THE CHANNEL BED



BURY 15FT LENGTH OF LOG IN TRENCH WITH COBBLE/GRAVEL STREAM BED MATERIAL TO 2FT DEPTH OF COVER .

SECTION

2 TYPICAL DETAIL - TYPE 2 CHANNEL SPANNING LARGE WOOD STRUCTURE
22 NOT TO SCALE



NO.	BY	DATE	REVISION DESCRIPTION


BB	PL, DM, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

LARGE WOOD TYPICAL DETAILS-
CHANNEL SPANNING




1
17
TYPICAL DETAIL - PLAN
APEX STRUCTURE
NOT TO SCALE

SEQUENCE:

1. INSTALL COFFERDAM, IF REQUIRED.
2. EXCAVATE PIT WORKING FROM ONE SIDE A MINIMAL WIDTH NECESSARY TO INSTALL PILES AND FIRST TIER OF LOGS. PROCEED ACROSS PIT USING EXCAVATED MATERIAL AS BACKFILL ON PLACED LOGS PARTIALLY BURYING LOGS TO PREVENT FLOATATION.
3. INSTALL ADDITIONAL LAYERS OF LOGS AND BACKFILL EACH LAYER. PLACE COTTONWOOD POLES WHILE BACKFILLING. PUMP AS NEEDED.
4. DO NOT FILL IN FRONT OF STRUCTURE. APPLY SURPLUS FILL TO TOP OF STRUCTURE.
5. INSTALL SMALL TREES AND SLASH IN ROOTWAD MATRIX. DO NOT DAMAGE ROOTWADS.
6. REMOVE COFFERDAM.

NOTES:

1. SPECIFIC ORIENTATION OF LOGS AND BALLAST MATERIALS MAY VARY FROM TYPICAL DRAWINGS DEPENDING ON SITE CONDITIONS & SIZE/SHAPE OF MATERIAL DELIVERED OR SALVAGED AT SITE.
2. LOGS SHALL BE BALLASTED TO RESIST BUOYANCY BY PARTIAL BURIAL AND BRACING TO WOODEN PILES.
3. BOLT HORIZONTAL LOGS TO LOG PILES PER DETAIL.



2
17
TYPICAL DETAIL - PROFILE
APEX STRUCTURE
NOT TO SCALE

VIBRATORY PILE DRIVING:


DESCRIPTION
THIS WORK CONSISTS OF INSTALLING LOG PILES WHERE SHOWN ON THE PLANS.

MATERIALS
WOODEN PILES SHALL BE LOGS WITH 15\"/>

CONSTRUCTION
FINAL POSITIONING OF LOG PILES SHALL BE IN THE APPROXIMATE LOCATIONS SHOWN ON THE PLANS. EACH PILE SHALL BE INSTALLED TO A DEPTH EXCEEDING 15' BELOW BOTTOM OF PIT. VARY LENGTHS EXTENDING ABOVE FINISHED GRADE FROM 3FT TO 6FT. TOP ENDS SHALL BE SNAPPED BEFORE INSTALLATION OR ROUGHENED TO REMOVE CUT END.

QUANTITIES ESTIMATE:

- | | |
|---|-----------------------------------|
| 1. 18\"/> | 12 EACH |
| 2. 12-15\"/> | 12 EACH |
| 3. EXCAVATION (BELOW OHW) | APPROX 200 CY |
| 4. FILL (BELOW OHW, SALVAGED EXCAVATION MATERIAL) | APPROX 200 CY |
| 5. SMALL WOODY DEBRIS/SLASH | APPROX 20 CY MODERATELY COMPACTED |
| 6. BOULDERS | 12 |



BOLTED CONNECTION NOTES:

1. BOLTS SHALL BE MINIMUM 1 1/4\"/>
2. DRILL 1 3/8\"/>
3. INSERT THREADBAR.
4. INSTALL PLATE WASHERS AND NUTS. SECURE NUTS BY CHISELING THREADS.
5. FILE OR GRIND OFF SHARP EDGES.
6. EACH MAINSTEM STRUCTURE SHALL HAVE AT LEAST 6 THREADBAR CONNECTIONS.

3
17
TYPICAL LOG-LOG CONNECTIONS
NOT TO SCALE



EXPIRES: 11/23/2025

BB	PL, DM, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

LARGE WOOD TYPICAL DETAILS-
APEX STRUCTURE

SHEET

23 OF 34

DIG TRENCH WITH EXCAVATOR.
MAINTAIN SLOPE AS VERTICAL AS
POSSIBLE. MAXIMUM TRENCH WIDTH 2'.

STEP 1

FLOW

TRENCH DEPTH TO EXTEND
A MINIMUM OF 1-FT BELOW
GROUNDWATER ELEVATION

BACKFILL WITH NATIVE SUBSTRATE

LIVE CUTTINGS, SEE SHEET 31

EXCAVATION EXTENTS

TRENCH DEPTH TO EXTEND A
MINIMUM OF 1-FT. BELOW
GROUNDWATER ELEVATION

SECTION

FLOW

2. LAY 3-6 PIECES OF SLASH PER LINEAR
FOOT IN TRENCH (APPROXIMATELY 1 CY
OF SLASH FOR A 20FT WILLOW TRENCH)

STEP 2

1. PUSH SOIL FIRMLY AND CAREFULLY AGAINST INSTALLED
LIVE CUTTINGS. SLUICE WITH WATER TO SETTLE SOIL AND
REMOVE AIR POCKETS NEAR CUTTINGS. COMPACT BACKFILL
IN 12 INCH LIFTS TO IMPROVE CUTTING TO SOIL CONTACT.

NOTES:

1. ALL LIVE CUTTINGS TO BE CUT TO A POINT IMMEDIATELY PRIOR TO INSTALLATION
2. EXCAVATE TRENCH TO 1 FT BELOW WATER TABLE DEPTH. PUMP WATER INTO TRENCH. INSTALL LIVE CUTTINGS WITH CUT ENDS IN TOE OF TRENCH.
3. COMPACT BACKFILL IN 12 INCH LIFTS TO IMPROVE CUTTING TO BACKFILL MATERIAL CONTACT.
4. PUMP WATER IN O THE TRENCH WHILE BACKFILLING UNTIL WATER VISIBLE "BUBBLES" ON SURFACE
5. TAMP IN MATERIAL AT GROUND AROUND LIVE CUTTING.
6. MAINTAIN TRENCH EXCAVATION AS CLOSE TO VERTICAL AS THE SOIL WILL ALLOW TO MINIMIZE OVERALL DISTURBANCE FOOTPRINT.

SLUICE WITH WATER TO SETTLE SOIL AND
REMOVE AIR POCKETS NEAR CUTTINGS.

FILL OVER SLASH TO FINISHED GRADE, TAKING CARE TO
AVOID DAMAGING LIVE CUTTINGS

STEP 3

CLIP LIVE CUTTINGS SO THAT
3-6 INCHES REMAINS ABOVE
FINISHED GRADE

20-30 FOOT LONG EXCAVATED TRENCH
ORIENTED PERPENDICULAR TO
DOMINANT FLOW DIRECTION, TYP

15' TRENCH
SPACING, TYP.

INSTALL 1 LIVE CUTTING EVERY TWO FEET AND 3-6 PIECES
OF SLASH PER LINEAR FOOT

4-5'
TRENCH
OVERLAP

WILLOW TRENCH ROUGHNESS ZONE (SEE PLAN)

PLAN

NOT TO SCALE

FLOW

SEQUENCE

1
24

WILLOW TRENCH TYPICAL DETAIL

NOT TO SCALE



TRENCH INSTALLATION



COMPLETED TRENCH



EXPIRES: 11/23/2025

BB	PL, DM, JB, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA





501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

TYPICAL DETAILS- FLOODPLAIN
ROUGHNESS (1 OF 2)

SHEET


24 OF 34



MACHINE PLACED ANGLED PILE NOTES:

1. ANGLED PILES TO BE MECHANICALLY DRIVEN WITH VIBRATORY PILE DRIVER INTO UNDISTURBED EARTH TO MIN. 6' DEPTH OR UNTIL REFUSAL AS DIRECTED BY C.O. INSTALLATION BY EXCAVATION ONLY THROUGH PRIOR APPROVAL OF YRWP.
2. AFTER FINISH GRADE HAS BEEN ESTABLISHED, CUT ANGLED PILE SO THAT NO MORE THAN 3 FT. OF PILE EXTENDS ABOVE TOP OF LOG, PER YRWP MAR CUT ENDS OF ANGLED PILE FOR "NATURAL" APPEARANCE.
3. ANGLED PILES SHALL HAVE MINIMUM LENGTH OF 10'.
4. DRIVE PILES AT THE ANGLE SHOWN WHERE ACCESS BY EXCAVATOR AND/OR SUBSTRATE ALLOWS TO PREVENT LOGS FROM FLOATING.

1
25 HORIZONTAL LOG WITH ANGLED VERTICAL LOG BALLAST TYPICAL DETAIL
NOT TO SCALE



2
25 PILES WITH SLASH TYPICAL DETAIL
NOT TO SCALE



EXPIRES: 11/23/2025

NO.	BY	DATE	REVISION DESCRIPTION

BB	PL, DM, JB, JB, NS	PL, JB, MB
DRAWN	DESIGNED	CHECKED
PL, DM, EA	05/09/2025	23-02-21
APPROVED	DATE	PROJECT

CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION
TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2
WHITE SWAN, WA



501 Portway Avenue, Suite 101
Hood River, OR 97031
541.386.9003
www.interfluve.com

TYPICAL DETAILS- FLOODPLAIN
ROUGHNESS (2 OF 2)

SHEET
25 OF 34

LOG PILES

ALL LOG PILES SHALL BE INSTALLED USING VIBRATORY PILE DRIVING EQUIPMENT. INSTALLATION BY HAMMERING OR VIBRATORY PLATE COMPACTOR SHALL NOT BE ALLOWED.

IF SITE CONDITIONS DO NOT PERMIT VIBRATORY DRIVING AS DETERMINED BY YRWP, INSTALLATION BY EXCAVATION MAY BE PERMITTED WITH WRITTEN AUTHORIZATION BY YRWP

ACCEPTABLE MINIMUM VIBRATORY PILE DRIVING EQUIPMENT SHALL INCLUDE: HMC MOVAX SONIC SIDE GRIP VIBRATORY PILE DRIVER - MODEL SP80, GRIZZLY MG90, OR EQUIVALENT.

LOG PILES SHALL BE A MAXIMUM OF 16" DIAMETER AT BREAST HEIGHT, WITH NO BARK.

RIGGING

RIGGING FOR LOG PILE TESTING SHALL CONFORM TO THE TENSION SCALE MANUFACTURER'S RECOMMENDATIONS.

CHOKERS, CABLES AND AND SHACKLES SHALL HAVE MINIMUM WORKING LOAD RATING OF 12 TONS. FITTINGS SHALL BE SIZED ACCORDINGLY

TESTING

TESTING OF LOG PILES SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER.

EACH LOG PILE TEST SHALL HAVE UPWARD LOAD GRADUALLY INCREASED AND AS CLOSELY ALIGNED TO AXIS OF LOG PILE AS POSSIBLE. RECORD THE LOG PILE DIAMETER, EMBEDMENT DEPTH AND MAXIMUM FORCE REQUIRED TO MOVE THE LOG PILE. UP TO A TOTAL OF THREE LOADINGS MAY BE REQUIRED AT EACH EMBEDMENT DEPTH.


PROOF TESTS SHALL BE MADE AT UP TO FOUR EMBEDMENT DEPTHS TO BE DETERMINED IN THE FIELD. AS A GUIDELINE TEST EMBEDMENT DEPTHS MAY INCLUDE 6', 8', 10', AND 12'.

EXCAVATOR CONDUCTING PULL OUT LOADING SHALL BE POSITIONED NO CLOSER THAN EMBEDMENT DEPTH OF LOG PILE IF POSSIBLE. IF A CLOSER POSITIONING IS REQUIRED, EXCAVATOR SHALL BE NO CLOSER THAN THAT REQUIRED TO GENERATE DESIRED LOADING WITH DISTANCE FROM LOG PILE NOTED IN THE TEST RECORD.

PULL OUT RESISTANCE READING SHALL BE COMPARED AGAINST EXCAVATOR MAX LIFT OFFSET TABLE.


2 LOG PILES PER LOG JAM AND 5% OF LOG PILES IN PILE FIELDS SHALL BE PROOF TESTED. IF RESULTS VARY MORE THAN 50% THEN IT SHOULD BE ANTICIPATED THAT UP TO 25% OF THE PRODUCTION LOG PILES SHALL BE PROOF TESTED.


CONSTRUCTED DRIVEN LOG PILE EMBEDMENT DEPTH SPECIFIED IN THE PLANS MAY BE REDUCED OR INCREASED, PENDING PULL OUT TEST RESULTS, AT NO ADDITIONAL COST.




1 LOG PILE PULLOUT TESTING
26 NOT TO SCALE






				BB DRAWN	PL, DM, JB, JB, NS DESIGNED	PL, JB, MB CHECKED	CONFEDERATED TRIBES AND BANDS OF THE YAKAMA NATION TOPPENISH THREE WAY LEVEE REMOVAL PHASE 2 WHITE SWAN, WA	 501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com	REVEGETATION PLAN (1 OF 3)	SHEET
				PL, DM, EA APPROVED	05/09/2025 DATE	23-02-21 PROJECT				27 OF 34
NO.	BY	DATE	REVISION DESCRIPTION							



LEGEND

- | | | | |
|--------|---|--|---|
| ----- | PROPERTY LINE | | |
| ● 42.0 | RIVER MILE | | |
| ----- | EXISTING ACCESS | | |
| ----- | PROPOSED ACCESS | | |
| ----- | PROPOSED CHANNEL ALIGNMENT | | |
| ----- | EXISTING 2 FT CONTOURS | | |
| 600+00 | PROPOSED 1 FT CONTOURS | | |
| ----- | LIMITS OF DISTURBANCE | | |
| | OVERBANK SEED AND LIVE PLANTS (10.0 ACRES) | | WILLOW TRENCH ROUGHNESS SEE DETAIL (1/24) |
| | TRANSITIONAL/ UPLAND SEED AND LIVE PLANTS (5.5 ACRES) | | HORIZONTAL LOG ROUGHNESS SEE DETAIL (1/25) |
| | TRANSITIONAL/ UPLAND SEED ONLY (2.5 ACRES) | | PILES AND SLASH ROUGHNESS SEE DETAIL (2/25) |
| | WILLOW BANK INSTALLATION | | |



LEGEND

- | | |
|--------|---|
| --- | PROPERTY LINE |
| ● 42.0 | RIVER MILE |
| --- | EXISTING ACCESS |
| --- | PROPOSED ACCESS |
| --- | PROPOSED CHANNEL ALIGNMENT |
| --- | EXISTING 2 FT CONTOURS |
| 600+00 | PROPOSED 1 FT CONTOURS |
| --- | LIMITS OF DISTURBANCE |
| XXXXXX | OVERBANK SEED AND LIVE PLANTS (10.0 ACRES) |
| XXXXXX | TRANSITIONAL/ UPLAND SEED AND LIVE PLANTS (5.5 ACRES) |
| XXXXXX | TRANSITIONAL/ UPLAND SEED ONLY (2.5 ACRES) |
| --- | WILLOW BANK INSTALLATION |
- | | |
|--------------------------------------|--------|
| WILLOW TRENCH ROUGHNESS SEE DETAIL | (1/24) |
| HORIZONTAL LOG ROUGHNESS SEE DETAIL | (1/25) |
| PILES AND SLASH ROUGHNESS SEE DETAIL | (2/25) |

SEED AND PLANT LISTS

Overbank Seeding		
Botanical Name	Common Name	% Composition By Weight
<i>Hordeum brachyantherum</i>	meadow barley	60%
<i>Scirpus microcarpus</i>	panicked bulrush	10%
<i>Elymus glaucus</i>	blue wildrye	10%
<i>Leymus cinereus</i>	basin wildrye	10%
<i>Juncus balticus</i>	baltic rush	5%
<i>Eleocharis palustris</i>	spike sedge	5%
<i>Carex stipata</i>	awl-fruited sedge	5%

NOTES:

1. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE SEEDED AND STRAWED WITHIN 3 DAYS OF WORK AREA COMPLETION. AREA OF THE OVERBANK REVEGETATION ZONE IS 10.0 ACRES.
2. BROADCAST SEED AT A RATE OF 30 LBS PER ACRE. A TOTAL OF 300 LBS OF SEED WILL BE REQUIRED.
3. SEED MIX TO BE APPLIED WITH 50:50 RICE HULLS (BY VOLUME) TO FACILITATE EVEN DISTRIBUTION.
4. STRAW MULCH TO BE APPLIED AT A RATE OF 2 TONS/ ACRE. LEAVE APPROXIMATELY 25% OF THE GROUND SURFACE VISIBLE THROUGH THE MULCH OVER ALL DISTURBED AREAS.
5. STRAW MULCH IS CONSIDERED INCIDENTAL TO SEEDING.

Transitional/ Upland Seeding		
Botanical name	Common Name	% Composition By Weight
<i>Hordeum brachyantherum</i>	meadow barley	15%
<i>Elymus glaucus</i>	blue wildrye	15%
<i>Leymus cinereus</i>	basin wildrye	35%
<i>Achillea millefolium</i>	yarrow	1%
<i>Lomatium papilioniferum</i>	desert parsley	2%
<i>Eriophyllum lanatum</i>	woolly sunflower	2%
<i>Lupinus rivularis</i>	River lupine	5%
<i>Pseudoroegneria spicata</i>	bluebunch wheatgrass	25%

NOTES:

1. ALL AREAS IMPACTED BY CONSTRUCTION SHALL BE SEEDED AND STRAWED WITHIN 3 DAYS OF WORK AREA COMPLETION. AREA OF THE TRANSITIONAL/ UPLAND REVEGETATION ZONE IS 8.0 ACRES.
2. BROADCAST SEED AT A RATE OF 30 LBS PER ACRE. A TOTAL OF 240 LBS OF SEED WILL BE REQUIRED.
3. SEED MIX TO BE APPLIED WITH 50:50 RICE HULLS (BY VOLUME) TO FACILITATE EVEN DISTRIBUTION.
4. STRAW MULCH ITO BE APPLIED AT A RATE OF 2 TONS/ ACRE. LEAVE APPROXIMATELY 25% OF THE GROUND SURFACE VISIBLE THROUGH THE MULCH OVER ALL DISTURBED AREAS.
5. STRAW MULCH IS CONSIDERED INCIDENTAL TO SEEDING.

Live Staking (roughness treatments, large wood structures, willow banks)					
Botanical name	Common name	Type	Size	Spacing	Quantity
<i>Salix exigua</i>	Coyote willow	Live stake	3/4" - 1-1/2" dia, 5-8 ft long	See treatment detail	1850
<i>Salix geyeriana</i>	Geyer's willow	Live stake	3/4" - 1-1/2" dia, 5-8 ft long	See treatment detail	1850
<i>Salix lasiandra</i>	Pacific willow	Live stake	3/4" - 1-1/2" dia, 5-8 ft long	See treatment detail	1850

NOTES:

- NOTES:
1. A TOTAL QUANTITY OF 5,500 LIVE WILLOW STAKES WILL BE REQUIRED. THE FRACTION OF THIS TOTAL OF EACH SPECIES MAY VARY, +/- 15%.
 2. LIVE WILLOW STAKES OF EACH SPECIES MUST BE SOURCED FROM MULTIPLE LOCATIONS TO INCREASE GENETIC DIVERSITY OF INSTALLED MATERIAL.

Overbank Live Plants					
Botanical name	Common Name	Type	Size	Spacing	Quantity
<i>Rosa woodsii</i>	Woods' rose	Tubeling	10 in3	6 ft o.c.	3025
<i>Ribes aureum</i>	golden currant	Tubeling	10 in3	6 ft o.c.	3025
<i>Alnus rhombifolia</i>	white alder	Tubeling	10 in3	6 ft o.c.	3025
<i>Philadelphus lewisii</i>	Lewis' mock orange	Tubeling	10 in3	6 ft o.c.	3025

NOTES:

1. PLANTING AREAS OVERLAP WITH ROUGHNESS TREATMENTS. LOCALIZED ADJUSTMENTS TO THE NEAREST APPROPRIATE LOCATION MAY BE MADE TO OPTIMIZE PLANTING CONDITIONS SUCH AS AVOIDING PLANTING ON LOGS, OTHER PLANTS, COMPACTED SLASH OR ROCK OUTCROPS.

Transitional/ Upland Live Plants					
Botanical name	Common Name	Type	Size	Spacing	Quantity
<i>Artemesia tridentata</i>	big sagebrush	Tubeling	10 in3	10 ft o.c.	1200
<i>Chrysothamnus viscidiflorus</i>	green rabbit-brush	Tubeling	10 in3	10 ft o.c.	1200

[illegible]

31 OF 34

PILES: CONSTRUCTION OF PILES SHALL INCLUDE ON-SITE MOVEMENT AND INSTALLATION OF PILES TO DESIGNATED SITES SHOWN IN THE PLANS. PILES SHALL BE PER THE APPROXIMATE NUMBERS AND QUANTITIES INDICATED ON THE PLANS. SPECIFIC LOCATIONS SHALL BE DETERMINED IN THE FIELD AND DIRECTED BY THE OWNER. THE REQUIRED EMBEDMENT DEPTH IS INDICATED ON THE PLANS. EACH PILE SHALL HAVE A "BROKEN TOP" BY STUMP-GRINDING OR MAKING MULTIPLE PLUNGE CUTS WITH CHAIN SAW TO PROVIDE A ROUGHENED OR RAGGED END. PILES SHALL BE OF VARYING HEIGHTS EXTENDING FROM 2 TO 5 FEET ABOVE FINISHED GRADE. ONE BOLT SHALL BE INSTALLED IN EACH PILE CONNECTING TO TOP LOG AS DETAILED IN THE PLANS.

PILES SHALL BE INSTALLED BY VIBRATORY PILE DRIVER MEETING OR EXCEEDING THE FOLLOWING CHARACTERISTICS:

- a. MINIMUM OF 800 KN (80 TONS) OF CENTRIFUGAL FORCE.
- b. SIDE GRIP WITH MINIMUM 16" SPACE BETWEEN ENDS OF JAWS SO THAT 16" DIAMETER LOG WILL FIT INTO THE JAWS WITHOUT NEEDING TO SLIDE THE GRIP OVER THE END AND DOWN THE LOG.
- c. PRE-APPROVED PILE DRIVERS INCLUDE: MOVAX SP-80, GRIZZLY MG90, OR EQUIVALENT.

TESTING: AT EACH LOG STRUCTURE SITE, A MINIMUM OF ONE PILE SHALL BE TESTED FOR PULLOUT RESISTANCE. EACH TEST WILL REQUIRE UP TO FOUR INDIVIDUAL PULLS, EACH AT A DEEPER DEPTH. SEE DETAILS IN PLANS. THE CONTRACTOR SHALL PROVIDE THE TENSION LINK, METER, AND ASSOCIATED HARDWARE (RATED 12 TON).

SLASH: SLASH SHALL BE INCORPORATED INTO LOG STRUCTURES AS SHOWN IN THE PLANS AND DIRECTED BY THE OWNER. INTERMINGLE, STACK, AND RACK SLASH MATERIAL TO THE INSTALLED LWM AND PILE TO EMULATE NATURAL ACCUMULATIONS OF WOOD MATERIAL.

SALVAGED TREE: ANY TREES CLEARED FOR ACCESS OR ALREADY DOWNED TREES IMMEDIATELY ADJACENT TO CONSTRUCTION SITE AND REQUIRING MOVEMENT FOR SITE ACCESS MAY BE INCORPORATED, AS DIRECTED BY THE OWNER. SALVAGED TREE TOPS MAY BE USED AS SLASH.

EARTHWORK: WHERE PARTIAL BURIAL OF LWM IS REQUIRED, EXCAVATE TO SUBGRADE AND STOCKPILE MATERIAL WITHIN THE DESIGNATED DISTURBANCE AREA. SORT MATERIALS BY GENERAL SIZES, SEPARATING PILES FOR COARSE AND FINE MATERIAL. BACKFILL THE LWM AS EACH LAYER IS INSTALLED. USE COARSE FILL ALONG EXTERIOR OF FILL ZONE AND ALONG WATERWARD EDGE, AND FINER MATERIALS WITHIN INTERIOR OF FILL ZONE. SILT AND SAND SHALL NOT BE USED FOR BACKFILL AND SHALL BE HAULED FROM THE SITE; CONTRACTOR SHALL SALVAGE OR IMPORT GRAVEL/COBBLE ALLUVIUM FOR BACKFILL AT NO ADDITIONAL COST. WHERE POOL EXCAVATION IS INCLUDED, EXCAVATED MATERIAL SHALL BE SALVAGED AND PLACED AS BACKFILL IN LWM STRUCTURE. BACKFILL ALONG WATERWARD EDGE SHALL BE LAYERED WITH SLASH WITH LIFTS NO THICKER THAN 18INCHES AND BUCKET COMPACTED. SLASH SHALL EXTEND 10FT MINIMUM INTO FILL. BACKFILL THE LOGS AS EACH LAYER IS INSTALLED.

WILLOW PLANTINGS SHALL BE INSTALLED IN LARGE WOOD STRUCTURES AND AS SHOWN ON PLANS AND DETAILS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT SHALL BE MADE PER EACH STRUCTURE FOR:

- ITEM 009 - TYPE 1 CHANNEL SPANNING STRUCTURE
- ITEM 010 - TYPE 2 CHANNEL SPANNING STRUCTURE

- ITEM 011 - TYPE 1 BANK BURIED STRUCTURE
- ITEM 012 - TYPE 2 BANK BURIED STRUCTURE
- ITEM 013 - APEX/ CHANNEL PLUG STRUCTURE
- ITEM 014- SIDE CHANNEL INLET LW STRUCTURE

THE CONTRACT PRICE SHALL BE FULL COMPENSATION FOR ALL COSTS INCURRED FOR EQUIPMENT, MATERIALS AND LABOR FOR HANDLING, LOADING AND HAULING LWM FROM STOCKPILE AREAS, EXCAVATING TO SUBGRADE, SELECTIVE HANDLING OF EXCAVATED MATERIALS AND BACKFILL, SALVAGE OR IMPORT OF SUITABLE BACKFILL MATERIAL, INSTALLING AND SECURING LWM, PILES, SLASH AND SALVAGED TREE TOPS AS OUTLINED IN THE PLANS. EARTHWORK, HAUL AND DISPOSAL OF SPOILS. INSTALLING SLASH AND SALVAGED TREES SHALL BE INCIDENTAL.

WILLOW PLANTINGS INCLUDED IN LARGE WOOD STRUCTURES SHALL BE INCIDENTAL TO LARGE WOOD STRUCTURES. STORAGE, WATERING, EXCAVATION, INSTALLATION AND BACKFILL AND ANY OTHER WORK NECESSARY TO INSTALL LIVE WILLOWS SHALL BE INCIDENTAL.

ITEM 015 FLOODPLAIN ROUGHNESS – WILLOW TRENCH

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF FLOODPLAIN ROUGHNESS – WILLOW TRENCH AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR FLOODPLAIN ROUGHNESS – WILLOW TRENCH SHALL BE PER LINEAL FOOT OF COMPLETED INSTALLATION.

ITEM 016 FLOODPLAIN ROUGHNESS – HORIZONTAL LOG

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF FLOODPLAIN ROUGHNESS – HORIZONTAL LOG AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR FLOODPLAIN ROUGHNESS – HORIZONTAL LOG SHALL BE PER LINEAL FOOT OF COMPLETED INSTALLATION.

ITEM 017 FLOODPLAIN ROUGHNESS – PILES AND SLASH

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF FLOODPLAIN ROUGHNESS – PILES AND SLASH AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR FLOODPLAIN ROUGHNESS – PILES AND SLASH SHALL BE PER ACRE OF COMPLETED INSTALLATION.

ITEM 018 OVERBANK SEED AND LIVE PLANTS

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF OVERBANK SEED AND LIVE PLANTS AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR OVERBANK SEED AND LIVE PLANTS SHALL BE PER ACRE OF COMPLETED INSTALLATION.

ITEM 019 TRANSITIONAL / UPLAND SEED AND LIVE PLANTS

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF TRANSITIONAL / UPLAND SEED AND LIVE PLANTS AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR TRANSITIONAL / UPLAND SEED AND LIVE PLANTS SHALL BE PER ACRE OF COMPLETED INSTALLATION.

ITEM 020 TRANSITIONAL / UPLAND SEED ONLY

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF TRANSITIONAL / UPLAND SEED ONLY AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR TRANSITIONAL / UPLAND SEED ONLY SHALL BE PER ACRE OF COMPLETED INSTALLATION.

ITEM 021 WILLOW BANK INSTALLATION

SHALL INCLUDE ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY FOR CARE, INSTALLATION AND MAINTENANCE OF WILLOW BANK INSTALLATION AS SHOWN IN THE PLANS.

MEASUREMENT AND PAYMENT

MEASUREMENT AND PAYMENT FOR WILLOW BANK INSTALLATION SHALL BE PER ACRE OF COMPLETED INSTALLATION.

OPTIONAL ADDITIVE ALTERNATE ITEMS

FOLLOWING ARE OPTIONAL ADDITIVE ALTERNATE ITEMS. OWNER SHALL DETERMINE IF ITEMS ARE REQUIRED, QUANTITIES AND LOCATIONS FOR PLACEMENTS. OWNER SHALL PROVIDE WRITTEN AUTHORIZATION TO IMPLEMENT THESE ITEMS PRIOR TO PROCUREMENT, TRANSPORT, HANDLING OR INSTALLATION.

ITEM 022 - JAM BALLAST BOULDERS

OWNER SHALL DETERMINE IF ADDITIONAL JAM BALLAST BOULDERS (BOULDERS) ARE REQUIRED. CONTRACTOR SHALL PROCURE AND IMPORT, HAUL AND PLACE BOULDERS. UNLESS NOTED HEREIN, BOULDERS SHALL MEET WSDOT STANDARD SPECIFICATION 9-13.1. BOULDERS SHALL BE MINIMUM 4FT EQUIVALENT DIAMETER WITH SPECIFIC GRAVITY OF 2.65 OR GREATER AND SHALL WEIGH NO LESS THAN 5,500 POUNDS DRY WEIGHT PER EACH. BOULDERS SHALL BE ROUNDED TO SUBANGULAR.

MEASUREMENT AND PAYMENT

JAM BALLAST BOULDERS SHALL BE MEASURED AND PAID FOR PER EACH BOULDER. PAYMENT WILL BE FULL COMPENSATION FOR ALL COSTS INCURRED FOR SALVAGE OR IMPORT OF BOULDERS, HAULING, STOCKPILING AND PLACING.

ITEM 023 - IMPORTED BOULDER BACKFILL

OWNER SHALL DETERMINE IF IMPORTED BOULDER BACKFILL IS REQUIRED FOR BACKFILL ON BANK BURIED LARGE WOOD STRUCTURES. THIS MATERIAL IS COMPRISED OF COBBLE TO MEDIUM SIZED BOULDERS. SOURCE IS TO BE DETERMINED. CONTRACTOR SHALL HAUL AND PLACE IMPORTED BOULDER BACKFILL BANK BURIED LARGE WOOD STRUCTURES AS DIRECTED BY ENGINEER.

MEASUREMENT AND PAYMENT

IMPORTED BOULDER BACKFILL SHALL BE MEASURED AND PAID FOR PER CUBIC YARD PLACED. PAYMENT WILL BE FULL COMPENSATION FOR ALL COSTS INCURRED FOR IMPORTED BOULDER BACKFILL, HAULING, STOCKPILING AND PLACING



Toppenish Creek 3-Way Levee Removal (Phase II)

Basis of Design Report

Appendix 7.5

Revegetation Specifications

May 2025

1 **SPECIFICATION**
2 **TOPPENISH CREEK THREE-WAY LEVEE REMOVAL AND RESTORATION – PHASE II**

3
4
5 **DIVISION 8**
6 **MISCELLANEOUS CONSTRUCTION**

7
8 **8-01 Erosion Control and Water Pollution Control**

9
10 **8-02 Roadside Restoration**

11
12 **8-02.3 Construction Requirements**

13
14 **8-02.3(2) Work Plans**

15 Section 8-02.3(2) is revised to read:

16 (*****)

17
18 Three Work Plan submittals under this section:

- 19 1. Restoration Work Plan: This plan is required when trees or native vegetation will be
20 removed. The Contractor shall submit a Type 3 Working Drawing within 15 calendar days
21 prior to any earth disturbing activities.
22 2. Weed Control Plan: The Contractor shall submit for approval the Weed Control Plan as a
23 Type 3 Working Drawing. The plan shall be submitted at the same time as the
24 Revegetation Work Plan. The plan will require approval prior to beginning the following
25 additional activities: selective clearing, surface preparation, application of chemical
26 herbicides, or any weed control activities.
27 3. Plant Establishment Plan: This plan is required prior to completion of Initial Planting. See
28 8-02.3(2)C Plant Establishment Plan.
29

30
31 **8-02.3(2)A Roadside Work Plan**

32 Section 8-02.3(2)A is revised to read:

33 (*****)

34
35 **8-02.3(2)A Revegetation Work Plan**

36
37 The Revegetation Work Plan shall define the expected impacts to the project area and
38 restoration resulting from Work necessary to meet all Contract requirements. The Contractor
39 shall define how the restoration Work included in the Contract will be phased and coordinated
40 with project Work such as earthwork, staging, access, erosion and water pollution control,
41 irrigation, etc. The Revegetation Work Plan shall include the following:

- 42
43 1. Means and methods for vegetation protection (in accordance with Section 1-07.16(2)).
44 2. Locations outside of clearing limits where vegetation shall be removed to provide access
45 routes or other needs to accomplish the Work.
46 3. Plans for removal, preservation and stockpile of topsoil or other native materials, if outside
47 of clearing and grubbing limits and within the project limits.
48 4. Plan for propagation and procurement of plants, ground preparation for planting, and
49 installation of plants.

5. Means and methods to limit soil compaction where seeding and planting are to occur, such as steel plates, hog fuel access roads, wood mats for sensitive areas (including removal) and decompaction for unavoidable impacts.
6. Plan and timing to incorporate or remove erosion control items.

8-02.3(2)B Weed and Pest Control Plan

Section 8-02.3(2)B is revised to read:

(*****)

8-02.3(2)B Weed Control Plan

The Weed Control Plan shall describe all weed control needs for the project.

The plan for control of weeds on the Contract in accordance with Section 8-02.3(3) shall include the following:

1. Names of plan preparer and herbicide operators, including contact information. The Contractor shall provide the Engineer evidence that all operators are licensed with appropriate endorsements, and that any herbicide used is registered for use by the Washington State Department of Agriculture.
2. Means and methods of weed control approved by Owner, including mechanical and/or chemical. The Contractor shall provide a site plan indicating where the noted methods of weed control will be implemented.
3. Schedule and timing for weed control including re-entry times for herbicide application by herbicide type, if any.
4. Proposed herbicide use, if approved by Owner, in accordance with Section 8-02.3(3)A: name, application rate, and Safety Data Sheets of all proposed herbicides. The Contractor shall provide a copy of the current product label for each herbicide to be used.
5. Plan to ensure worker safety until herbicide re-entry periods are met.
6. Site management and control protocol for all anticipated pests including herbivory (browse and girdling), fungal and insect infestations, and all applicable aquatic invasive species per RCW 77.135.010. Document equipment cleaning and/or sterilization protocols in accordance with Section 1-05.9, including provisions to prevent the spread of listed species.

8-02.3(2)C Plant Establishment Plan

Prior to installation of plants the Contractor shall submit a Plant Establishment Plan for the Owner's approval. Plan shall describe how 8-02.3(13) Plant Establishment and 8-02.3(14) Plant Replacement will be addressed.

8-02.3(3) Weed and Pest Control

Section 8-02.3(3), including Section B, is revised to read:

(*****)

8-02.3(3) Weed Control

The Contractor shall control weed species within the project area during construction using integrated management principles consisting of mechanical, biological, and/or chemical controls that are outlined in the Weed Control Plan or as designated by the Owner.

Controlling weeds consists of killing and removing weeds by methods approved by Owner

1 **8-02.3(3)B Restoration Area Weed Control**

2
3 Seeding and planting area weed control consists of controlling weeds in seeded and planted
4 areas shown on the Plans. This Work is included in the bid items for seeding and planting.
5

6 All seeding and planting areas shall be prepared so that they are weed and unnatural debris
7 free at the time of planting and until completion of the project. The planting areas shall
8 include the entire ground surface, regardless of cover, areas around plants, and those areas
9 shown on the Plans.

10
11 Within seeding and planting areas, all noxious weed species are unwanted and shall be
12 controlled unless specifically allowed by the Owner to remain.
13

14 All applications of post-emergent herbicides shall be made while green and growing tissue is
15 present. Residual herbicides shall not be used where rhizomatous species or perennial
16 species are indicated.
17

18 Should unwanted vegetation reach the flowering and seed stage in violation of these
19 Specifications, the Contractor shall physically remove and bag the seed heads prior to seed
20 dispersion. All physically removed vegetation and seed heads shall be disposed of off-site at
21 no cost to the Owner.
22

23 **8-02.3(4) Topsoil**

24
25 Sections 8-02.3(4)B and C are omitted.
26

27 **8-02.3(5) Restoration Seeding and Planting Area Preparation**

28
29 **8-02.3(5)A Seeding Area Preparation**

30
31 Section 8-02.3(5)A. is revised to read:
32 (*****)
33

34 The Contractor shall prepare restoration seeding areas as follows:

- 35 1. Remove all unnatural debris from areas to be seeded. Dispose of removed materials
36 offsite.
37 2. Prepare restoration seeding area to a weed free and bare condition.
38 3. Bring area to the specified finished grade.
39 4. Seed and mulch within two days of preparation.
40

41 **8-02.3(5)C Planting Area Preparation**

42
43 Section 8-02.3(5)C is revised to read:
44 (*****)
45

46 Any areas impacted by construction activities, including staging and temporary access
47 routes designated for planting with the exception of the riparian vegetation management
48 areas shall be uniformly and wholly decompacted to a depth of 12 inches, leaving no holes
49 or mounds over 12 inches in depth or height.
50

Contractor shall rip slopes longitudinally across the slope (i.e. perpendicular to slope) to promote capture of runoff and minimize erosion.

Upon completion of the ripping, only low ground pressure seeding equipment shall be allowed to enter the decompacted areas unless otherwise approved by Owner's Representative. Low ground pressure (LGP) seeding equipment shall have a maximum ground pressure of 6 pounds per square inch.

Temporary access roads that were cleared of woody vegetation but not grubbed shall not be ripped/decompacted unless the Owner's Representative determines that flush cut vegetation has been so severely impacted that the areas will require decompaction and replanting.

8-02.3(6) Mulch and Amendments

Sections 8-02.3(6)A and B are omitted.

8-02.3(7) Layout of Planting, Lawn and Seeding Areas

Section 8-02.3(7) is revised to read:
(*****)

8-02.3(7) Layout of Planting and Seeding Areas

The Contractor shall lay out and prepare planting and lawn areas and receive the Engineer's acceptance of layout and preparation prior to any installation activities. See details and notes on the Plans for planting layout schematic.

8-02.3(8) Planting

8-02.3(8)A Dates and Conditions for Planting

Section 8-02.3(8)A paragraph 7 is revised to read:
(*****)

After delivery and prior to installation, tubelings shall be closely monitored for sufficient root moisture and shall be protected from sun, wind and extreme temperatures. Stored tubelings shall be watered and misted several times a day when necessary to maintain proper root moisture and to reduce transpiration in sunny and windy locations.

The Contractor shall minimize foot traffic and soil disturbance during installation of the tubelings.

Install the tubelings so the stem base is at or slightly above finish grade. Plant tubelings fully into planting soil, not into mulch. Install tubelings to their full depth without bending the tubeling. Tubelings demonstrating "J-roots" shall not be acceptable. Backfill planting holes and tamp the soil around each tubeling in-place so that it is firmly seated in the soil, with no air pockets. Following backfilling, tubelings shall be watered thoroughly until bubbles are observed at the ground surface.

1 Section 8-02.3(8)A. is supplemented with the following:
2 (*****)
3

4 Live stakes for use on the floodplain and as live cuttings shall be harvested during
5 dormancy, which shall tentatively range from October 1 through November 15 unless
6 otherwise approved by Owner's representative.
7

8 At the time of live stake harvest, no leaf buds shall have initiated growth beyond one-quarter
9 inch and the cambium layer shall be moist, green, and healthy. Materials shall be
10 maintained in a continuously cool, covered, and moist state prior to use and be in good
11 condition when installed.
12

13 Expected dates for Contractor-performed planting shall be identified in the Project Schedule
14 described in section 1-08.3(2)A. Notification shall be provided to Owner 5 days prior to
15 planting work.
16

17 Live cuttings shall be installed no earlier than October 1 unless approved by the Engineer.
18
19

20 **8-02.3(8)B Plant Installation** 21

22 Section 8-02.3(8)B is revised as follows:
23 (*****)

24 The Contractor must coordinate live cutting delivery and storage to ensure that cuttings do
25 not desiccate (dry out) before planting. No more cuttings than can be planted within 24
26 hours after removal from storage shall be delivered to an installation location. Live cuttings
27 that are not used in a day shall be wrapped in wet burlap sacks and stored in a location with
28 an air temperature between 37 °F and 65 °F until the next planting day or returned to
29 storage.
30

31 The Contractor shall deliver live stakes and poles to the project site in tagged bundles of 5
32 to 25 cuttings. Live cuttings shall be bundled into groups, each with a mixture of diameter
33 ranges and an equal number of male and female cuttings. Label individual bundles with an
34 aluminum tag. Tags on each bundle will clearly indicate the species, date and location of
35 collection, the date soaking began.
36

37 Cuttings shall be properly stored. If cold storage is necessary, the collected and soaked
38 cuttings shall be stored for no more than an additional 10 days at 37 °F to 41 °F until
39 planting. After the cuttings have been removed from cold storage, they shall be soaked for
40 no more than another 5 days to complete soaking and ensure hydration before and after
41 storage.
42

43 The Contractor shall maintain a list of species, and quantities of collected live cuttings at the
44 end of each collection day. The Contractor shall provide the Engineer with an on-site plant
45 material inventory within 24 hours of a request. The Engineer may also request an
46 inspection of the collection, storage, and live cutting inventory 24 hours in advance of the
47 inspection. The request shall include the quantities of plant species and date of scheduled
48 installation.
49

1 If air temperatures are above 80 degrees during installation, sprinklers that continuously
2 mist the Live Cutting Work area are required during installation to reduce ambient air
3 temperatures and reduce heat stress on Live Cuttings.

4
5 The last paragraph of 8-02.3(8)B is revised to read:
6 (*****)

7
8 When installing plants, the Contractor shall dig planting holes three times the diameter of the
9 container or root ball size as described in the Plans. Any glazed surface of the planting hole
10 shall be roughened prior to planting.

11 12 13 **8-02.3(9) Seeding, Fertilizing, and Mulching**

14 15 16 **8-02.3(9)A Dates for Application of Seed**

17
18 Section 8-02.3(9)A is revised as follows:
19 (*****)

20
21 Unless otherwise allowed by the Engineer, the Contractor shall apply seed for restoration
22 between October 1 and November 15.

23
24 All disturbed or finished graded ground surfaces shall be prepared and seeded during the
25 first available seeding window. When environmental conditions are not conducive to
26 satisfactory results, the Engineer may suspend the seeding Work until such time that the
27 desired results are likely to be obtained. If seeding is suspended, temporary erosion control
28 methods according to Section 8-01 shall be used to protect the bare soil until seeding
29 conditions improve.

30 31 **8-02.3(9)B Seeding and Fertilizing**

32
33 Section 8-02.3(9)B is revised as follows:
34 (*****)

35
36 The Contractor shall prepare the seeding area in accordance with Section 8-02.3(5)A
37 and apply seed at the rate and mix specified on the Plans. The Contractor
38 shall notify the Engineer within 5 days in advance of any seeding operation and shall
39 not begin the Work until areas prepared or designated for seeding have been accepted.
40 Following the Engineer's acceptance, seeding of the accepted ground surfaces shall
41 begin immediately.

42
43 Seeding shall not be done during windy weather or when the ground is frozen, or
44 excessively wet.

45
46 Seed shall be applied using a hand-held seed spreader at a rate of 30 pounds per acre as
47 described in the Plans.

48 49 **8-02.3(9)D Inspection**

50

1 Section 8-02.3(9)D is revised as follows:
2 (*****)

3
4 Seeded areas will be observed by the Engineer upon completion of seeding. The Work in
5 any area will not be measured for payment until a uniform distribution of the materials is
6 accomplished at the specified rate. Areas that have not received a uniform application of
7 seed at the specified rate, as determined by the Engineer, shall be re-seeded prior to
8 payment for seeding within a designated area.
9

10 **8-02.3(11) Mulch**

11 Section 8-02.3(11) is revised as follows:
12 (*****)

13
14 Sections 8-02.3(11)A shall be omitted.
15

16 **8-02.3(12) Inspection and Completion of Initial Planting**

17
18 Omit the following from 8-02.3(12)3.:
19 (*****)

20
21 ...including but not limited to, full operation of the irrigation system.
22
23

24 **8-02.3(13) Plant Establishment**

25
26 Omit the following from 8-02.3(13):
27 (*****)

28
29 Subsequent year plant establishment periods shall begin immediately at the completion of
30 the preceding year's plant establishment period. Each subsequent plant establishment
31 period shall be one full calendar year in duration.
32

33 During the plant establishment period(s) after the first-year plant establishment, the Work
34 necessary for the continued healthy and vigorous growth of all plants material shall be
35 performed as directed by the Engineer.
36

37 Payment for water used to water plants during the subsequent year(s) of plant
38 establishment will be paid under the plant establishment item.
39

40 Section 8-02.3(13) is supplemented with the following:
41 (*****)

42
43 80 percent survival is required during the warranty period of one year from the date of
44 acceptance of final project completion at no additional cost to the Owner. Inspection of Live
45 Cutting survival for warranty shall be in August during the warranty period.
46

47 **8-02.3(14) Plant Replacement**

48
49 Section 8-02.3(14) is supplemented with the following:
50 (*****)

Replacement of Live Cuttings shall be done vertically when plant replacement is required. The Live Cuttings shall be installed into a drive bar pilot hole or another approved method to not damage the Live Cutting.

8-02.4 Measurement

Section 8-02.4 is revised as follows:

(*****)

No separate measurement will be made for PSIFE __ (Plant Selection Including Plant Establishment).

No separate measurement shall be made for Project Area Weed Control. Work shall be considered incidental to related planting areas.

“Overbank Seed and Live Plant Areas” will be measured by the acre using plan area measurement or through the use of design data.

“Transitional/ Upland Seed and Live Plant Areas” will be measured by the acre using plan area measurement or through the use of design data.

“Transitional/ Upland Seed Only Areas” will be measured by the acre using plan area measurement or through the use of design data.

8-02.5 Payment

Section 8-02.5 is supplemented with the following:

(*****)

No separate payment shall be made for Project Area Weed Control. The cost of performing the work as described herein, shall be included in the related planting areas.

(A) Payment will be made for “Overbank Seed and Live Plant Areas” per acre.

(B) Payment will be made for “Transitional/ Upland Seed and Live Plant Areas” per acre.

(C) Payment will be made for “Transitional/ Upland Seed Only Areas” per acre.

The Bid Item price shall be full compensation for all costs incurred to complete the Work as shown on the Plans and described in the Specifications.

PSIFE __ (Plant Selection Including Plant Establishment) is incidental to all live plants and seeding areas provided.

No payment shall be made for items specified under 8-02.5 which are not included on the Bid Form.

**DIVISION 9
MATERIALS**

9-14 Erosion Control and Roadside Planting

9-14.3 Seed

Section 9-14.3 is revised to read:

(*****)

Seed mixes and seeding zones for the seed mixes are delineated on plans.

1. Contractor shall purchase seed in the quantity and at the percentages provided in the seed mix tables.
2. Contractor shall source the seed from within the appropriate genetic zones of the Columbia Plateau and Pleistocene Lake Basins ecoregions as defined by the US Environmental Protection Agency (EPA). The seed certification class shall be Certified (blue tag) in accordance with WAC 16-302 and meet the following requirements:

Prohibited Weed	0 percent max.
Noxious Weed	0 percent max.
Other Weed	0.2 percent max.
Other Crop	0.4 percent max.

3. Prior to seed purchase, the Contractor shall submit a list of suppliers and their seed sources (Submittal) and identify any difficulties in obtaining species or quantities.
4. Owner's Representative shall review submittal and approve or provide comments in order to assist the Contractor with securing appropriate seed.
5. Contractor shall provide the seed labels that include the germination rate and purity. Based on the certified testing results required by 9-14.2 of the Standard Specifications, the actual pounds of each grass species applied shall be adjusted so as to provide the specified pounds of PLS per species per acre. Seeds shall be certified "Weed Free," indicating there are no noxious or nuisance weeds in the seed.
6. Contractor shall not make any substitutions without the approval of the Owner's Representative.
7. If substitutions are required, and substituted species have substantially lower cost than the originally contract specified species; the cost for the seed shall be reduced accordingly.
8. Contractor shall be responsible for ordering, storing and delivering seed to the project site and storing site in a cool, dry location, out of direct sunlight on an as needed basis.
9. Any seed that is damaged due to herbivory or moisture prior to being spread will be rejected and will be the responsibility of the Contractor to procure replacement seed at no additional cost to the Owner.

9-14.5 Mulch and Amendments

9-14.5(3) Bark or Wood Chip Mulch

Section 9-14.5(3) is supplemented with the following:

(*****)

1 All bark or wood chip mulch shall be Certified Weed-Free per North American Invasive
2 Species Management Association (NAISMA) standards or the Washington Weed Free Hay
3 and Mulch program (WWHAM).

4 5 **9-14.7 Plant Materials**

6 **9-14.7(1) Description**

7
8 Section 9-14.7(1) paragraph 4 is revised to read:
9 (*****)

10
11 Cuttings are live plant material without a previously developed root system. Source plants for
12 cuttings shall be healthy and either dormant or in vigorous seasonal growth when cuttings are
13 taken. All cuts shall be made with a sharp instrument producing a clean cut and no adjacent
14 bark damage. Cuttings may be collected. If cuttings are collected, the requirement to be
15 nursery grown or held in nursery conditions does not apply. Written permission shall be
16 obtained from property owners and provided to the Engineer before cuttings are collected.
17 The Contractor shall collect cuttings in accordance with applicable sensitive area ordinances.
18 Collection sites shall be located within the Toppenish Creek Watershed and within +/- 500 foot
19 elevation band from the project site unless otherwise approved by Owner.

20
21 Cuttings shall meet the following requirements:

22
23 Section 9-14.7(1)2. and 3. are revised to read:
24 (*****)

- 25
26 2. Live Stake cuttings shall have a basal end diameter between $\frac{3}{4}$ inch and $1\frac{1}{2}$ inches. The
27 top end shall have straight top cut immediately above a bud. The basal rooting end shall
28 be cut at an approximate 45-degree angle at time of harvest. Live stakes are cut from one-
29 to two-year-old wood. Live stake cuttings shall be cut and installed with the bark intact with
30 no branches, stems, or leaves attached.

31
32 Section 9-14.7(1) is supplemented with the following:
33 (*****)

- 34
35 1. Live cuttings sourced from plants during the growing season shall be harvested no
36 less than 7 days and no more than 14 days prior to installation. Live cuttings shall be
37 continuously and completely submerged 6 inches under fresh water from within 1 hour
38 of harvest to within 1 hour of installation.
39 2. Live cuttings sourced from plants during the dormant season shall be harvested no
40 more than 300 days prior to installation. See 8-02.3(8)A for additional requirements
41 for the storage of dormant season harvested live cuttings.
42 3. Live cuttings shall have the lower basal rooting end recut cut to an approximate 45-
43 degree angle no more than 1 hour prior to installation. The fresh cut prior to installation
44 shall be 1 to 2 inches up from the original 45-degree cut made at time of harvest.

45 46 **9-14.7(2) Quality**

47
48 Section 9-14.7(2) paragraph 3 is revised to read:
49 (*****)

1 All plant material, except live cuttings, shall be purchased from a nursery licensed to sell
2 plants in their state or province.

3
4 Section 9-14.7(2) is supplemented with the following:
5 (*****)
6

7 No less than 15 days prior to the first delivery of Live Cuttings to the project site, the
8 Contractor shall submit source, type, size, count, and species information for all Plants and
9 Live Cuttings required for the project for approval by the Engineer.

10
11 Live cutting plant material shall be inspected upon delivery to the project site by the
12 Engineer.

13
14 The Contractor may request that the Engineer inspect plant materials at least three business
15 days in advance of delivery.