

30% DESIGN

CHELAN COUNTY, WA MAY, 2025

1 OF 22

THE OWNER WILL PROVIDE A PRE-BID SITE TOUR. THE CONTRACTOR SHALL ATTEND THIS PRE-BID TOUR FOR SITE FAMILIARIZATION AND TO POSE QUESTIONS TO THE OWNER AND OWNER'S REPRESENTATIVE.

THE SELECTED CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH OWNER AND OWNER'S REPRESENTATIVE PRIOR TO MOBILIZING TO SITE AND BEGINNING CONSTRUCTION.

IN WATER WORK WINDOW IS JULY 1-31

EXISTING DATA

TOPOGRAPHIC DATA WAS COLLECTED BY INTER-FLUVE USING RTK GPS EQUIPMENT ON NOVEMBER 14 & 15, 2018 AND NOVEMBER 2 & 3, 2020. DATA ARE REFERENCED TO NAD83, STATE PLANE, WASHINGTON NORTH, NAVD88, US SURVEY FEET.

HYDRAULIC MODELING BY INTER-FLUVE USING USACE HEC-RAS 5.0.7.

SOILS

SOILS WITHIN THE PROJECT AREA CONSIST OF BEVERLY FINE SANDY LOAM. BRIEF GRAVELLY SANDY LOAM, ALLUVIAL LAND, RIVERWASH, PEOH SILT LOAM, GODDARD COBBLY FINE SANDY LOAM, AS MAPPED BY NRCS.

HIGHWAY 207 EMBANKMENT MATERIALS

CONTRACTOR SHALL CONDUCT OWN SOILS INVESTIGATIONS AS NEEDED, AT NO ADDITIONAL COST.

UTILITIES

THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.

THE CONTRACTOR SHALL CALL (800-424-5555 OR 811) FOR UTILITY LOCATE PRIOR TO CONSTRUCTION

THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES.

THE CONTRACTOR SHALL PROVIDE EQUIPMENT AND LABOR TO AID THE AFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR DESTROYED UTILITIES AT NO ADDITIONAL COST.

EXISTING UTILITIES WILL BE DECOMMISSIONED AND REMOVED/ABANDONED (TBD) IN PHASE 1.

CONSTRUCTION STAKING

OWNER'S REPRESENTATIVE WILL PROVIDE STAKING OF PROJECT LIMITS, AND ELEVATION CONTROL POINTS. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED.

CONTRACTOR SHALL MEET WITH THE OWNER AND OWNER'S REPRESENTATIVE TO DEFINE AND MARK LIMITS OF DISTURBANCE PRIOR TO MOBILIZATION OF EQUIPMENT OR MATERIALS ONTO THE SITE.

CONTRACTOR SHALL STAKE PROJECT LIMITS AND GRADES STAKES BASED ON PROJECT ELEVATION CONTROL POINTS. THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO ADDITIONAL COST.

CONTRACTOR SHALL COORDINATE WITH ENGINEER FOR INITIAL AND PERIODIC CHECKING OF CONTRACTOR'S STAKEOUT. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED.

CONSTRUCTION MATERIALS

OWNER PROVIDED LOGS, LOGS WITH ROOTWADS AND LOG PILES WILL BE LOCATED IN A DESIGNATED STOCKPILE/STAGING AREA. CONTRACTOR SHALL PROCURE, PROVIDE AND PLACE SLASH MATERIALS.

LOCATION, ALIGNMENT, AND ELEVATION OF LOGS AND LOGS WITH ROOTWADS ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS AND MATERIAL SIZE, PER DIRECTION BY OWNER OR **OWNER'S REPRESENTATIVE.**

ANY EXCESS CONSTRUCTION MATERIALS SHALL BE NEATLY STORED AT AN APPROVED STAGING LOCATION. UPON COMPLETION OF THE PROJECT ANY EXCESS MATERIALS, WITH THE EXCEPTION OF ANY LARGE WOODY MATERIAL (LWM), WILL BECOME THE PROPERTY OF THE CONTRACTOR AND HAULED OFFSITE IN A TIMELY MANNER AND LEGALLY DISPOSED OF.

PHASE 1 CONSTRUCTION WILL INCLUDE RELOCATING HIGHWAY 207 ROADWAY AND UTILITIES,

EXISTING HIGHWAY 207 EMBANKMENT TO BE ABANDONED WILL BE REMOVED IN THIS PHASE 2 WORK. EXISTING HIGHWAY 207 EMBANKMENT TO BE ABANDONED WILL BE REMOVED IN THIS PHASE 2 WORK. CONSTRUCTION ACCESS/TRAFFIC CONTROL MIN-PLACE QUANTITIES AND NOT APPROX APPROXIMATE FACTORED FOR EXPANSION OF BMP BEST MANAGEMENT PRACTICE EXCAVATED MATERIAL OR COMPACTION CY CUBIC YARDS OF PLACED MATERIAL. MEASUREMENT DEGREE AND PAYMENT SHALL NOT BE BASED ON WEIGHT TICKETS OR TRUCK MEASURE DBH DIAMETER AT BREAST HEIGHT	PHASE 1 CONSTRUCTION WILL INCLUDE F DECOMMISSIONING AND REMOVAL OF U			IWAY 207 F	ROADWAY AN	D UTILITIES,		1.	ESTIMATED MATE		ES ARE			
									IN-PLACE QUANTIT FACTORED FOR EX	TES AND NO PANSION OF	Т	BMP	BEST MANAGEMENT PRACTICE	
	CONSTRUCTION ACCESS/	TRA	FFIC C	ONTRO	DL									
THE CONTRACTOR IS SOLUCY AS DOUBLE TO BE OVECLOBERGA TRATECONTROL ON ACCEPTABLE Y PLOTOBING AND ACCEPTABLE Y FOOT THE CONTRACTOR IS SOLUCY AS DOUBLE TO REPORTING AND ACCEPTABLE TO ACTION BOL THE CONTRACTOR SOLUCY AS DOUBLE TO REPORT ON AND ACCEPTABLE TO ACTION BOL Sec. FOOT ADDITION BOL THE CONTRACTOR IS SOLUCY AS DOUBLE TO REPORT ON AND ACCEPTABLE TO ACTION BOL THE CONTRACTOR IS SOLUCY AND SOLUCE AND ACCEPTABLE TO ACTION BOL Sec. FOOT ADDITION BOL THE CONTRACTOR IS SOLUCY AND SOLUCE TO ACTION AND ACCEPTABLE TO ACTION BOL THE CONTRACTOR IS SOLUCY AND ADDITION BOL Sec. FOOT ADDITION BOL THE STA ADD ACCESS DOUTES THE CONTRACTOR IS SOLUCY AND ADDITION BOL ADDITION BOL THE CONTRACTOR IS SOLUCY ADDITION BOL Sec. FOOT ADDITION BOL THE STA ADD ACCESS DOUTES THE CONTRACTOR IS SOLUCY AND ADDITION BOL THE CONTRACTOR IS SOLUCY ADDITION BOL Sec. Sec. <td< td=""><td colspan="8">CONTRACTOR SHALL SUBMIT AN ACCESS, STAGING, AND STOCKPILE PLAN TO THE OWNER'S</td><td>WEIGHT TICKETS C</td><td>R TRUCK M</td><td>EASURE</td><td>DIA EA</td><td>DIAMETER EACH</td><td></td></td<>	CONTRACTOR SHALL SUBMIT AN ACCESS, STAGING, AND STOCKPILE PLAN TO THE OWNER'S								WEIGHT TICKETS C	R TRUCK M	EASURE	DIA EA	DIAMETER EACH	
											ATION ARE	ESC ' or FT	EROSION AND SEDIMENT CONTRO	
CONTRACTOR SHALL IMPLEMENT LARGE VIEWS TO CONTROL AND MININGE WIND BLOWN DUST FROM THE STREAM ACCOUNT OF SAME ACCOUNT OF SAME ACCOUNT AND ACCOUNT OF SAME ACCOUNT AND ACCOUNT OF SAME ACCOUNT AND ACCOUNT OF SAME ACCOUNT OF S					JIRED TRAFFI	C CONTROL						HWY	HIGHWAY	EM
AT PROJECT COMPETION, ROUGS AND ACCESS BOUTDS SHALL BE INFORMED, GRADE D, AND RESURCED MAX Septemicitation of using strankands between unsolution. Works and its end of the information of the informat		IRES TO	CONTROL	AND MINI	MIZE WIND B	LOWN DUST	FROM					LWM	LARGE WOODY MATERIAL	
ALL DETURBED AREAS INCLUDING, BUT NOT LIMITED TO: PROADS, DRIVEWAWS, TEMPORAMY ACCESS NORTH AMERICAN DATING TO: TO DETURBANCE STATES OF DRIVEWAWS, TEMPORAMY ACCESS CONDICIS, STAND AND REAS AND STIRUCTURE LOCATIONS AND BERSTORE OF DRIVERAUE NORTH AMERICAN DATING TO: TO DETURBANCE STAND OF 383 CONTRACTORS NALL SEED AND MULL ALL DESTUREE DO STRATES SECREPT CHANNEL BETWEEN TOPS OF BAMK AND COSTS NORTH AMERICAN USAN ATTER VIETAL SECRET CONTRACTORS NALL SECRET CHANNEL BETWEEN TOPS OF BAMK AND COSTS CONTRACTORS NALL SEED AND MULC ALL DISTURBED SUBJECATION. ORIVIN WAITER ORIVIN WAITER CONTRACTORS NALL SEED AND MULC ALL DISTURBED SUBJECATION. State STORE TO ORIGINAL ORIVIN WAITER CONTRACTORS NALL SEED AND MULC ALL DISTURBED SUBJECATION. State STORE TO ORIGINAL State STORE TO ORIGINAL CONTRACTORS NALL SEED AND MULC ALL DISTURBED SUBJECATION. State STORE TO ORIGINAL State STORE TO ORIGINAL CONTRACTORS NALL SEED AND MULC ALL DISTURBED SUBJECATION. State STORE TO ORIGINAL State STORE TO ORIGINAL CONTRACTORS NALL SEED AND MULC ALL DISTURBED SUBJECATION. State STORE TO ORIGINAL State STORE TO ORIGINAL CONTRACTORS NALL SEED TO DISTURBANCE STATE DEPARTMENT OF TRACTORS NALL SEED TO ORIGINAL State STORE TO ORIGINAL State STORE TO ORIGINAL CONTRACTORS NALL SEED TO STATE STORE TO ORIGINAL State STORE TO ORIGINAL SERVICE State STORE TO ORIGINAL State STORE TO ORIGINAL SERVIL	TO PRE-PROJECT CONDITION PER WASHI SPECIFICATION OR USFS STANDARDS PER	NGTON	DEPARTM	ENT OF TR	ANSPORTATIO	ON STANDAI)				MAX MIN MP	MAXIMUM MINIMUM MILEPOST	
CONTRACTOR SHULL SEED AND MURCH ALL DISTURBED SURFACES EXCEPT CHANNEL BETWEEN TOPS OF BRINK AND DISTING GAVEE RADAS. \$ ALL DISTURBED AREAS OUTSIDE THE UNITS OF DISTURBANCE SHALL BE RESTORED TO ORGINAL CONTROL ON RETTER AT NO ADDITIONAL COST. \$ QUANTITIES ESTIMATE	ROUTES, STAGING AREAS AND STRUCTUP CONDITION OR BETTER. THIS WILL INCLU DISTURBED AREAS AS WELL AS REMOVAL	RE LOCA DE, BUT OF ANY	ATIONS SHA T IS NOT LII Y TRASH A	ALL BE REST MITED TO 7 ND DEBRIS	FORED TO PRI ANY GRADING . THE OWNER	E-PROJECT 6/BLADING (S REPRESEN	DF NTATIVE					NAD 83 NAVD88 NRCS OHW	NORTH AMERICAN DATUM OF 19 NORTH AMERICAN VERTICAL DAT NATURAL RESOURCES CONSERVA ORDINARY HIGH WATER	UM OF 1988
ALL DISTRETO AREAS OUTSIDE THE LUMITS OF DISTURBANCE SHALL BE RESTORED TO ORIGINAL Series 100 (1990) Series 1000) Series 100 (1990) Series 1000) Series 1000) Series 1000 (1990) Series 1000) Series 1000 (1990) Series 1000) Series 10000 (1990) Series 100000 (1990) Series 100000 (1990) Series 100000 (1990) Series 100000 (1990) Series 10000000 (1990) Series 1000000 (1990) Ser		LL DIST	URBED SU	RFACES EX	CEPT CHANNI	EL BETWEEN	TOPS OF					% LBS	PERCENT POUNDS	
Cacion Structure quantity Units Log w/Rw Burried single log Surface single log	CONDITION OR BETTER AT NO ADDITION			ICE SHALL I	BE RESTORED	TO ORIGIN	AL					RM RTK GPS	RIVER MILE	OSITIONING
Oration Structure quantity units DS W/RW single log				1										
hase 2 - River Left Long to tag				Log w/RW			Log pile	Slash						
Bar Proughness lws 12 est 5 50 10 44 10 1		quanti	tty units		single log	single log			tree	(CY)	(CY)			
Tigget trees (separate contract) 4 ea 1			02	5			5			50	50			ENGINEERS
FP roughness logs 4 ea 1 v				5			5		1		50	USFS	UNITED STATES FOREST SERVICE	
Apex Ivis 2 ea 4 7 4 300 300 Base 2 R. studied is sum(life of structures) kigety per structure) 68 0 4 74 8 4 1200 1200 hase 2 R. studied lass with studied lass with structures is and buried lass with studied l	FP roughness logs	4	ea			1							WASHINGTON DEPARTMENT OF F	ISH AND
Phase 2 Ru subtoial = Sum((# of structures))(qty per structure)) hase 2 - Niver Right: Apex Nixs 4 ea 4 - 7 4 - 300 300 Bank buried isw strees 4 ea 9 - 4 4 2 300 300 Bank buried isw strees 4 ea 9 - 4 4 4 6 300 300 Bank buried isw strees 4 ea 9 - 12 - 12 3 3 5 50 50 CED3 Bank bor structure 4 ea 12 - 11 14 3 6 6 0 590 Deflector lws 3 ea - 2 9 2 - 0 0 0 Riodoplain lws 7 ea - 3 - 4 - 1 0 0 0 Riodoplain lws 7 ea - 3 - 4 - 1 0 0 0 Riodoplain lws 7 ea - 3 - 4 - 1 0 0 0 Riodoplain lws 7 ea - 3 - 1 0 0 0 Riodoplain lws 7 ea - 3 - 1 0 0 0 Riodoplain lws 7 ea - 3 - 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Salvage/Tipped trees 3 8 ea - 1 0 1 0 0 0 Nease 2 Ris subtoial = Sum((# of structure)) 222 58 100 4118 108 129 33710 8120 Phase 2 Total = 200 58 100 418 108 129 33710 8120 Phase 2 Total = 200 58 100 418 108 129 33740 9320 XAKAMA NATION FISHERIES R.R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT X.R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT X.R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT	Apex lws	2	ea	4			7	4		300	300		WASHINGTON STATE DEPARTMEN	
Apex lws 4 ea 4 7 4 300 300 Bank buried lws 1 ea 9 4 4 2 300 300 Bank buried lws w/trees 4 ea 9 4 4 6 300 300 Bank buried lws w/trees 4 ea 9 2 1 40 40 Bank buried lws w/trees 4 ea 2 2 1 40 40 Bank buried lws w/trees 4 ea 7 12 3 3 50 50 Bar coughness wood structures 5 ea 1 14 3 6 0 590 Deflector lws 3 ea 1 2 9 2 0 0 0 Floodplain lws 7 ea 3 4 1 1 0 0 Salvaged/Tipped trees 38 ea 1 1 0 0 0 Slash 14 ea 1 1 0 0 0	Phase 2 RL subtotal = Sum[(# of structures)x	qty per	structure)]	68	0	4	74	8	4	1200	1200			
Bank buried lws 1 ea 9 4 4 2 300 300 Bank buried lws w/trees 4 ea 9 4 4 6 300 300 Bank buried lws w/trees 4 ea 9 2 2 1 40 40 Bank margin wood 8 ea 7 12 3 3 50 50 CED3 Bank barb structure 4 ea 12 1 14 3 6 0 590 Deflector lws 3 ea 2 9 2 0 0 0 Floodplain lws 7 ea 3 4 1 - - - Buried log 37 ea 1 0 0 -	hase 2 - River Right													
Bank buried lws w/trees 4 ea 9 4 4 4 6 300 300 Bank buried small lws 2 ea 2 1 40 40 Bank margin wood 8 ea 7 122 3 3 50 50 Bank margin wood 8 ea 7 122 3 3 50 50 CED3 Bank barb structures 5 ea 5 5 50 50 50 Deflector lws 3 ea 2 9 2 0 0 0 Inlet structure 2 ea 1 0 0 0 0 Roughness trees 8 ea 1 0 <td>Apex lws</td> <td>4</td> <td>ea</td> <td>4</td> <td></td> <td></td> <td>7</td> <td>4</td> <td></td> <td>300</td> <td>300</td> <td></td> <td></td> <td></td>	Apex lws	4	ea	4			7	4		300	300			
Bank buried small lws 2 ea 2 2 1 40 40 Bank margin wood 8 ea 7 12 3 3 50 50 Bar roughness wood structures 5 ea 5 5 50 50 50 CED3 Bank bar's structure 4 ea 12 1 14 3 6 0 590 Deflector lws 3 ea 2 9 2 0 0 0 Floodplain lws 7 ea 3 4 1 - <td>Bank buried lws</td> <td>1</td> <td>ea</td> <td>9</td> <td></td> <td></td> <td></td> <td>4</td> <td>2</td> <td></td> <td>300</td> <td></td> <td></td> <td></td>	Bank buried lws	1	ea	9				4	2		300			
Bank margin wood 8 ea 7 12 3 3 50 50 Bar roughness wood structures 5 ea 5 5 50 50 50 CED3 Bank barb structure 4 ea 12 1 14 3 6 0 590 Deflector lws 3 ea 2 9 2 0 0 0 Hindde Structure 2 ea 3 4 1 -	Bank buried lws w/trees		ea					4	6	300				
Bar roughness wood structures 5 ea 5 v 50 50 CED3 Bank barb structure 4 ea 12 1 14 3 6 0 590 Deflector lws 3 ea 2 9 2 0 0 Floodplain lws 7 ea 3 4 1 - - Inlet structure 2 ea 14 6 6 - - - Buried log 37 ea 1 - 0 0 - <td>Bank buried small lws</td> <td>2</td> <td>ea</td> <td>2</td> <td></td> <td></td> <td>2</td> <td>2</td> <td>1</td> <td>40</td> <td>40</td> <td></td> <td></td> <td></td>	Bank buried small lws	2	ea	2			2	2	1	40	40			
CED3 Bank barb structure 4 ea 12 1 14 3 6 0 590 Deflector lws 3 ea 2 9 2 0 0 Hold plant structure 2 ea 3 4 1	Bank margin wood	8	ea	7			12	3	3	50	50			
Deflector lws 3 ea 2 9 2 0 0 Floodplain lws 7 ea 3 4 1 - Inlet structure 2 ea 14 66 6 - - - Buried log 37 ea 1 0 0 - <th< td=""><td>Bar roughness wood structures</td><td>5</td><td>ea</td><td>5</td><td></td><td></td><td>5</td><td></td><td></td><td>50</td><td>50</td><td></td><td></td><td></td></th<>	Bar roughness wood structures	5	ea	5			5			50	50			
Floodplain lws 7 ea 3 4 1	CED3 Bank barb structure	4	ea	12		1	14	3	6	0	590			
Inlet structure 2 ea 14 6 6 Buried log 37 ea 1 Log piles 126 ea 1 0 0 Roughness trees 8 ea 1 0 0 Salvaged/Tipped trees 38 ea 1 0 0 Salvaged/Tipped trees 90 ea 1 0 0 Sufface logs 90 ea 1 0 0 0 Mainstem remeander 1 ea Phase 2 Total = 290 58 104 492 116 133 34910	Deflector lws	3	ea			2	9	2		0	0			
Buried log 37 ea 1 0 0 Log piles 126 ea 1 0 0 Roughness trees 8 ea 1 0 0 Salvaged/Tipped trees 38 ea 1 0 0 Slash 14 ea 1 0 0 Surface logs 90 ea 1 0 0 Mainstem remeander 1 0 0 0 Road removal/wetland channel ea 222 58 100 418 108 129 33710 8120 Phase 2 RR subtotal = Sum[(# of structures)x(qty per structure)] 222 58 104 492 116 133 34910 9320 //AKAMA NATION FISHERIES Sol Portway Avenue, Suite 101 Main Stem remeander 133 34910 9320 SHEET A.R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT Sol Portway Avenue, Suite 101 Main Stem remeander 133 34910 9320					3				1					
Log piles 126 ea 1 0 0 Roughness trees 8 ea 1 0 0 Salvaged/Tipped trees 38 ea 1 0 0 Salvaged/Tipped trees 38 ea 1 0 0 Salvaged/Tipped trees 38 ea 1 0 0 Surface logs 90 ea 1 0 0 Mainstem remeander 1 ea 27000 0 Mainstem remeander 1 ea 222 58 100 418 108 129 33710 8120 Phase 2 Total = 290 58 104 492 116 133 34910 9320 //AKAMA NATION FISHERIES Sol Portway Arenue, Suite 101 Hood River, 08 97031 Post OFFICE BX 151 TOPPENDEN, WA 38948 ABBREVIATIONS AND SHEET . R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT Sol Portway Arenue, Suite 101 Nation Post OFFICE BX 151 TOPPENDEN, WA 38948 ABBREVIATIONS AND 2 of 2				14			6	6						
Roughness trees 8 ea Image: construction of the set of t					1									
Salvaged/Tipped trees 38 ea Image: Construction of the sector of t			i ea				1							
Slash 14 ea 1 0 0 Surface logs 90 ea 1 0 0 Mainstem remeander 1 ea 3280 2330 Road removal/wetland channel 1 ea 27000 0 hase 2 RR subtotal = Sum[(# of structures)x(qty per structure)] 222 58 100 418 108 129 33710 8120 Phase 2 Total = 290 58 104 492 116 133 34910 9320 YAKAMA NATION FISHERIES Sol Portway Avenue, Suite 101 Hood River, 0R 97031 Yakama POST OFFICE BOX 151 GENERAL NOTES, ABBREVIATIONS AND SHEET AKAMA NATION FISHERIES Sol Portway Avenue, Suite 101 Hood River, 0R 97031 Yakama POST OFFICE BOX 151 GENERAL NOTES, ABBREVIATIONS AND SHEET N.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT Sol Portway Avenue, Suite 101 Hood River, 0R 97031 Shi 200 TOPPENISH, WA 98948 ABBREVIATIONS AND 2 OF Z									1	0	0			
Phase 2 Total = 290 58 104 492 116 133 34910 9320 (AKAMA NATION FISHERIES A. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT S01 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 S01 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 GENERAL NOTES, ABBREVIATIONS AND SHEET									1	0	0			
Phase 2 Total = 290 58 104 492 116 133 34910 9320 /AKAMA NATION FISHERIES R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT 501 Portway Avenue, Suite 101 Hood River, 0.8 97031 541.386,9003 Fortway Avenue, Suite 101 Hood River, 0.8 97031 541.386,9003 POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 GENERAL NOTES, ABBREVIATIONS AND SHEET								1						ant
Phase 2 Total = 290 58 104 492 116 133 34910 9320 (AKAMA NATION FISHERIES a. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT 501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 GENERAL NOTES, ABBREVIATIONS AND SHEET	Surface logs	90	ea			1				0	0		Dralimit	Idiy
Phase 2 Total = 290 58 104 492 116 133 34910 9320 (AKAMA NATION FISHERIES a. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT 501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 GENERAL NOTES, ABBREVIATIONS AND SHEET													IFIE	nuction
Phase 2 Total = 290 58 104 492 116 133 34910 9320 AKAMA NATION FISHERIES . R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT 501 Portway Avenue, Suite 101 Hood River, OR 97031 541,386,9003 Fortway Avenue, Suite 101 Hood River, OR 97031 541,386,9003 POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 93948 GENERAL NOTES, ABBREVIATIONS AND SHEET											-		tor Const	ruction
Phase 2 Total = 290 58 104 492 116 133 34910 9320 (AKAMA NATION FISHERIES A. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT S01 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 S01 Portway Avenue, Suite 101 Hood River, OR 97031 541.386,9003 POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 GENERAL NOTES, ABBREVIATIONS AND SHEET	Phase 2 RR subtotal = Sum[(# of structures)x	-											Not for de	
AKAWA NATION FISHERIES . R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT . R.M. 3.6 FLOODPLAIN		Phase	e 2 Total =	290	58	104	492	116	5 133	34910	9320			
AKAWA NATION FISHERIES . R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT . R.M. 3.6 FLOODPLAIN								<u>.</u>						SHFFT
R. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT	YAKAMA NATION FISHERIES							Yak	ama POST OFFICE				,	511221
	R. R.M. 3.6-4.6 FLOODPLAIN ENHANCEME	NT			Hood River, O	DR 97031	M	🚺 Nati	ion FORT R	DAD		ABBREV	IATIONS AND	2 ∩⊧ 2
QUANTITLS	PHASE 2 30% DESIGN		🔨 int	erfluve			6) Fish					ANTITIES	
												Q0/		

				<u>CM, NS</u>	DM	DM	
				DRAWN	DESIGNED	CHECKED	
				DM	05/30/2025	200237	
				APPROVED	DATE	PROJECT	
NO.	BY	DATE	REVISION DESCRIPTION				

NASON





- NOTES:

ABBREVIATIONS

HIP IV GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS

THE ACTIVITIES COVERED UNDER THE HIP ARE INTENDED TO PROTECT AND RESTORE FISH AND WILDLIFE HABITAT WITH LONG-TERM BENEFITS TO ESA-LISTED SPECIES. THE FOLLOWING GENERAL CONSERVATION MEASURES (DEVELOPED IN COORDINATION WITH USFWS AND NMFS) WILL BE APPLIED TO ALL ACTIONS OF THIS PROJECT.

PROJECT DESIGN AND SITE PREPARATION.

1. STATE AND FEDERAL PERMITS.

- ALL APPLICABLE REGULATORY PERMITS AND OFFICIAL PROJECT AUTHORIZATIONS WILL BE OBTAINED BEFORE PROJECT IMPLEMENTATION.
- THESE PERMITS AND AUTHORIZATIONS INCLUDE. BUT ARE NOT LIMITED TO, NATIONAL ENVIRONMENTAL B. POLICY ACT, NATIONAL HISTORIC PRESERVATION ACT, THE APPROPRIATE STATE AGENCY REMOVAL AND FILL PERMIT, USACE CLEAN WATER ACT (CWA) 404 PERMITS, CWA SECTION 401 WATER QUALITY CERTIFICATIONS, AND FEMA NO-RISE ANALYSES.

2. TIMING OF IN-WATER WORK.

- APPROPRIATE STATE (OREGON DEPARTMENT OF FISH AND WILDLIFE (ODFW), WASHINGTON Α. DEPARTMENT OF FISH AND WILDLIFE (WDFW), IDAHO DEPARTMENT OF FISH AND GAME (IDFG), AND MONTANA FISH WILDLIFE AND PARKS (MFWP)) GUIDELINES FOR TIMING OF IN-WATER WORK WINDOWS (IWW) WILL BE FOLLOWED.
- CHANGES TO ESTABLISHED WORK WINDOWS WILL BE APPROVED BY REGIONAL STATE BIOLOGISTS AND Β. BPA'S EC LEAD.
- C. BULL TROUT. FOR AREAS WITH DESIGNATED IN-WATER WORK WINDOWS FOR BULL TROUT OR AREAS KNOWN TO HAVE BULL TROUT, PROJECT PROPONENTS WILL CONTACT THE APPROPRIATE USFWS FIELD OFFICE TO INSURE THAT ALL REASONABLE IMPLEMENTATION MEASURES ARE CONSIDERED AND AN APPROPRIATE IN-WATER WORK WINDOW IS BEING USED TO MINIMIZE PROJECT EFFECTS.
- D. LAMPREY. WORKING IN STREAM OR RIVER CHANNELS THAT CONTAIN PACIFIC LAMPREY WILL BE AVOIDED FROM MARCH 1 TO JULY 1 FOR REACHES <5.000 FEET IN ELEVATION AND FROM MARCH 1 TO AUGUST 1 FOR REACHES >5,000 FEET. IF EITHER TIMEFRAME IS INCOMPATIBLE WITH OTHER OBJECTIVES, THE AREA WILL BE SURVEYED FOR NESTS AND LAMPREY PRESENCE, AND AVOIDED IF POSSIBLE. IF LAMPREYS ARE KNOWN TO EXIST, THE PROJECT SPONSOR WILL UTILIZE DEWATERING AND SALVAGE PROCEDURES (SEE FISH SALVAGE AND ELECTROFISHING SECTIONS) TO MINIMIZE ADVERSE EFFECTS.
- E. THE IN-WATER WORK WINDOW WILL BE PROVIDED IN THE CONSTRUCTION PLANS.

3. CONTAMINANTS.

- EXCAVATION OF MORE THAN 20 CUBIC YARDS WILL REQUIRE A SITE VISIT AND DOCUMENTED ASSESSMENT FOR POTENTIAL CONTAMINANT SOURCES. THE SITE ASSESSMENT WILL BE STORED WITH PROJECT FILES OR AS AN APPENDIX TO THE BASIS OF DESIGN REPORT.
- THE SITE ASSESSMENT WILL SUMMARIZE: R
 - 1. THE SITE VISIT, CONDITION OF THE PROPERTY, AND IDENTIFICATION OF ANY AREAS USED FOR VARIOUS INDUSTRIAL PROCESSES;
 - 2. AVAILABLE RECORDS, SUCH AS FORMER SITE USE, BUILDING PLANS, AND RECORDS OF ANY PRIOR CONTAMINATION EVENTS;
 - 3. INTERVIEWS WITH KNOWLEDGEABLE PEOPLE, SUCH AS SITE OWNERS, OPERATORS, OCCUPANTS, NEIGHBORS, OR LOCAL GOVERNMENT OFFICIALS; AND
 - 4. THE TYPE, QUANTITY, AND EXTENT OF ANY POTENTIAL CONTAMINATION SOURCES.

4. SITE LAYOUT AND FLAGGING.

- CONSTRUCTION AREAS TO BE CLEARLY FLAGGED PRIOR TO CONSTRUCTION.
- AREAS TO BE FLAGGED WILL INCLUDE:
 - SENSITIVE RESOURCE AREAS, SUCH AS AREAS BELOW ORDINARY HIGH WATER, SPAWNING AREAS, SPRINGS, AND WETLANDS;
 - EQUIPMENT ENTRY AND EXIT POINTS;
 - 3. ROAD AND STREAM CROSSING ALIGNMENTS:
 - 4. STAGING, STORAGE, AND STOCKPILE AREAS; AND
 - 5. NO-SPRAY AREAS AND BUFFERS.

5. TEMPORARY ACCESS ROADS AND PATHS.

- A. EXISTING ACCESS ROADS AND PATHS WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER AND LENGTH OF TEMPORARY ACCESS ROADS AND PATHS THROUGH RIPARIAN AREAS AND FLOODPLAINS WILL BE MINIMIZED.
- B. VEHICLE USE AND HUMAN ACTIVITIES, INCLUDING WALKING, IN AREAS OCCUPIED BY TERRESTRIAL ESA-LISTED SPECIES WILL BE MINIMIZED.
- C. TEMPORARY ACCESS ROADS AND PATHS WILL NOT BE BUILT ON SLOPES WHERE GRADE, SOIL, OR OTHER FEATURES SUGGEST A LIKELIHOOD OF EXCESSIVE EROSION OR FAILURE. IF SLOPES ARE STEEPER THAN 30%, THEN THE ROAD WILL BE DESIGNED BY A CIVIL ENGINEER WITH EXPERIENCE IN STEEP ROAD DESIGN.
- D. THE REMOVAL OF RIPARIAN VEGETATION DURING CONSTRUCTION OF TEMPORARY ACCESS ROADS WILL BE MINIMIZED. WHEN TEMPORARY VEGETATION REMOVAL IS REQUIRED, VEGETATION WILL BE CUT AT GROUND LEVEL (NOT GRUBBED).
- E. AT PROJECT COMPLETION, ALL TEMPORARY ACCESS ROADS AND PATHS WILL BE OBLITERATED, AND THE SOIL WILL BE STABILIZED AND REVEGETATED. ROAD AND PATH OBLITERATION REFERS TO THE MOST COMPREHENSIVE DEGREE OF DECOMMISSIONING AND INVOLVES DECOMPACTING THE SURFACE AND DITCH, PULLING THE FILL MATERIAL ONTO THE RUNNING SURFACE, AND RESHAPING TO MATCH THE ORIGINAL CONTOUR.
- F. HELICOPTER FLIGHT PATTERNS WILL BE ESTABLISHED IN ADVANCE AND LOCATED TO AVOID TERRESTRIAL ESA-LISTED SPECIES AND THEIR OCCUPIED HABITAT DURING SENSITIVE LIFE STAGES.

6. TEMPORARY STREAM CROSSINGS.

- A. EXISTING STREAM CROSSINGS OR BEDROCK WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER OF TEMPORARY STREAM CROSSINGS WILL BE MINIMIZED.
- TEMPORARY BRIDGES AND CULVERTS WILL BE INSTALLED TO ALLOW FOR EQUIPMENT AND VEHICLE CROSSING OVER PERENNIAL STREAMS DURING CONSTRUCTION. TREATED WOOD SHALL NOT BE USED ON TEMPORARY BRIDGE CROSSINGS OR IN LOCATIONS IN CONTACT WITH OR DIRECTLY OVER WATER.
- C. FOR PROJECTS THAT REQUIRE EQUIPMENT AND VEHICLES TO CROSS IN THE WET:
 - 1. THE LOCATION AND NUMBER OF ALL WET CROSSINGS SHALL BE APPROVED BY THE BPA EC LEAD AND DOCUMENTED IN THE CONSTRUCTION PLANS;
 - 2. VEHICLES AND MACHINERY SHALL CROSS STREAMS AT RIGHT ANGLES TO THE MAIN CHANNEL WHENEVER POSSIBLE;
 - NO STREAM CROSSINGS WILL OCCUR 300 FEET UPSTREAM OR 100 FEET DOWNSTREAM OF AN 3 EXISTING REDD OR SPAWNING FISH; AND
 - 4. AFTER PROJECT COMPLETION. TEMPORARY STREAM CROSSINGS WILL BE OBLITERATED AND BANKS RESTORED.

7. STAGING, STORAGE, AND STOCKPILE AREAS

- A. STAGING AREAS (USED FOR CONSTRUCTION EQUIPMENT STORAGE, VEHICLE STORAGE, FUELING, SERVICING, AND HAZARDOUS MATERIAL STORAGE) WILL BE 150 FEET OR MORE FROM ANY NATURAL WATER BODY OR WETLAND. STAGING AREAS CLOSER THAN 150 FEET WILL BE APPROVED BY THE EC I FAD
- B. NATURAL MATERIALS USED FOR IMPLEMENTATION OF AQUATIC RESTORATION, SUCH AS LARGE WOOD, GRAVEL, AND BOULDERS, MAY BE STAGED WITHIN 150 FEET IF CLEARLY INDICATED IN THE PLANS THAT AREA IS FOR NATURAL MATERIALS ONLY.
- C. ANY LARGE WOOD, TOPSOIL, AND NATIVE CHANNEL MATERIAL DISPLACED BY CONSTRUCTION WILL BE STOCKPILED FOR USE DURING SITE RESTORATION AT A SPECIFICALLY IDENTIFIED AND FLAGGED AREA.
- D. ANY MATERIAL NOT USED IN RESTORATION, AND NOT NATIVE TO THE FLOODPLAIN, WILL BE DISPOSED OF OUTSIDE THE 100-YEAR FLOODPLAIN.

8. EQUIPMENT.

- A. MECHANIZED EQUIPMENT AND VEHICLES WILL BE SELECTED, OPERATED, AND MAINTAINED IN A MANNER THAT MINIMIZES ADVERSE EFFECTS ON THE ENVIRONMENT (E.G., MINIMALLY-SIZED, LOW PRESSURE TIRES; MINIMAL HARD-TURN PATHS FOR TRACKED VEHICLES; TEMPORARY MATS OR PLATES WITHIN WET AREAS OR ON SENSITIVE SOILS).
- B. EQUIPMENT WILL BE STORED, FUELED, AND MAINTAINED IN AN CLEARLY IDENTIFIED STAGING AREA THAT MEETS STAGING AREA CONSERVATION MEASURES.

9. EROSION CONTROL

- **GEOSYNTHETIC FABRIC:**

- WILL BE REMOVED.
- WILL BE AVAILABLE AT THE WORK SITE:

10. DUST ABATEMENT.

- EROSION.
- D. APPLICATION OF DU AVOIDED DURING C AT STREAM CROSSI **RESULT IN UNFILTER** ABATEMENT MATER THESE WOULD BE A WATERBODY OR ST GREATER WHERE VE STEEP).
- E. SPILL CONTAINMEN DURING APPLICATION OF DU
- F. PETROLEUM-BASED FOR DUST ABATEME

loso				BPA	BPA	BPA	YAKAMA NATION FISHERIES		501 Portway Avenue, Suite 101	Valar	POST OFFICE BOX 151
G:\M-P\Nc	IO. BY	r DATE	REVISION DESCRIPTION	DRAWN BPA APPROVED	DESIGNED	CHECKED 200237 PROJECT	NASON CR. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT PHASE 2 30% DESIGN	interfluve	Hood River, OR 97031 541.386.9003 www.interfluve.com	Yakama Nation Fisheries	FORT ROAD FORT ROAD TOPPENISH, WA 98948 (509)865-5121

C. EQUIPMENT WILL BE REFUELED IN A VEHICLE STAGING AREA OR IN AN ISOLATED HARD ZONE. SUCH AS A PAVED PARKING LOT OR ADJACENT, ESTABLISHED ROAD (THIS MEASURE APPLIES ONLY TO GAS-POWERED EQUIPMENT WITH TANKS LARGER THAN 5 GALLONS).

D. BIODEGRADABLE LUBRICANTS AND FLUIDS WILL BE USED ON EQUIPMENT OPERATING IN AND ADJACENT TO THE STREAM CHANNEL AND LIVE WATER.

E. EQUIPMENT WILL BE INSPECTED DAILY FOR FLUID LEAKS BEFORE LEAVING THE VEHICLE STAGING AREA FOR OPERATION WITHIN 150 FEET OF ANY NATURAL WATER BODY OR WETLAND.

F. EQUIPMENT WILL BE THOROUGHLY CLEANED BEFORE OPERATION BELOW ORDINARY HIGH WATER, AND AS OFTEN AS NECESSARY DURING OPERATION, TO REMAIN GREASE FREE.

A. TEMPORARY EROSION CONTROL MEASURES INCLUDE:

1. TEMPORARY EROSION CONTROLS WILL BE IN PLACE BEFORE ANY SIGNIFICANT ALTERATION OF THE ACTION SITE AND APPROPRIATELY INSTALLED DOWNSLOPE OF PROJECT ACTIVITY WITHIN THE RIPARIAN BUFFER AREA UNTIL SITE REHABILITATION IS COMPLETE:

2. IF THERE IS A POTENTIAL FOR ERODED SEDIMENT TO ENTER THE STREAM, SEDIMENT BARRIERS WILL BE INSTALLED AND MAINTAINED FOR THE DURATION OF PROJECT IMPLEMENTATION;

3. TEMPORARY EROSION CONTROL MEASURES MAY INCLUDE SEDGE MATS, FIBER WATTLES, SILT FENCES, JUTE MATTING, WOOD FIBER MULCH AND SOIL BINDER, OR GEOTEXTILES AND

4. SOIL STABILIZATION UTILIZING WOOD FIBER MULCH AND TACKIFIER (HYDRO-APPLIED) MAY BE USED TO REDUCE EROSION OF BARE SOIL IF THE MATERIALS ARE NOXIOUS WEED FREE AND NONTOXIC TO AQUATIC AND TERRESTRIAL ANIMALS, SOIL MICROORGANISMS, AND VEGETATION;

5. SEDIMENT WILL BE REMOVED FROM EROSION CONTROLS ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE CONTROL; AND

6. ONCE THE SITE IS STABILIZED AFTER CONSTRUCTION, TEMPORARY EROSION CONTROL MEASURES

B. EMERGENCY EROSION CONTROLS. THE FOLLOWING MATERIALS FOR EMERGENCY EROSION CONTROL

1. A SUPPLY OF SEDIMENT CONTROL MATERIALS; AND

2. AN OIL-ABSORBING FLOATING BOOM WHENEVER SURFACE WATER IS PRESENT.

A. THE PROJECT SPONSOR WILL DETERMINE THE APPROPRIATE DUST CONTROL MEASURES BY CONSIDERING SOIL TYPE, EQUIPMENT USAGE, PREVAILING WIND DIRECTION, AND THE EFFECTS CAUSED BY OTHER EROSION AND SEDIMENT CONTROL MEASURES.

B. WORK WILL BE SEQUENCED AND SCHEDULED TO REDUCE EXPOSED BARE SOIL SUBJECT TO WIND

C. DUST-ABATEMENT ADDITIVES AND STABILIZATION CHEMICALS (TYPICALLY MAGNESIUM CHLORIDE, CALCIUM CHLORIDE SALTS, OR LIGNINSULFONATE) WILL NOT BE APPLIED WITHIN 25 FEET OF WATER OR A STREAM CHANNEL AND WILL BE APPLIED SO AS TO MINIMIZE THE LIKELIHOOD THAT THEY WILL ENTER STREAMS. APPLICATIONS OF LIGNINSULFONATE WILL BE LIMITED TO A MAXIMUM RATE OF 0.5 GALLONS PER SQUARE YARD OF ROAD SURFACE, ASSUMING MIXED 50:50 WITH WATER.

DR JUS NGS C RED D RIALS REAS REAM EGETA T EQU	BATEMENT CHEMICALS WILL BE ST BEFORE WET WEATHER, AND OR OTHER AREAS THAT COULD ELIVERY OF THE DUST TO A WATERBODY (TYPICALLY WITHIN 25 FEET OF A I CHANNEL; DISTANCES MAY BE ATION IS SPARSE OR SLOPES ARE JIPMENT WILL BE AVAILABLE BATEMENT CHEMICALS. DUCTS WILL NOT BE USED	Prelimin Not for Const	ary
	HIP IV GEN	FRAI	SHEET
51	CONSERVA		
48		-	3 OF 22
	MEASURES (2	I UF 3)	

PROJECT DESIGN AND SITE PREPARATION (CONTINUED).

11. SPILL PREVENTION, CONTROL, AND COUNTER MEASURES.

- A. A DESCRIPTION OF HAZARDOUS MATERIALS THAT WILL BE USED, INCLUDING INVENTORY, STORAGE, AND HANDLING PROCEDURES WILL BE AVAILABLE ON-SITE.
- B. WRITTEN PROCEDURES FOR NOTIFYING ENVIRONMENTAL RESPONSE AGENCIES WILL BE POSTED AT THE WORK SITE.
- C. SPILL CONTAINMENT KITS (INCLUDING INSTRUCTIONS FOR CLEANUP AND DISPOSAL) ADEQUATE FOR THE TYPES AND QUANTITY OF HAZARDOUS MATERIALS USED AT THE SITE WILL BE AVAILABLE AT THE WORK SITE.
- D. WORKERS WILL BE TRAINED IN SPILL CONTAINMENT PROCEDURES AND WILL BE INFORMED OF THE LOCATION OF SPILL CONTAINMENT KITS
- E. ANY WASTE LIQUIDS GENERATED AT THE STAGING AREAS WILL BE TEMPORARILY STORED UNDER AN IMPERVIOUS COVER, SUCH AS A TARPAULIN, UNTIL THEY CAN BE PROPERLY TRANSPORTED TO AND DISPOSED OF AT A FACILITY THAT IS APPROVED FOR RECEIPT OF HAZARDOUS MATERIALS.
- F. PUMPS USED ADJACENT TO WATER SHALL USE SPILL CONTAINMENT SYSTEMS.

12. INVASIVE SPECIES CONTROL

- A. PRIOR TO ENTERING THE SITE, ALL VEHICLES AND EQUIPMENT WILL BE POWER WASHED, ALLOWED TO FULLY DRY, AND INSPECTED TO MAKE SURE NO PLANTS, SOIL, OR OTHER ORGANIC MATERIAL ADHERES TO THE SURFACE.
- B. WATERCRAFT, WADERS, BOOTS, AND ANY OTHER GEAR TO BE USED IN OR NEAR WATER WILL BE INSPECTED FOR AQUATIC INVASIVE SPECIES.
- C. WADING BOOTS WITH FELT SOLES ARE NOT TO BE USED DUE TO THEIR PROPENSITY FOR AIDING IN THE TRANSFER OF INVASIVE SPECIES UNLESS DECONTAMINATION PROCEDURES HAVE BEEN APPROVED BY THE EC LEAD.

WORK AREA ISOLATION AND FISH SALVAGE.

1. WORK AREA ISOLATION.

- A. ANY WORK AREA WITHIN THE WETTED CHANNEL WILL BE ISOLATED FROM THE ACTIVE STREAM WHENEVER ESA-LISTED FISH ARE REASONABLY CERTAIN TO BE PRESENT, OR IF THE WORK AREA IS LESS THAN 300-FEET UPSTREAM FROM KNOWN SPAWNING HABITATS.
- B. WORK AREA ISOLATION AND FISH SALVAGE ACTIVITIES WILL COMPLY WITH THE IN-WATER WORK WINDOW.
- C. DESIGN PLANS WILL INCLUDE ALL ISOLATION ELEMENTS AND AREAS (COFFER DAMS, PUMPS, DISCHARGE AREAS, FISH SCREENS, FISH RELEASE AREAS, ETC.).
- D. WORK AREA ISOLATION AND FISH CAPTURE ACTIVITIES WILL OCCUR DURING PERIODS OF THE COOLEST AIR AND WATER TEMPERATURES POSSIBLE. NORMALLY EARLY IN THE MORNING VERSUS LATE IN THE DAY, AND DURING CONDITIONS APPROPRIATE TO MINIMIZE STRESS AND DEATH OF SPECIES PRESENT.

2. FISH SALVAGE.

- A. MONITORING AND RECORDING WILL TAKE PLACE FOR DURATION OF SALVAGE. THE SALVAGE REPORT 3. ELECTROFISHING. WILL BE COMMUNICATED TO AGENCIES VIA THE PROJECT COMPLETION FORM (PCF).
- B. SALVAGE ACTIVITIES SHOULD TAKE PLACE DURING CONDITIONS TO MINIMIZE STRESS TO FISH SPECIES, TYPICALLY PERIODS OF THE COOLEST AIR AND WATER TEMPERATURES WHICH OCCUR IN THE MORNING VERSUS LATE IN THE DAY.
- C. SALVAGE OPERATIONS WILL FOLLOW THE ORDERING, METHODS, AND CONSERVATION MEASURES SPECIFIED BELOW:
 - 1. SLOWLY REDUCE WATER FROM THE WORK AREA TO ALLOW SOME FISH TO LEAVE VOLITIONALLY.
- 2. BLOCK NETS WILL BE INSTALLED AT UPSTREAM AND DOWNSTREAM LOCATIONS AND MAINTAINED IN A SECURED POSITION TO EXCLUDE FISH FROM ENTERING THE PROJECT AREA.
- 3. BLOCK NETS WILL BE SECURED TO THE STREAM CHANNEL BED AND BANKS UNTIL FISH CAPTURE AND TRANSPORT ACTIVITIES ARE COMPLETE, BLOCK NETS MAY BE LEFT IN PLACE FOR THE DURATION OF THE PROJECT TO EXCLUDE FISH AS LONG AS PASSAGE REQUIREMENTS ARE MET.
- 4. NETS WILL BE MONITORED HOURLY DURING IN-STREAM DISTURBANCE.
- 5. IF BLOCK NETS REMAIN IN PLACE MORE THAN ONE DAY, THE NETS WILL BE MONITORED AT LEAST

DAILY TO ENSURE THEY ARE SECURED AND FREE OF ORGANIC ACCUMULATION. IF BULL TROUT ARE PRESENT, NETS ARE TO BE CHECKED EVERY 4 HOURS FOR FISH IMPINGEMENT.

- 6. CAPTURE FISH THROUGH SEINING AND RELOCATE TO STREAMS.
- 7. WHILE DEWATERING, ANY REMAINING FISH WILL BE COLLECTED BY HAND OR DIP NETS.
- 8. SEINES WITH A MESH SIZE TO ENSURE CAPTURE OF THE RESIDING ESA-LISTED FISH WILL BE USED.
- 9. MINNOW TRAPS WILL BE LEFT IN PLACE OVERNIGHT AND USED IN CONJUNCTION WITH SEINING.
- 10. ELECTROFISH TO CAPTURE AND RELOCATED FISH NOT CAUGHT DURING SEINING PER ELECTROFISH CONSERVATION MEASURES.
- 11. CONTINUE TO SLOWLY DEWATER STREAM REACH
- 12. COLLECT ANY REMAINING FISH IN COLD-WATER BUCKETS AND RELOCATED TO THE STREAM.
- 13. LIMIT THE TIME FISH ARE IN A TRANSPORT BUCKET.
- 14. MINIMIZE PREDATION BY TRANSPORTING COMPARABLE SIZES IN BUCKETS.
- 15. BUCKET WATER TO BE CHANGED EVERY 15 MINUTES OR AERATED.
- 16. BUCKETS WILL BE KEPT IN SHADED AREAS OR COVERED.
- 17. DEAD FISH WILL NOT BE STORED IN TRANSPORT BUCKETS, BUT WILL BE LEFT ON THE STREAM BANK TO AVOID MORTALITY COUNTING ERRORS.
- D. SALVAGE GUIDELINES FOR BULL TROUT, LAMPREY, MUSSELS, AND NATIVE FISH.
 - 1. CONDUCT SITE SURVEY TO ESTIMATE SALVAGE NUMBERS.
 - 2. PRE-SELECT SITE(S) FOR RELEASE AND/OR MUSSEL BED RELOCATION.
 - 3. SALVAGE OF BULL TROUT WILL NOT TAKE PLACE WHEN WATER TEMPERATURES EXCEED 15 DEGREES CELSIUS.
 - 4. IF DRAWDOWN LESS THAN 48 HOURS, SALVAGE OF LAMPREY AND MUSSELS MAY NOT BE NECESSARY IF TEMPERATURES SUPPORT SURVIVAL IN SEDIMENTS.
 - 5. SALVAGE MUSSELS BY HAND, LOCATING BY SNORKELING OR WADING.
 - SALVAGE LAMPREY BY ELECTROFISHING (SEE ELECTROFISHING FOR LARVAL LAMPREY SETTINGS 6. AND LARVAL LAMPREY DRY SHOCKING SETTINGS).
 - 7. SALVAGE BONY FISH AFTER LAMPREY WITH NETS OR ELECTROFISHING (SEE ELECTROFISHING FOR APPROPRIATE SETTINGS).
 - REGULARLY INSPECT DEWATERED SITE SINCE LAMPREY LIKELY TO EMERGE AFTER DEWATERING 8. AND MUSSELS MAY BECOME VISIBLE.
 - 9. MUSSELS MAY BE TRANSFERRED IN COOLERS.
 - 10. MUSSELS WILL BE PLACED INDIVIDUALLY TO ENSURE ABILITY TO BURROW INTO NEW HABITAT.

- A. INITIAL SITE SURVEY AND INITIAL SETTINGS.
 - 1. IDENTIFY SPAWNING ADULTS AND ACTIVE REDDS TO AVOID.
 - RECORD WATER TEMPERATURE. ELECTROFISHING WILL NOT OCCUR WHEN WATER 2 TEMPERATURES ARE ABOVE 18 DEGREES CELSIUS.
 - IF POSSIBLE, A BLOCK NET WILL BE PLACED DOWNSTREAM AND CHECKED REGULARLY TO CAPTURE 3. STUNNED FISH THAT DRIFT DOWNSTREAM.
 - 4. INITIAL SETTINGS WILL BE 100 VOLTS, PULSE WIDTH OF 500 MICRO SECONDS, AND PULSE RATE OF 30 HERTZ
 - RECORDS FOR CONDUCTIVITY, WATER TEMPERATURE, AIR TEMPERATURE, ELECTROFISHING 5. SETTINGS, ELECTROFISHER MODEL, ELECTROFISHER CALIBRATION, FISH CONDITIONS, FISH MORTALITIES, AND TOTAL CAPTURE RATES WILL BE INCLUDED IN THE SALVAGE LOG BOOK.
- B. ELECTROFISHING TECHNIQUE.
 - 1. SAMPLING WILL BEGIN USING STRAIGHT DC. POWER WILL REMAIN ON UNTIL THE FISH IS NETTED

NO. BY	Y D	DATE	REVISION DESCRIPTION	BPA DRAWN BPA APPROVED	BPA DESIGNED DATE	BPA CHECKED 200237 PROJECT	YAKAMA NATION FISHERIES Nason cr. r.m. 3.6-4.6 floodplain enhancement PHASE 2 30% DESIGN	interfluve	501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com	Yakama Nation Fisheries	POST OFFICE BOX : FORT ROAD TOPPENISH, WA 98 (509)865-5121
--------	-----	------	----------------------	---------------------------------	-------------------------	-------------------------------------	--	------------	---	-------------------------------	---

MAXIMUM LEVELS

- INCREASE.
- SEE THE BED OF THE STREAM).
- 9.
- C. SAMPLE PROCESSING.
 - WATER TRANSFERS, ETC.
- 4.
- D. BULL TROUT ELECTROFISHING.
- DEGREES CELSIUS
- E. LARVAL LAMPREY ELECTROFISHING.
 - SMITH-ROOT APEX BACKPACK.

- SECOND STAGE (O 4 IMMEDIATELY AFT PULSE SETTING OF
- 5 USE DIP NETS FOR MESH NET SWEEPS

WHEN USING STRAIGHT DC. GRADUALLY INCREASE VOLTAGE WHILE REMAINING BELOW

2. MAXIMUM VOLTAGE WILL BE 1100 VOLTS WHEN CONDUCTIVITY IS <100 MILLISECONDS, 800 VOLTS WHEN CONDUCTIVITY IS BETWEEN 100 AND 300 MILLISECONDS, AND 400 VOLTS WHEN CONDUCTIVITY IS >300 MILLISECONDS.

3. IF FISH CAPTURE IS NOT SUCCESSFUL USING STRAIGHT DC, THE ELECTROFISHER WILL BE SET TO INITIAL VOLTAGE FOR PDC. VOLTAGE, PULSE WIDTH, AND PULSE FREQUENCY WILL BE GRADUALLY INCREASED WITHIN MAXIMUM VALUES UNTIL CAPTURE IS SUCCESSFUL.

4. MAXIMUM PULSE WIDTH IS 5 MILLISECONDS. MAXIMUM PULSE RATE IS 70 HERTZ

5. ELECTROFISHING WILL NOT OCCUR IN ONE AREA FOR AN EXTENDED PERIOD.

6. THE ANODE WILL NOT INTENTIONALLY COME INTO CONTACT WITH FISH. THE ZONE FOR POTENTIAL INJURY OF 0.5 M FROM THE ANODE WILL BE AVOIDED.

7. SETTINGS WILL BE LOWERED IN SHALLOWER WATER SINCE VOLTAGE GRADIENTS LIKELY TO

8. ELECTROFISHING WILL NOT OCCUR IN TURBID WATER WHERE VISIBILITY IS POOR (I.E. UNABLE TO

OPERATIONS WILL IMMEDIATELY STOP IF MORTALITY OR OBVIOUS FISH INJURY IS OBSERVED. ELECTROFISHING SETTINGS WILL BE REEVALUATED.

1. FISH SHALL BE SORTED BY SIZE TO AVOID PREDATION DURING CONTAINMENT.

2. SAMPLERS WILL REGULARLY CHECK CONDITIONS OF FISH HOLDING CONTAINERS, AIR PUMPS,

3. FISH WILL BE OBSERVED FOR GENERAL CONDITIONS AND INJURIES

EACH FISH WILL BE COMPLETELY REVIVED BEFORE RELEASE. ESA-LISTED SPECIES WILL BE PRIORITIZED FOR SUCCESSFUL RELEASE.

1. ELECTROFISHING FOR BULL TROUT WILL ONLY OCCUR FROM MAY 1 TO JULY 31. NO ELECTROFISHING WILL OCCUR IN ANY BULL TROUT OCCUPIED HABITAT AFTER AUGUST 15. IN FMO HABITATS ELECTROFISHING MAY OCCUR ANY TIME.

2. ELECTROFISHING OF BULL TROUT WILL NOT OCCUR WHEN WATER TEMPERATURES EXCEED 15

PERMISSION FROM EC LEAD WILL BE OBTAINED IF LARVAL LAMPREY ELECTROFISHER IS NOT ONE OF FOLLOWING PRE-APPROVED MODELS: ABP-2 "WISCONSIN", SMITH-ROOT LR-24, OR

2. LARVAL LAMPREY SAMPLING WILL INCORPORATE 2-STAGE METHOD: "TICKLE" AND "STUN".

3. FIRST STAGE: USE 125 VOLT DC WITH A 25 PERCENT DUTY CYCLE APPLIED AT A SLOW RATE OF 3 PULSES PER SECOND. IF TEMPERATURES ARE BELOW 10 DEGREES CELSIUS. VOLTAGE MAY BE INCREASED GRADUALLY (NOT TO EXCEED 200 VOLTS). BURSTED PULSES (THREE SLOW AND ONE SKIPPED) RECOMMENDED TO INCREASE EMERGENCE.

ER LAI 30 PU VISIBL	AL FOR EXPERIENCED NETTERS): MPREY EMERGE, USE A FAST JLSES PER SECOND. .E LAMPREY. SIENES AND FINE BE USED IN POOR VISIBILITY.		
		Prelimin Not for Const	ary
51	HIP IV GEN		SHEET
48	CONSERVATION		4 OF 22
	MEASURES (2	2 OF 3)	

WORK AREA ISOLATION AND FISH SALVAGE (CONTINUED). D. THE PROJECT SPONSOR WILL RETAIN THE RIGHT OF REASONABLE ACCESS TO THE SITE TO MONITOR AND MAINTAIN THE SITE OVER THE LIFE OF THE PROJECT. SAMPLING WILL OCCUR SLOWLY (>60 SECONDS PER METER) STARTING AT UPSTREAM AND 6. WORKING DOWNSTREAM. 6. REVEGETATION. A. PLANTING AND SEEDING WILL OCCUR PRIOR TO OR AT THE BEGINNING OF THE FIRST GROWING MULTIPLE SWEEPS TO OCCUR WITH 15 MINUTES BETWEEN SWEEPS. 7. SEASON AFTER CONSTRUCTION. POST-DRAWDOWN "DRY-SHOCKING" WILL BE APPLIED IF LARVAL LAMPREY CONTINUE TO EMERGE 8 KEY). B. A MIX OF NATIVE SPECIES (INVASIVE SPECIES NOT ALLOWED) APPROPRIATE TO THE SITE WILL BE USED ANODES TO BE PLACED ONE METER APART TO SAMPLE ONE SQUARE METER AT A TIME FOR AT TO REESTABLISH VEGETATION, PROVIDE SHADE, AND REDUCE EROSION. REESTABLISHED VEGETATION LEAST 60 SECONDS. FOR TEMPERATURES LESS THAN 10 DEGREES CELSIUS, MAXIMUM VOLTAGE MAY SHOULD BE AT LEAST 70% OF PRE-PROJECT CONDITIONS WITHIN THREE YEARS. BE GRADUALLY INCREASED TO 400 VOLTS (DRY-SHOCKING ONLY). LOCATION POINT. C. VEGETATION SUCH AS WILLOWS, SEDGES, OR RUSH MATS WILL BE SALVAGED FROM DISTURBED OR DEWATERING. 1 ABANDONED AREAS TO BE REPLANTED. A. DEWATERING WILL OCCUR AT A RATE SLOW ENOUGH TO ALLOW SPECIES TO NATURALLY MIGRATE OUT D. SHORT-TERM STABILIZATION MEASURE MAY INCLUDE THE USE OF NON-NATIVE STERILE SEED MIX OF THE WORK AREA. (WHEN NATIVE NOT AVAILABLE), WEED-FREE CERTIFIED STRAW, OR OTHER SIMILAR TECHNIQUES. 3. B. WHERE A GRAVITY FEED DIVERSION IS NOT POSSIBLE, A PUMP MAY BE USED. PUMPS WILL BE E. SURFACE FERTILIZER WILL NOT BE APPLIED WITHIN 50 FEET OF ANY STREAM, WATE BODY, OR INSTALLED TO AVOID REPETIVE DEWATERING AND REWATERING. 4. WETLAND **OR COASTAL SCOUR** C. WHEN FISH ARE PRESENT, PUMPS WILL BE SCREENED IN ACCORDANCE WITH NMFS FISH SCREEN FENCING WILL BE INSTALLED AS NECESSARY TO PREVENT ACCESS TO REVEGETATED SITES BY LIVESTOCK C. TURBIDITY SHALL BE MEASURED (BACKGROUND LOCATION AND COMPLIANCE POINTS) EVERY 4 HOURS CRITERIA. NMFS ENGINEERING REVIEW AND APPROVAL WILL BE OBTAINED FOR PUMPS EXCEEDING 3 F. OR UNAUTHORIZED PERSONS CUBIC FEET PER SECOND. WHILE WORK IS BEING IMPLEMENTED. D. DISSIPATION OF FLOW ENERGY AT THE BYPASS OUTFLOW WILL BE PROVIDED TO PREVENT DAMAGE TO G. INVASIVE PLANTS WILL BE REMOVED OR CONTROLLED UNTIL NATIVE PLANT SPECIES ARE WELL ESTABLISHED (TYPICALLY THREE YEARS POST-CONSTRUCTION). THE STREAM CHANNEL AND RIPARIAN VEGETATION. E. SEEPAGE WATER WILL BE PUMPED TO A TEMPORARY STORAGE AND TREATMENT SITE OF INTO UPLAND 7. SITE ACCESS AND IMPLEMENTATION MONITORING. AREAS TO ALLOW WATER TO PERCOLATE THROUGH SOIL AND VEGETATION PRIOR TO REENTERING THE STREAM CHANNEL A. THE PROJECT SPONSOR WILL PROVIDE CONSTRUCTION MONITORING DURING IMPLEMENTATION TO ENSURE ALL CONSERVATION MEASURES ARE ADEQUATELY FOLLOWED, EFFECTS TO LISTED SPECIES ARE NOT GREATER THAN PREDICTED, AND INCIDENTAL TAKE LIMITATIONS ARE NOT EXCEEDED. CONSTRUCTION AND POST CONSTRUCTION CONSERVATION MEASURES. B. THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL SUBMIT THE PROJECT COMPLETION 1. FISH PASSAGE FORM (PCF) WITHIN 30 DAYS OF PROJECT COMPLETION. PROJECT COMPLETION FORM (PCF). A. FISH PASSAGE WILL BE PROVIDED FOR ADULT AND JUVENILE FISH LIKELY TO BE PRESENT DURING CONSTRUCTION UNLESS PASSAGE DID NOT EXIST BEFORE CONSTRUCTION. THE STREAM IS NATURALLY 8. CWA SECTION 401 WATER QUALITY CERTIFICATION. IMPASSABLE, OR PASSAGE WILL NEGATIVELY IMPACT ESA-LISTED SPECIES OR THEIR HABITAT. EC LEAD USING THE PROJECT COMPLETION FORM (PCF). A. THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL COMPLETE AND RECORD WATER B. FISH PASSAGE ALTERNATIVES WILL BE APPROVED BY THE BPA EC LEAD UNDER ADVISEMENT BY THE QUALITY OBSERVATIONS (SEE TURBIDITY MONITORING) TO ENSURE IN-WATER WORK IS NOT NMFS HABITAT BIOLOGIST. DEGRADING WATER QUALITY. 2 CONSTRUCTION AND DISCHARGE WATER B. DURING CONSTRUCTION, WATER QUALITY PROVISIONS PROVIDED BY THE OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY, WASHINGTON DEPARTMENT OF ECOLOGY, IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE FOLLOWED. A. SURFACE WATER MAY BE DIVERTED TO MEET CONSTRUCTION NEEDS ONLY IF DEVELOPED SOURCES ARE UNAVAILABLE OR INADEQUATE. STAGED REWATERING PLAN. B. DIVERSIONS WILL NOT EXCEED 10% OF THE AVAILABLE FLOW. A. WHEN REINTRODUCING WATER TO DEWATERED AREAS AND NEWLY CONSTRUCTED CHANNELS, A C. CONSTRUCTION DISCHARGE WATER WILL BE COLLECTED AND TREATED TO REMOVE DEBRIS, STAGED REWATERING PLAN WILL BE APPLIED. NUTRIENTS, SEDIMENT, PETROLEUM HYDROCARBONS, METALS, AND OTHER POLLUTANTS. B. THE FOLLOWING WILL BE APPLIED TO ALL REWATERING EFFORTS. COMPLEX REWATERING EFFORTS TIME AND EXTENT OF DISTURBANCE. MAY REQUIRE ADDITIONAL NOTES OR A DEDICATED SHEET IN THE CONSTRUCTION DETAILS. 3 A. EARTHWORK REQUIRING IN-STREAM MECHANIZED EQUIPMENT (INCLUDING DRILLING, EXCAVATION, TURBIDITY MONITORING PROTOCOL WILL BE APPLIED TO REWATERING EFFORTS. 1 DREDGING, FILLING, AND COMPACTING) WILL BE COMPLETED AS QUICKLY AS POSSIBLE. PRE-WASH THE AREA BEFORE REWATERING. TURBID WASH WATER WILL BE DETAINED AND PUMPED 2. TO THE FLOODPLAIN OR SEDIMENT CAPTURE AREAS RATHER THAN DISCHARGING TO FISH-BEARING B. MECHANIZED EQUIPMENT WILL WORK FROM TOP OF BANK UNLESS WORK FROM ANOTHER LOCATION WILL RESULT IN LESS HABITAT DISTURBANCE (TURBIDITY, VEGETATION DISTURBANCE, ETC.). STREAMS. CESSATION OF WORK INSTALL SEINE NETS AT UPSTREAM END TO PREVENT FISH FROM MOVING DOWNSTREAM UNTIL 2/3 3. OF TOTAL FLOW IS RESTORED TO THE CHANNEL. A. PROJECT OPERATIONS WILL CEASE WHEN HIGH FLOW CONDITIONS MAY RESULT IN INUNDATION OF THE PROJECT AREA (FLOOD EFFORTS TO DECREASE DAMAGES TO NATURAL RESOURCES PERMITTED). 4. STARTING IN EARLY MORNING INTRODUCE 1/3 OF NEW CHANNEL FLOW OVER PERIOD OF 1-2 HOURS. B. WATER QUALITY LEVELS EXCEEDED. SEE CWA SECTION 401 WATER QUALITY CERTIFICATION AND TURBIDITY MEASURES. 5. INTRODUCE SECOND THIRD OF FLOW OVER NEXT 1 TO 2 HOURS AND BEGIN FISH SALVAGE OF BYPASS CHANNEL IF FISH ARE PRESENT. 5. SITE RESTORATION. REMOVE UPSTREAM SEINE NETS ONCE 2/3 FLOW IN REWATERED CHANNEL AND DOWNSTREAM A. DISTURBED AREAS, STREAM BANKS, SOILS, AND VEGETATION WILL BE CLEANED UP AND RESTORED TO TURBIDITY IS WITHIN ACCEPTABLE RANGE (LESS THAN 40 NTU OR LESS THAN 10% BACKGROUND) IMPROVED OR PRE-PROJECT CONDITIONS. INTRODUCE FINAL THIRD OF FLOW ONCE FISH SALVAGE EFFORTS ARE COMPLETE AND 7. B. PROJECT-RELATED WASTE WILL BE REMOVED. DOWNSTREAM TURBIDITY VERIFIED TO BE WITHIN ACCEPTABLE RANGE. C. TEMPORARY ACCESS ROADS AND STAGING WILL BE DECOMPACTED AND RESTORED. SOILS WILL BE 8 INSTALL PLUG TO BLOCK FLOW INTO OLD CHANNEL OR BYPASS. REMOVE ANY REMAINING SEINE LOOSENED IF NEEDED FOR REVEGETATION OR WATER INFILTRATION. NETS. YAKAMA NATION FISHERIES BPA BPA BPA 501 Portway Avenue, Suite 101 Yakama POST OFFICE BOX 1 DRAWN DESIGNED CHECKED Hood River, OR 97031 FORT ROAD NASON CR. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT Nation 541.386.9003 TOPPENISH, WA 98 BPA 200237 Fisheries inter fluve www.interfluve.com (509)865-5121 PHASE 2 30% DESIGN

DAT

PROJECT

APPROVED

REVISION DESCRIPTIO

IN LAMPREY SYSTEMS, LAMPREY SALVAGE AND DRY SHOCKING MAY BE NECESSARY.

TURBIDITY MONITORING.

A. RECORD THE READING, LOCATION, AND TIME FOR THE BACKGROUND READING APPROXIMATELY 100 FEET UPSTREAM OF THE PROJECT AREA USING A RECENTLY CALIBRATED TURBIDIMETER OR VIA VISUAL OBSERVATION (SEE THE HIP HANDBOOK TURBIDITY MONITORING SECTION FOR A VISUAL OBSERVATION

RECORD THE TURBIDITY READING, LOCATION, AND TIME AT THE MEASUREMENT COMPLIANCE

50 FEET DOWNSTREAM FOR STREAMS LESS THAN 30 FEET WIDE.

100 FEET DOWNSTREAM FOR STREAMS BETWEEN 30 AND 100 FEET WIDE.

200 FEET DOWNSTREAM FOR STREAMS GREATER THAN 100 FEET WIDE.

300 FEET FROM THE DISCHARGE POINT OR NONPOINT SOURCE FOR LOCATIONS SUBJECT TO TIDAL


D. IF THERE IS A VISIBLE DIFFERENCE BETWEEN A COMPLIANCE POINT AND THE BACKGROUND, THE EXCEEDANCE WILL BE NOTED IN THE PROJECT COMPLETION FORM (PCF). ADJUSTMENTS OR CORRECTIVE MEASURES WILL BE TAKEN IN ORDER TO REDUCE TURBIDITY.

E. IF EXCEEDANCES OCCUR FOR MORE THAN TWO CONSECUTIVE MONITORING INTERVALS (AFTER 8 HOURS). THE ACTIVITY WILL STOP UNTIL THE TURBIDITY LEVEL RETURNS TO BACKGROUND. THE BPA EC LEAD WILL BE NOTIFIED OF ALL EXCEEDANCES AND CORRECTIVE ACTIONS AT PROJECT COMPLETION.


F. IF TURBIDITY CONTROLS (COFFER DAMS, WADDLES, FENCING, ETC.) ARE DETERMINED INEFFECTIVE, CREWS WILL BE MOBILIZED TO MODIFY AS NECESSARY. OCCURRENCES WILL BE DOCUMENTED IN THE

FINAL TURBIDITY READINGS, EXCEEDANCES, AND CONTROL FAILURES WILL BE SUBMITTED TO THE BPA

	Prelimin Not for Const	ary
51	HIP IV GENERAL	SHEET
948	CONSERVATION MEASURES (3 OF 3)	5 of 22



	Prelimin Not for Const	ary
(151 98948 1	TYPICAL DETAILS - EROSION CONTROL AND ENVIRONMENTAL PROTECCTION	SHEET 6 OF 22



COFFERDAM NOTES:

- TEMPORARY SHEET PILE AND PEA GRAVEL FILLED SAND BAGS ARE PRE-APPROVED METHODS OF ISOLATING CONSTRUCTION 1. WATER FROM THE WATERWAY.
- SHEETPILE COFFERDAM SHALL BE SEALED BY COVERING THE COFFERDAM WITH PLASTIC SHEETING HELD IN PLACE BY 2. STANDARD SANDBAGS PLACED IN ROWS AT THE TOE OF COFFERDAM. THE PLASTIC SHEETING SHALL BE DRAPED ALONG THE CHANNEL BOTTOM ON THE WORK AREA SIDE OF THE COFFERDAM WITH OUTWARD EDGE OF SHEETING MINIMUM 4-FEET FROM TOE OF COFFERDAM. MULTIPLE LAYERS OF SHEETING AND SANDBAGS MAY BE REQUIRED TO FORM A WATERTIGHT SEAL.
- 3. PLASTIC SHEETING SHALL BE MINIMUM 6-MIL THICKNESS. ROLL LENGTH SHALL BE LONG ENOUGH TO ENSURE THAT ENTIRE LENGTH OF COFFERDAM WILL BE COVERED WITHOUT A SEAM.
- CONTRACTOR SHALL PROVIDE PUMPING SUFFICIENT FOR A NET INFLOW TO THE WORK AREA, AND DISCHARGE TURBID WATER 4. TO UPLAND FLOODPLAIN.
- COFFERDAM AND ALL MATERIALS INCLUDING PLASTIC SHEETING, SAND BAGS AND PEA GRAVEL FILL. SHALL BE COMPLETELY 5. REMOVED FROM THE SITE AFTER CONSTRUCTION IS COMPLETED AND TURBIDITY HAS BEEN REMOVED.







POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 (509)865-5121




7 OF 22

SHEET


Preliminary

Not for Construction










































PROFILE - EXISTING ROAD PRISM, STA 29+00 - 19+00





PROFILE - EXISTING ROAD PRISM, STA 19+00 - 9+00



PROFILE - EXISTING ROAD PRISM, STA 9+00 - 0+00







OSD					CM	DM	DM
ž					DRAWN	DESIGNED	CHECKED
1					DM	05/30/2025	200237
Σ					APPROVED	DATE	PROJECT
6	NO.	BY	DATE	REVISION DESCRIPTION			

YAKAMA NATION FISHERIES NASON CR. R.M. 3.6-4.6 FLOODPLAIN ENHANCEMENT PHASE 2 30% DESIGN






POST OFFICE BOX 151 FORT ROAD TOPPENISH, WA 98948 (509)865-5121 Yakama Nation Fisheries


PROFILE - SIDE CHANNEL


SHEET 16^{of} 22

Preliminary Not for Construction





Creek Floodplain -	2 TYPICAL SECTION - F	ROAD REMOVAL/WETLAND TERRACE		
NO. BY DATE REVISION DESCRIPTION	CMDMDMDRAWNDESIGNEDCHECKEDDM05/30/2025200237APPROVEDDATEPROJECT	YAKAMA NATION FISHERIES Nason cr. r.m. 3.6-4.6 floodplain enhancement PHASE 2 30% DESIGN	501 Portway Avenue, Suite 101 Hood River, OR 97031 541.386.9003 www.interfluve.com	Yakama Nation Fisheries POST OFFICE BOX 151 FORT ROAD TOPFENISH, WA 98948 (509)865-5121







		Prelimit Not for Cons	hary truction
X 151 98948 21	CROSS SECT	CROSS SECTIONS	










VEL ALI END OF			
		Prelimir Not for Cons	truction
151 8948 L	LARGE WOOD TYPI (4 OF 5		SHEET 210F 22



Preliminary Not for Construction SHEET 22°F 22