

Questions from Wenatchee RM 2.2 Pre-bid Site Tour 4/29/2025

This project is in IFPL region 675. Per the Scope of Work Section 8, Contractor is responsible for all IFPL requirements, including meeting waiver requirements and waiver preparation if necessary. Please see the Scope of Work for further details.

Willow stakes for baffles will be provided. Contractor is responsible for moving from a storage location on-site and installing in the designed trenches. These are live plants and will need to be handled with care during transport and installation.

The selected construction contractor is only responsible for leaving disturbed areas ready for re-planting and decompacting surfaces that were compacted during construction and staging. All other requirements for re-planting the site (including straw and mulch delivery) will be handled by a separate contractor.

Tracked equipment is required for wet crossings. Wheeled equipment is not allowed to enter the active channel.

We do not anticipate any construction noise time limits. Weekend work is permitted if necessary.

This site requires archeological monitoring during construction. Yakama Nation archaeologists will be present for any ground-disturbing activities.

Item 007, the temporary access bridge (typical on sheet 11), can be substituted with a different method for crossing the side channel. One alternative could be a temporary culvert, at least 24 inch diameter. Any crossing would need to keep sediment and equipment out of the side channel and maintain fish passage throughout the project. The location of the crossing will need to be rehabilitated to the same condition as it was before being used as an access route. Please make clear what method you are proposing in your bid package.