

# **Contractor's Bid Package**

## **FOR**

### **White Creek Phase 3 Restoration Project**

### **Wood Harvest**

#### **Addendum 1**

#### **8/3/26**

**Except as specifically modified by this Addendum, all other terms, conditions, requirements, specifications, and provisions of the Request for Proposals (RFP) shall remain unchanged and in full force and effect.**

Section II - Contractor Responsibilities – the Contractor shall be responsible for preventing any fire resulting from its operations or activities. The Contractor shall always maintain appropriate fire prevention and suppression equipment on-site while work is being performed. The Contractor shall be solely responsible for any damage, repairs, restoration, or compensation resulting from fires or other impacts caused by the Contractor's operations, employees, or equipment.

Section IV - Minimum Equipment – strike sentence “Additionally, a self-loader log truck will be necessary to move logs from Glenwood to two landings.”

#### Section V – Specifications

- The IFPL zone for the harvesting operations is 609E, Not 680
- The access road shall be graded/bladed and brushed as specified prior to the commencement of tree harvesting and shall be left in equal or better condition upon completion of the project. Existing water bars and roadside ditches disturbed during grading/blading operations shall be restored and re-established as part of the Contractor's road maintenance activities.
- Material removed from the existing berm shall be used to construct barriers adjacent to the newly installed gate to prevent or discourage vehicles from bypassing (flanking) the gate.